

অসম চৰকাৰ



GOVERNMENT OF ASSAM
O/o-THE PROJECT DIRECTOR

ASSAM HEALTH INFRASTRUCTURE DEVELOPMENT AND MANAGEMENT SOCIETY
NAYANTARA SUPER MARKET COMPLEX, SIXMILE, GUWAHATI – 781022

Response to second set of Pre-Bid Queries

Project Name : Assam Health System Strengthening Project supported by JICA

JICA Loan No. : ID-P 302

Name of the Contract : Construction of Super-specialty Hospital Block and allied buildings within Lakhimpur Medical College, Fakhruddin Ali Ahmed Medical College - Barpeta and Silchar Medical College campus involving Civil, MEP Works, External Development Works (Package 1-1A).

IFB No: the Employer/JICA/SUPER SPECILATY TENDER/2025/ECF NO. 598510/01-A

Sl.No.	Reference Clause & Page No.	Tender Condition	Query / Clarification required by the bidder	Pre-bid Replies /Response by the Employer
1	General	Table 1: Summary of Milestones : The said Summary of Milestones have been given in Section 1-IX of the Tender Document.	Tender document states Completion Schedule of 30 Months for both the packages. Your goodself is aware that both packages contain three individual locations with variation in scope & site conditions. Looking in the scope & conditions, we realise that completion time of individual site may vary and it would be justified to consider individual site as an independent contract for Taking Over and issuance of Completion Certificate rather than linking all the sites together. We request you to consider Phase-wise/ Site-wise completion and taking over.	The Tender Conditions shall prevail.
2	General	Procedure of RA Bill : Package wise RA Bill system mentioned in Tender document	We request to consider site-wise submission & release of RA Bills in place of Package wise to ensure good work progress and healthy cash flow of individual sites.	The Tender Conditions shall prevail.
3	General	Type of Cement (OPC/PPC/PSC) to be used for construction has not been specified in the Tender document /BOQ properly.	We request to clarify type of Cement viz. OPC,PPC or PSC to be used for Concrete & other Architectural Works.	Refer sl no.50 of the Responses to 1st set of Pre-bid queries published on 04/02/2025
4	General	Green Building Norms: Nothing has been mentioned in the Bid Document	Kindly clarify if the said project is planned for any GRIHA rating.	GRIHA ratings not to be considered.
5	Section IV, Annexure -1, BOQ	Item No. 6.38 , 6.47 : Providing and laying autoclaved aerated cement blocks masonry -----	Normal Cement Plaster items have been given in the BOQ. Kindly verify the suitability of Cement Plaster on AAC Block surface. As per our experience, cracks will appear on normal cement plastered surface if applied on AAC block. May please be clarified.	Refer SI no. 1, Corrigendum-2 dated 07/02/2025 Updated Annexure-1 Bill of Quantities (Excel format). In the revised BOQ, refer sl no. 148,166
6	Section VI, Works Requirements , Annexure-2 : Technical Specifications	LIST OF PREFERRED MAKE / MANUFACTURERS FOR DIFFERENT MATERIALS TO BE USED FOR CIVIL WORKS Sl. No.48 Page 134 AAC Block : Superlite, Ultralyte, Genex & Equivalent	We request to include BrikOLite in the make list. This manufacturer is also Assam based and supplying material to several ongoing projects in the state.	Refer Annexure-C(List Of approved make list),Corrigendum No.1 Dated 30/01/2025. Please note, the make list given as Annexure-C under Corrigendum no. 1 shall supersede any other makes mentioned elsewhere in the Bid Document.

Sl.No.	Reference Clause & Page No.	Tender Condition	Query / Clarification required by the bidder	Pre-bid Replies /Response by the Employer
7	Section IV_ Annexure 1 _ P1 - 1A BOQ Sub Head 34 : Fire Alarm and Decton System Item SI No. 652	Supplying, installation, testing and commissioning of micro processor based intelligent addressable main fire alarm panel, central processing unit with the following loop modules and capable of supporting not less than 240 devices (including detectors) and minimum 120 detectors per loop and loop length up to 2 km, network communication card, minimum 320 character graphics/ LCD display with touch screen or other keypad and minimum 4000 events history log in the non volatile memory (EPROM), power supply unit (230 ± 5% V, 50 hz), 48 hrs back-up with 24 volt sealed maintenance free batteries with automatic charger. The panel shall have facility to connect printer to printout log and facility to have seamless integration with analog/digital voice evacuation system (which is part of the schedule of work under SH: PA System) and shall be complete with all accessories . The panel shall be compatible for IBMS system with open protocol BACnet/ Modbus over IP complete as per specifications.	As a genral practice kindly accept for 24hrs battery backup with 30 min alarm condition.	BOQ descriptions as given in the BOQ shall remain unchanged.
8	Section IV_ Annexure 1 _ P1 - 1A BOQ Sub Head 39 : Air cooled Chiller Item SI No. 687-689 ANNEXURE - 2 SECTION VI : WORKS REQUIREMENT SPECIFICATIONS Page No. 525 of 700	Ambiant Condition :DB temp. 90 deg F and WB temp. 78 Deg F, <u>3.0 Air Cooled Condenser</u> 3.3 Air Entry temperature -- 45 Deg Centigrade	We understand that the BOQ Clause shall prevail. i.e. Ambiant Condition shall be : DB temp. 90 deg F and WB temp. 78 Deg F. --- Kindly Confirm	Yes. BOQ clause shall prevail. BOQ descriptions as given in the BOQ shall remain unchanged.
9	Section IV_ Annexure 1 _ P1 - 1A BOQ Bill No. : 5 , HVAC Works Item SI No. 687-899		It was noted and understood from the BOQ for HVAC System, that supply of VFD-s are not in scope for this tender / project. ----kindly confirm.	The Supply of VFD's are not in the scope of this HVAC tender Bill of Quantities
10	Section IV_ Annexure 1 _ P1 - 1A BOQ Item SI No. 908	625 KVA DG set with suitable capacity of Day Oil Tank describe as above	From the Manufacturers , it was noted that no DG sets of rating 625 KVA are manufactured. Available Nearest Rating shall be 650 KVA. Hence, we request to amend the capacity of DG sets in BOQ.	Refer SI no. 1, Corrigendum-2 dated 07/02/2025 Updated Annexure-1 Bill of Quantities (Excel format). In the revised BOQ, refer sl no. 908, 909,914
11	Section IV_ Annexure 1 _ P1 - 1A BOQ Public Address System Item SI No. 1182-1209	SITC of Cable Tray of Bends , Tee-s, Cross Membars & Reducers ---- UOM-s are mentioned in Metre.	We understand that Units of Cable Tray Bends, Tee-s , Cross Membars and Reducers shall be "Nos" of "Each" instaed of Metre.--- Kindly confirm.	Refer SI no. 1, Corrigendum-2 dated 07/02/2025 Updated Annexure-1 Bill of Quantities (Excel format). In the revised BOQ, refer sl no. 1182-1209.
12	Section IV_ Annexure 1 _ P1 - 1A BOQ Public Address System Item SI No. 1222	Supply,Installation, Testing & Commissioning of 8 zone IP based, digital Voice Alarm controller expandable upto 128 zones. The voice alarm controller should be able to connect directly over Ethernet. It should have functions like the audio playing, zone control, fault monitoring, log recording, volume control and amplifier switchover. The Voice alarm controller should also have the following functions: . 255 Priorities . Time schedule broadcasts . Its own PTT microphone . Capable of amplifier redundancy	We request your goodself to kindly review the requirement of 3 nos of controllers for each hospital block and confirm.	BOQ descriptions as given in the BOQ shall remain unchanged.

Sl.No.	Reference Clause & Page No.	Tender Condition	Query / Clarification required by the bidder	Pre-bid Replies /Response by the Employer																																																								
13	Section IV_ Annexure 1 _ P1 - 1A BOQ Public Address System Item SI No. 1223	Supply,Installation, Testing & Commissioning of IP based Networkable touch screen paging station for selection of zones, supervision of system status, setting of scheduled broadcasts with the following functions: . Built-in monitoring loudspeaker . Detachable goose-neck microphone LCD touchscreen display	Kindly accept for keypad based paging station.	BOQ descriptions as given in the BOQ shall remain unchanged.																																																								
14	Section IV_ Annexure 1 _ P1 - 1A BOQ Public Address System Item SI No. 1224 & 1225	SITC of 1x250W Class-D Amplifier with 4 independent channels --- 2 Nos SITC of 1x500W Class-D Amplifier with 4 independent channels --- 3 Nos	It was noted from the approved manufacturers that the combination of either 1X250W or 1X500W or both of Class D Amplifiers are not available with most of them. Kindly advise.	Refer SI no. 1, Corrigendum-2 dated 07/02/2025 Updated Annexure-1 Bill of Quantities (Excel format). In the revised BOQ, refer sl no. 1224-1225.																																																								
15	Section IV_ Annexure 1 _ P1 - 1A BOQ Public Address System Item SI No. 1270	13 Passenger (1632 Kg) Gearless without Machine Room having speed of 1 MPS - (G+5) - Passanger Lift	We understand that the Capacity shall be 884 Kgs in place of 1632 Kgs for 13 Passenger Lifts. --- Kindly confirm.	Refer SI no. 1, Corrigendum-2 dated 07/02/2025 Updated Annexure-1 Bill of Quantities (Excel format). In the revised BOQ, refer sl no. 1270.																																																								
16	Section IV_ Annexure 1 _ P1 - 1A BOQ Item SI No. 1336-1337	<table border="1"> <tr> <td colspan="7">CAMC (Comprehensive Annual Maintenance Contract)</td> </tr> <tr> <td colspan="7">Comprehensive Maintenance of the complete Medical Gas Pipeline System installation for 5 years after completion of Defect Liability Period / Warranty Period of Five Years as per terms and conditions of comprehensive maintenance described in the NTT as per following.</td> </tr> <tr> <td colspan="7">The Comprehensive Maintenance of MGPS Installation includes complete MGPS Installation, Labour, Spares, all consumables etc. as required including the following:</td> </tr> <tr> <td colspan="7">a) All MGPS Equipments in the NTT.</td> </tr> <tr> <td colspan="7">b) Preventive Maintenance including Testing & Calibration as per Technical / Service / Operational Manual of the Manufacturer.</td> </tr> <tr> <td colspan="7">c) MGPS Installation inside the MGPS Plant Room</td> </tr> <tr> <td>1336</td> <td>1st Year</td> <td>nos.</td> <td>1</td> <td>1</td> <td>1</td> <td>3.00</td> </tr> <tr> <td>1337</td> <td>2nd Year</td> <td>nos.</td> <td>1</td> <td>1</td> <td>1</td> <td>3.00</td> </tr> </table>	CAMC (Comprehensive Annual Maintenance Contract)							Comprehensive Maintenance of the complete Medical Gas Pipeline System installation for 5 years after completion of Defect Liability Period / Warranty Period of Five Years as per terms and conditions of comprehensive maintenance described in the NTT as per following.							The Comprehensive Maintenance of MGPS Installation includes complete MGPS Installation, Labour, Spares, all consumables etc. as required including the following:							a) All MGPS Equipments in the NTT.							b) Preventive Maintenance including Testing & Calibration as per Technical / Service / Operational Manual of the Manufacturer.							c) MGPS Installation inside the MGPS Plant Room							1336	1st Year	nos.	1	1	1	3.00	1337	2nd Year	nos.	1	1	1	3.00	The Description of the Item for CAMC for Medical Gas Pipeline System calls for comprehensive contract for a period of 5 years. However, the BOQ SI No. 1366 & 1367 ask for Comprehensive Maintenance for two years only. We understand that CAMC for 2 years only will be executed for MGPS under this contract. ----- Kindly confirm.	yes. The CAMC for MGPS shall be for 2 years. Refer SI No.1336,1337 of the revised BOQ.
CAMC (Comprehensive Annual Maintenance Contract)																																																												
Comprehensive Maintenance of the complete Medical Gas Pipeline System installation for 5 years after completion of Defect Liability Period / Warranty Period of Five Years as per terms and conditions of comprehensive maintenance described in the NTT as per following.																																																												
The Comprehensive Maintenance of MGPS Installation includes complete MGPS Installation, Labour, Spares, all consumables etc. as required including the following:																																																												
a) All MGPS Equipments in the NTT.																																																												
b) Preventive Maintenance including Testing & Calibration as per Technical / Service / Operational Manual of the Manufacturer.																																																												
c) MGPS Installation inside the MGPS Plant Room																																																												
1336	1st Year	nos.	1	1	1	3.00																																																						
1337	2nd Year	nos.	1	1	1	3.00																																																						
17	General	Approved Make List	For some items , it was noted that makes mentioned in BOQ and Approved Make List are not similar. We understand that makes mentioned in both BOQ and Make Lists can be considered	Refer Response given against sl no. 6 above.																																																								
18	ANNEXURE - 2 SECTION VI : WORKS REQUIREMENT SPECIFICATIONS Page No. 290	<u>Intelligent Multi Criteria Acclimating Detector</u> The detector design shall allow a wide sensitivity window, no less than 1 to 4% per foot obscuration	Kindly accept for sensitivity level UL268 3.52-4.17% / ft obs. As per the UL requirement.	BOQ descriptions as given in the BOQ shall remain unchanged.																																																								
19	ANNEXURE - 2 SECTION VI : WORKS REQUIREMENT SPECIFICATIONS Page No. 518-522	Electrical Make List. List of Makes for Lifts.	No list of Makes for Lifts are mentioned in the list. We propose Kone , OTIS , Johnson . Please confirm.	Please refer Annexure C (List Of approved make list),Corrigendum No.1 Dated-30/01/2025																																																								
20	ANNEXURE - 2 SECTION VI : WORKS REQUIREMENT SPECIFICATIONS Page No. 577-579	HVAC Make List. List of Makes for Chillers.	No List of Makes for Chillers are mentioned in the list. We propose Daikin , Kirloskar , Blue Star , Voltas and Dunham Bush . Please Confirm.	Refer SI no. 2, Corrigendum No.2 Dated 07/02/2025																																																								

Sl.No.	Reference Clause & Page No.	Tender Condition	Query / Clarification required by the bidder	Pre-bid Replies /Response by the Employer
21	ANNEXURE - 2 SECTION VI : WORKS REQUIREMENT SPECIFICATIONS	<u>7.1 MEDICAL GAS PIPELINE SYSTEM (MGPS)</u> All the items Shall be European CE Certified with 4 digit notified body number or American ETL/ American UL listed <u>MAKE IN INDIA POLICY</u>	It was noted from the approved manufacturers (Indian Only) and their products are not European CE Certified with 4 digit notified body number or American ETL/ American UL listed.	Since the bidding has been invited as ICB following JICA SBD,the specification clause shall prevail.
22	Page No. 582 - 614 Page no. 614	The MGPS work shall fully comply to Public Procurement (preference to make in India).	We also request to add some more Indian Makes in the list like M/s MDD , M/s Medfreshe , M/s PES & M/s SITA Medicare etc.	Refer SI no. 3, Corrigendum No.2 Dated 07/02/2025
23	ANNEXURE - 2 SECTION VI : WORKS REQUIREMENT SPECIFICATIONS Page No. 629	<u>LIST OF APPROVED MAKES FOR NURSE CALL SYSTEM</u> ZKR / AMBA / HELIX	As understand from M/s HELIX, they are not dealing with Nurse Call System. We request you to include M/s MDD , M/s Medfreshe & M/s PES Installations in the list.	Refer SI no. 4, Corrigendum No.2 Dated 07/02/2025

অসম চৰকাৰ



GOVERNMENT OF ASSAM

GOVERNMENT OF ASSAM
O/o-THE PROJECT DIRECTOR

ASSAM HEALTH INFRASTRUCTURE DEVELOPMENT AND MANAGEMENT SOCIETY
NAYANTARA SUPER MARKET COMPLEX, SIXMILE, GUWAHATI – 781022

Corrigendum No.2

Date : 07/02/2025

Project Name : Assam Health System Strengthening Project supported by JICA

JICA Loan No. : ID-P 302

Name of the Contract : Construction of Super-specialty Hospital Block and allied buildings within Lakhimpur Medical College, Fakhruddin Ali Ahmed Medical College - Barpeta and Silchar Medical College campus involving Civil, MEP Works, External Development Works (**Package 1-1A**).

IFB No: AHIDMS/JICA/SUPER SPECILATY TENDER/2025/ECF NO. 598510/01-A

Sl.No.	Reference Clause	Page No.	Instead of	Now read as
1	Section IV. Bidding Forms Annexure-1 Bill of Quantities	BF-10	Updated Annexure-1 Bill of Quantities (Excel format) enclosed to this document as Annexure-A under Corrigendum-1	Updated Annexure-1 Bill of Quantities (Excel format) enclosed to this document as Annexure-A under Corrigendum-2
2	Annexure C (List Of approved make list),Corrigendum No.1 Dated-30/01/2025	NA	Air Cooled Chiller- Makes missing Motor For AHU Fan- Makes missing Motor for Ventilation Fan- Makes missing Pan humidifier/ Strip Heater- Makes missing	Makes approved- Air Cooled Chiller- Kirloskar / Blue star / Voltas / Daikin / York / Trane Dunham Bush or equivalent Motor For AHU Fan- Seimens / ABB/ Crompton or equivalent Motor for Ventilation Fan- Seimens / ABB/ Crompton or equivalent Pan humidifier/ Strip Heater- KEPL / Rapidcool/ Emerald/ Danfoss/ Siemens or equivalent Any missing item- Prior permission is required from Employer.
3	Annexure C (List Of approved make list),Corrigendum No.1 Dated-30/01/2025	pdf 27	LIST OF APPROVED MAKES FOR MEDICAL GAS PIPELINE SYSTEM- attached under Annexure C (List Of approved make list), Corrigendum No.1 Dated-30/01/2025	LIST OF REVISED APPROVED MAKES FOR MEDICAL GAS PIPELINE SYSTEM- attached as Annexure B as Corrigendum No.2 Dated-07/02/2025
4	Annexure C (List Of approved make list),Corrigendum No.1 Dated-30/01/2025		LIST OF APPROVED MAKES FOR NURSE CALL SYSTEM- attached under Annexure C (List Of approved make list),Corrigendum No.1 Dated-30/01/2025 ZKR / AMBA MEDI NEX / HELIX / NIPPON ENGINEERING COMPANY/ CAREWELL / RELISON OR EQUIVALENT	Revised Approved Makes for Nurse call System- ZKR / AMBA MEDI NEX / NIPPON ENGINEERING COMPANY/ CAREWELL/ RELISON / MPS/ MDD/ MEDFRESHE OR EQUIVALENT

Project Name : Assam Health System Strengthening Project supported by JICA
JICA Loan No. : ID-P 302
Name of the Contract : Construction of Super-specialty Hospital Block and allied buildings within Lakhimpur Medical College, Fakhruddin Ali Ahmed Medical College - Barpeta and Silchar Medical College campus involving Civil, MEP Works, External Development Works.
IFB No:
A.Preamble
<p>1. The Bill of Quantities shall be read in conjunction with the General and Particular Conditions of Contract, Specification, and Drawings.</p> <p>2. The quantities given in the Bill of Quantities are estimated and provisional, and are given to provide a common basis for bidding. The payment shall be made based on the actual quantities of the work executed in accordance with the Contract.</p> <p>3. The rates and prices in the priced Bill of Quantities shall, except insofar as it is otherwise provided under the Contract, include all costs for construction plant, labour, supervision, materials, erection, maintenance, insurance, profit, taxes, and duties, together with all general risks, liabilities, and obligations set out or implied in the Contract.</p> <p>4. A rate or price shall be entered against each item in the Bill of Quantities, irrespective of whether quantities are stated or not. Items against which no rate or price is entered in the priced Bill of Quantities shall be deemed to be covered by the rates or prices entered for other items therein, and will not be paid for separately.</p> <p>5. The whole cost of complying with the provisions of the Contract shall be included in the items provided in the priced Bill of Quantities, and where no items are provided, the cost shall be deemed to be included in the rates or prices entered for the related items of work.</p> <p>6. General requirements, directions and/or descriptions of work and materials are not necessarily repeated or summarized in the Bill of Quantities. Relevant sections of the Contract documents shall be referred before entering prices against each item in the priced Bill of Quantities.</p> <p>7. Provisional Sums included and so designated in the Bill of Quantities shall be expended in whole or in part at the direction and discretion of the Engineer in accordance with Sub-Clause 13.5 or Sub-Clause 13.6 of the General Conditions of Contract, as applicable. Notwithstanding the above, the Provisional Sum for the cost of the DB shall require no prior instruction of the Engineer.</p> <p>8. No Contractor's overhead charges or profit shall be included or payable on the Provisional Sum for the cost of the DB.</p> <p>9. The method of measurement of completed work for payment shall be in accordance with IS 1200 (All parts) and CPWD specifications as applicable.</p> <p>10. Any unit rates and/or prices quoted in the Bill of Quantities in: (a) Indian Rupees (INR), there shall be no decimal places below zero. (b) Japanese Yen (JPY), there shall be no decimal places below zero. (c) United States Dollar (USD), there shall be two decimal places below zero. Any price(s) resulting from computations (such as unit price multiplied by quantity) shall be rounded down to the nearest decimal place(s) as indicated for each relevant currency above.</p> <p>11. All rates quoted for individual items shall be excluding GST. GST shall be added separately and payable at prevailing rates over and above the quoted rate as indicated in the Price Bid.</p> <p>12. Where there are any items of work provided in the Bills of Quantities for complying with requirements of sub-clauses 6.1 through 6.24 of the General Conditions of Contract, payment for such items are made only by monthly instalments upon the Contractor's compliance with all contract requirement with respect of that item, for each month, to the satisfaction of the Engineer.</p> <p>13. The Engineer shall have power (i) to make alteration in, omissions from, additions to, or substitutions for the original specifications, drawings, designs and instructions that may appear to him to be necessary or advisable during the progress of the work, and (ii) to omit a part of the works in case of non-availability of a portion of the site or for any other reasons and the contractor shall be bound to carry out the works in accordance with any instructions given to him in writing signed by the Engineer and such alterations, omissions, additions or substitutions shall form part of the contract as if originally provided therein and any altered, additional or substituted work which the contractor may be directed to do in the manner specified above as part of the works, shall be carried out by the contractor on the same conditions in all respects including price on which he agreed to do the main work</p> <p>14. Notwithstanding anything stated anywhere in the bid documents / contract, the rate to be quoted by the bidder shall be deemed to include overheads, profits, labour cess, ESIC, health insurance, PF, cost index and any other such items not specifically stated. However, the quoted rate for each item is excluding GST.</p> <p>15. The Contractor shall make all arrangements for ground breaking ceremony/ Inaugural function etc . for the project as required and the cost towards it deemed to be included in his rates/offer.</p>

Project Name : Assam Health System Strengthening Project supported by JICA

JICA Loan No. : ID-P 302

Name of the Contract : Construction of Super-specialty Hospital Block and allied buildings within Lakhimpur Medical College, Fakhruddin Ali Ahmed Medical College - Barpeta and Silchar Medical College campus involving Civil, MEP Works, External Development Works.

IFB No:

GRAND SUMMARY

Description	Amount		
	INR	JPY	USD
Facility No-1 Super Speciality Hospital at Silchar (SMCH)	-	-	-
Facility No-2 Super Speciality Hospital at Barpeta (FAAMCH)	-	-	-
Facility No-3 Super Speciality Hospital at Lakhimpur (LMCH)	-	-	-
(A) Total (SMCH+FAAMCH+LMCH)	-	-	-
(B) Specified Provisional Sums	19,109,250.00	-	-
(C) Total (A+B)	19,109,250.00	-	-
(D) Add contingency allowance (20%)	3,821,850.00	-	-
(E) Bid Price (C+D) [carried forward to Letter of Price Bid]	22,931,100.00	-	-
Note:The Employer shall add GST @ 18% during the contract signing			

Project Name : Assam Health System Strengthening Project supported by JICA				
JICA Loan No. : ID-P 302				
Name of the Contract : Construction of Super-specialty Hospital Block and allied buildings within Lakhimpur Medical College, Fakhruddin Ali Ahmed Medical College - Barpeta and Silchar Medical College campus involving Civil, MEP Works, External Development Works.				
IFB No:				
Specified Provisional Sums				
SI No	Description	Amount		
		INR	JPY	USD
1	Cost of Dispute Board (DB)	19,109,250.00		
	Total Specified Provisional Sums	19,109,250.00	-	-

Notes for the Bidders

- 1 Provisional Sums included and designated above shall be expended in whole or in part at the direction of the Engineer and in accordance with Sub-Clause 13.5 of the General Conditions. Notwithstanding the above, the Provisional Sum for the cost of the DB shall require no prior instruction of the Engineer.
- 2 No Contractor's overhead charges or profit shall be included or payable on the Provisional Sum for the Cost of the DB.

Project Name : Assam Health System Strengthening Project supported by JICA																					
JICA Loan no : ID-P 302																					
Name of the Contract : Construction of Super-specialty Hospital Block and allied buildings within Lakhimpur Medical College, Fakhruddin Ali Ahmed Medical College - Barpeta and Silchar Medical College campus involving Civil, MEP Works, External Development Works.																					
IFB no:																					
SL. no	Description of Item	Unit	Quantity				Rate			Amount											
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total		
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)
4	5	6	7=4+5+6	8.00	9.00	10.00	11=4x8	12=4x9	13=4x10	14=5x8	15=5x9	16=5x10	17=6x8	18=6x9	19=6x10	20=11+14+17	21=12+15+18	22=13+16+19			
1	2	3	4	5	6	7=4+5+6	8.00	9.00	10.00	11=4x8	12=4x9	13=4x10	14=5x8	15=5x9	16=5x10	17=6x8	18=6x9	19=6x10	20=11+14+17	21=12+15+18	22=13+16+19
I	Pre construction Work- Salvage/Tree cutting																				
I-1	Credit for demolition of building structures etc. complete and taking away all fetched material out of campus within 30 days after completing demolition part except the C&D waste kept for recycling and used the recycle product product for non structural work such as in foot path, manhole, lean concrete , filling under plinth re-filling of oundation etc. or as approved by Engineer-in-charge complete in all respect. The serviceable material received from dismantling/demolishing to be kept with executing agency and take away from the site as per direction of engineer-in-charge . Note : This amount to be paid by agency to the department. Quote the lump sum amount (in minus)	Job	-1	0	-1	-2.00				-	-	-	-	-	-	-	-	-	-	-	-
I-2	Felling trees of the girth (measured at a height of 1 m above ground level), including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material.	Nos	219	14	32	265.00				-	-	-	-	-	-	-	-	-	-	-	-
	Sub Head 1 : Earth Work & Carriage of Materials																				
	Carriage of material by mechanical transport including loading, unloading and stacking																				
	Earth																				
1	Up to 5 km.	cum	36658.00	1196.00	10.00	37864.00				-	-	-	-	-	-	-	-	-	-	-	-
2	5km to 10 km	cum	40289.42	4612.00	2812.60	47714.02				-	-	-	-	-	-	-	-	-	-	-	-
3	10km to 20km	cum	3631.42	4612.00	2802.60	11046.02				-	-	-	-	-	-	-	-	-	-	-	-
4	Disposal of moorum/building rubbish/ malba/ similar unserviceable, dismantled or waste material by mechanical transport including loading, transporting, unloading to approved municipal dumping ground for lead upto 10 km for all lifts, complete as per directions of Engineer-in-charge.	cum	8586.00	25320.00	24815.00	58721.00				-	-	-	-	-	-	-	-	-	-	-	-
5	Banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller, or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up, in embankments for roads, flood banks, marginal banks, and guide banks etc., lead upto 50 m and lift upto 1.5 m :																				
5	All kinds of soil	cum	1825.00	10472.00	5460.00	17757.00				-	-	-	-	-	-	-	-	-	-	-	-
6	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.																				
6	All kinds of soil	cum	6298.94	13756.40	25473.76	45529.10				-	-	-	-	-	-	-	-	-	-	-	-
7	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.																				
7	All kinds of soil	cum	1114.20	537.20	1114.20	2765.61				-	-	-	-	-	-	-	-	-	-	-	-
8	Close timbering in case of shafts, wells, cesspits, manholes and the like including strutting, shoring and packing cavities (wherever required) etc. complete. (Measurements to be taken of the face area timbered).																				
8	Depth not exceeding 1.5 m	sqm	145.98	119.58	145.98	411.53				-	-	-	-	-	-	-	-	-	-	-	-
9	Depth exceeding 1.5 m but not exceeding 3 m	sqm	94.98	68.58	94.98	258.53				-	-	-	-	-	-	-	-	-	-	-	-
10	Depth exceeding 3 m but not exceeding 4.5 m	sqm	63.61	50.50	63.61	177.71				-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
11	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	cum	8113.78	7218.00	17306.00	32637.78				-	-	-	-	-	-	-	-	-	-	-	-	-	-
12	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete	cum	38057.58	4153.29	4905.76	47116.64				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Extra for every additional lift of 1.5 m or part thereof in excavation / banking excavated or stacked materials.																						
	All kinds of soil																						
13	1.5 to 3.0	cum	1165.98	1408.22	1759.92	4334.12				-	-	-	-	-	-	-	-	-	-	-	-	-	-
14	3.0 to 4.5	cum	784.61	320.53	795.11	1900.24				-	-	-	-	-	-	-	-	-	-	-	-	-	-
15	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	cum	1118.00	1118.00	1050.00	3286.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Anti termite treatment																						
	Supplying chemical emulsion in sealed containers including delivery as specified.																						
16	Chlorpyrifos/ Lindane emulsifiable concentrate of 20%	litre	1777.00	1777.00	1881.00	5435.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Diluting and injecting chemical emulsion for POST-CONSTRUCTIONAL anti-termite treatment (excluding the cost of chemical emulsion) :																						
	Treatment of soil under existing floors using chemical emulsion @ one litre per hole, 300 mm apart including drilling 12 mm diam holes and plugging with cement mortar 1 :2 (1 cement : 2 Coarse sand) to match the existing floor :																						
17	With Chlorpyrifos/Lindane E.C. 20% with 1% concentration.	sqm	1451.93	1310.93	1451.93	4214.79				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Sub Head 2 : Concrete Work																						
	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :																						
18	1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	cum.	1293.62	901.90	1093.03	3288.54				-	-	-	-	-	-	-	-	-	-	-	-	-	-
19	1:5:10 (1 cement : 5 coarse sand (zone-III) derived from natural sources : 10 graded stone aggregate 40 mm nominal size derived from natural sources)	cum.	407.40	492.40	527.40	1427.20				-	-	-	-	-	-	-	-	-	-	-	-	-	-
20	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand (zone - III) : 6 graded stone aggregate 20 mm nominal size) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth.	sqm	257.00	257.00	299.00	813.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Sub Head 3 : RCC Work, Form work, Reinforcement & Expansion Joint.																						
	Form Work																						
	Centering and shuttering including strutting, propping etc. and removal of form for :																						
21	Foundations, footings, bases of columns, etc. for mass concrete.	sqm	2687.54	1936.27	3056.14	7679.95				-	-	-	-	-	-	-	-	-	-	-	-	-	-
22	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc	sqm	16687.65	14996.90	13669.56	45354.11				-	-	-	-	-	-	-	-	-	-	-	-	-	-
23	Suspended floors, roofs, landings, balconies and access platform.	sqm	32058.86	31115.76	27307.46	90482.09				-	-	-	-	-	-	-	-	-	-	-	-	-	-
24	Shelves (Cast in situ)	sqm	145.20	145.20	619.44	909.84				-	-	-	-	-	-	-	-	-	-	-	-	-	-
25	Lintels, beams, plinth beams, girders, bressumers and cantilevers	sqm	20122.49	19487.70	22619.48	62229.67				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
26	Columns, Pillars, Piers, Abutments, Posts and Struts	sqm	14898.00	14951.00	12520.00	42369.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
27	Stairs, (excluding landings) except spiral-staircases	sqm	846.05	846.05	941.93	2634.03				-	-	-	-	-	-	-	-	-	-	-	-	-	-
28	Extra for shuttering in circular work (20% of respective centering and shuttering items)	sqm	450.48	450.48	139.97	1040.93				-	-	-	-	-	-	-	-	-	-	-	-	-	-
29	Small lintels not exceeding 1.5 m clear span, moulding as in cornices, window sills, string courses, bands, copings, bed plates, anchor blocks and the like	sqm	10.00	23.00	26.80	59.80				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Edges of slabs and breaks in floors and walls																						
30	Under 20 cm wide	metre	402.80	342.70	396.80	1142.30				-	-	-	-	-	-	-	-	-	-	-	-	-	-
31	Weather shade, Chajjas, corbels etc., including edges	sqm	1624.13	1622.13	1151.22	4397.47				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Extra for additional height in centering, shuttering where ever required with adequate bracing, propping etc. including cost of de-shuttering and decentering at all levels, over a height of 3.5 m, for every additional height of 1 metre or part thereof (Plan area to be measured)																						
32	Suspended floors, roofs, landing, beams and balconies (Plan area to be measured).	sqm	18414.24	18414.24	16658.72	53487.20				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Reinforcement TMT Steel																						
	Steel Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.																						
33	Thermo-Mechanically Treated bars of grade Fe-500D or more.	kg	1084155.50	1036827.00	1206975.89	3327958.39				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.																						
34	Thermo-Mechanically Treated bars of grade Fe-500 D or more.	kg	1973648.50	1948052.43	1849889.43	5771590.36				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Reinforced Cement Concrete																						
	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.																						
	All works upto plinth level																						
35	Concrete of M25 grade with minimum cement content of 330 kg /cum	cum	1570.85	899.93	1256.41	3727.19				-	-	-	-	-	-	-	-	-	-	-	-	-	-
36	Concrete of M30 grade with minimum cement content of 350 kg /cum	cum	6205.03	6523.41	7431.49	20159.94				-	-	-	-	-	-	-	-	-	-	-	-	-	-
37	Concrete of M40 grade with minimum cement content of 390 kg /cum	cum	172.19	172.19	158.64	503.03				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	All works above plinth level upto floor V level																						
38	Concrete of M25 grade with minimum cement content of 330 kg /cum	cum	359.45	325.45	1648.21	2333.11				-	-	-	-	-	-	-	-	-	-	-	-	-	-
39	Concrete of M30 grade with minimum cement content of 350 kg /cum	cum	8037.16	7657.74	7678.81	23373.71				-	-	-	-	-	-	-	-	-	-	-	-	-	-
40	Concrete of M40 grade with minimum cement content of 390 kg/cum	cum	3491.18	3494.13	3052.50	10037.81				-	-	-	-	-	-	-	-	-	-	-	-	-	-
41	Add for using extra cement in the items of design mix over and above the specified cement content therein	quintal	3027.91	3027.91	3014.15	9069.97				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
42	Extra for R.C.C./ B.M.C/ R.M.C. work above floor V level for each four floors or part thereof.	cum	3572.29	3364.02	2648.33	9584.64				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Expansion Joint																						
	Providing and fixing in position Stainless steel Grade 304 plate-1.0 mm thick as per design for expansion joints.																						
43	200 mm wide.	metre	175.30	175.30	0.00	350.60				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing of expansion joint system related with floor location as per drawings and direction of Engineer-In-Charge. The joints system will be of extruded aluminum base members, self aligning / self centering arrangement and support plates etc. as perASTM B221-02. The system shall be such that it provides floor to floor /floor to wall expansion control system for various vertical localtion in load application areas that accommodates multi directional seismic movement without stress to it's components. System shall consist of metal profiles with a universal aluminum base member designed to accommodate various project conditions and finish floor treatments. The cover plate shall be designed of width and thickness required to satisfy projects movement and loading requirements and secured to base members by utilizing manufacturer's pre-engineered self- centering arrangement that freely rotates / moves in all directions.The Self - centering arrangement shall exhibit circular sphere ends that lock and slide inside the corresponding aluminum extrusion cavity to allow freedom of movement and flexure in all directions including vertical displacement. Provision of Moisture Barrier Membrane in the Joint System to have watertight joint is mandatory requirement all as per the manufactures design and as approved by Engineer -inCharge. (Material shall confirm to ASTM 6063).																						
44	Floor Joint of 200 mm gap	metre	60.90	60.90	25.92	147.72				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing of expansion joint system related with wall joint (internal/external) location as per drawings and direction of Engineer-InCharge. The joints shall be of extruded aluminum base members, self aligning / centering arrangement and support plates as perASTM B221-02. The material shall be such that it provides an Expansion Joints System suitable for vertical wall to wall/ wall to corner application, both new and existing construction in office Buildings & complexes with no slipping down tendency amongst the components of the Joint System. The Joint System shall utilize light weight aluminum profiles exhibiting minimal exposed aluminum surfaces mechanically snap locking the multicellular to facilitate movement. (Material shall confirm to ASTM 6063).																						
45	Wall Joint of 200 mm gap	metre	353.40	353.40	130.80	837.60				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing of expansion joint system of approved make and manufactures for various roof locations as per approved drawings and direction of Engineer-In-Charge. The joints shall be of extruded aluminum base members with, self aligning and self centering arragement support plates asper ASTM B221-02. The system shall be such that it provides watertight roof to roof/roof to corner joint cover expansion control system that is capable of accommodating multidirectional seismic movement without stress to its components. System shall consist of metal profile that incorporates a universal aluminum base member designed to accommodate various project conditions and roof treatments. The cover plate shall be designed of width and thickness required to satisfy movement and loading requirements and secured to base members by utilizing manufacturer's pre-engineered self-centering arrangement that freely rotates / moves in all directions. The Self centering arrangement shall exhibit circular sphere ends that lock and slide inside the corresponding aluminum extrusion cavity to allow freedom of movement and flexure in all directions including vertical displacement. The Joint System shall resists damage or deterioration from the impact of falling ice, exposure to UV, airborne contaminants and occasional foot traffic from maintenance personnel. Provision of Moisture Barrier Membrane in the Joint System to have water tight joint is mandatory requirement. (Material shall confimetre to ASTM 6063).																						
46	Roof Joint of 200 mm gap	metre	46.52	46.52	25.92	118.96				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Sub Head 4 : Masonry Work																						
	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:																						

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
47	Cement mortar 1:6 (1 Cement : 6 coarse sand)	cum	195.32	89.92	217.45	502.69				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :																						
48	Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	381.58	357.67	309.45	1048.70				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Extra for brick work / AAC block masonry / Tile brick masonry in superstructure above floor V level, for each four floors or part thereof by mechanical means.	cum	2002.00	1949.00	1890.00	5841.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in :																						
50	cement mortar 1:4 (1 cement : 4 coarse sand)	sqm	10.00	10.00	10.00	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level.																						
51	Cement mortar 1:4 (1 cement :4 coarse sand)	sqm	30.00	10.00	60.92	100.92				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Brick work with non modular fly ash bricks conforming to IS:12894, class designation 10 average compressive strength in super structure above plinth level up to floor V level in :																						
52	Cement mortar 1:6 (1 cement : 6 Coarse sand)	cum	10.00	10.00	10.00	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and laying autoclaved aerated cement blocks masonry with 100 mm thick AAC blocks in super structure above plinth level up to floor V level in cement mortar 1:4 (1 cement : 4 coarse sand). The rate includes providing and placing in position 2 nos 6 mm dia M.S. bars at every third course of masonry work.	cum	757.00	749.00	587.00	2093.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and laying autoclaved aerated cement blocks masonry with 150mm to 300 mm thick AAC blocks in super structure above plinth level up to floor V level with RCC band at sill level and lintel level with approved block laying polymer modified adhesive mortar all complete as per direction of Engineer-in-Charge.	cum	5143.04	5170.04	5725.04	16038.12				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Sub Head 5 : Cladding Work																						
	Providing and fixing 18 mm thick gang saw cut, mirror polished, pre-moulded and pre-polished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.																						
	Granite stone slab of colour black, Cherry/Ruby red																						
55	Area of slab over 0.50 sqm	sqm	20.96	20.96	24.85	66.77				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Granite stone slab all colour and texture except black, Cherry/ Ruby red																						
56	Area of slab upto 0.50 sqm	sqm	5.24	5.24	6.21	16.69				-	-	-	-	-	-	-	-	-	-	-	-	-	-
57	Area of slab over 0.50 sqm	sqm	606.00	606.00	719.00	1931.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Extra for fixing marble /granite stone, over and above corresponding basic item, in facia and drops of width upto 150 mm with epoxy resin based adhesive, including cleaning etc. complete.	metre	12.00	12.00	12.00	36.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Extra for providing opening of required size & shape for wash basin/ kitchen sink in kitchen platform, vanity counter and similar location in marble/ Granite/ stone work, including necessary holes for pillar taps etc. including moulding, rubbing and polishing of cut edges etc. complete.	each	10.00	10.00	10.00	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
	Providing & Fixing decorative high pressure laminated sheet of plain / wood grain in gloss / matt/ suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality.																							
91	1.0 mm thick	sqm	1227.63	1278.96	1209.87	3716.46				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
92	Providing and fixing panic bar / latch (Double point) fitted with a singlebody, Trim Latch & Lock on back side of the Panic Latch of reputedbrand and manufacture to be approved by the Engineer- in-charge, all complete.	each	18.00	40.00	74.00	132.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing factory made uPVC white colour fixed glazed windows/ventilators comprising of uPVC multi-chambered frame and mullion (where ever required) extruded profiles duly reinforced with 1.60 ± 0.2 mm thick galvanized mild steel section made from roll forming process of required length (shape & size according to uPVC profile) , uPVC extruded glazing beads of appropriate dimension, EPDM gasket, G.I fasteners 100 x 8 mm size for fixing frame to finished wall, plastic packers, plastic caps and necessary stainless steel screws etc. Profile of frame shall be rm cut and fusion welded at all corners, mullion (if required) shall be also fusion welded including drilling of holes for fixing hardware's and drainage of water etc.After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size and of approved quality, all complete as per approved drawing & direction of Engineer-in-Charge. (Single / double glass panes and silicon sealant shall be paid separately). Variation in profile dimension in higher side shall be accepted but no extra payment on this account shall be made.																							
93	Fixed window / ventilator made of (small series) frame 47 x 50 mm & mullion 47 x 68 mm both having wall thickness of 1.9 ± 0.2 mm and single glazing bead of appropriate dimension. (Area upto 0.75 sqm.)	sqm	169.00	145.00	194.00	508.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing factory made uPVC white colour sliding glazed window upto 1.50 m in height dimension comprising of uPVC multi-chambered frame with in-built roller track and sash extruded profiles duly reinforced with 1.60 ± 0.2 mm thick galvanized mild steel section made from roll forming process of required length (shape & size according to uPVC profile), appropriate dimension of uPVC extruded glazing beads and uPVC extruded interlocks, EPDM gasket, wool pile, zinc alloy (white powder coated) touch locks with hook, zinc alloy body with single nylon rollers (weight bearing capacity to be 40 kg), G.I fasteners 100 x 8 mm size for fixing frame to finished wall and necessary stainless steel screws etc. Profile of frame & sash shall be mitred cut and fusion welded at all corners, including drilling of holes for fixing hardware's an drainage of water etc.After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size and of approved quality, all complete as per approved drawing & direction of Engineer-in-charge. (Single / double glass panes,wire mesh and silicon sealant shall be paid eparately). Variation in profile dimension in higher side shall be accepted but no extra payment on this account shall be made.																							
94	Three track three panels sliding window with fly proof SS wire mesh (Two nos. glazed & one nos wire mesh panels)made of (small series) frame 92 x 44 mm & sash 32 x 60 mm both having wall thickness of 1.9 ± 0.2 mm and single glazing bead of appropriate dimension (Area of window upto 1.75 sqm).	sqm	140.00	100.00	112.00	352.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
95	Two track two panels sliding window made of (big series) frame 67 x 50 mm & sash 46 x 62 mm both having wall thickness of 2.3 ± 0.2 mm and single glazing bead / double glazing bead of appropriate dimension . (Area of window above 1.75 sqm upto 2.50 sqm).	sqm	262.00	252.00	256.00	770.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing Pre -laminated medium density fibre board exterior grade (Grade-I) IS:14587:1998 marked, to frame, backing or studding with screws etc. complete (Frames, backing or studding to be paid separately).																							
96	Pre-laminated with decorative lamination on both side exterior Grade - I MDF Board 12 mm thick conforming to IS:14587	sqm	142.00	139.00	113.00	394.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
97	Providing and fixing fire resistant door frame of section 50 x 60 mm on horizontal side & 35 x 60 mm on vertical sides having built in rebate made out of 1.6 mm thick GI sheet (Zinc coating not less than 120gm/m ²) suitable for mounting 120 min Fire Rated Glazed Door Shutters.The frame shall be filled with Mineral wool Insulation having density min 96kg/m ³ . The frame will have a provision of G.I.Anchor fasteners 14 no (5 each on vertical style & 4 on horizontal style of size M10 x 80) suitable for fixing in the opening along with Factory made Template for SS Ball Bearing Hinges of Size 100x89x3mm for fixing of fire rated glazed shutter . The frame shall be finished with a approved fire resistant primer or Powder coating of not less than 30 micron in desired shade as per the directions of Engineer - in- charge . (Cost of SS ball bearing hinges is excluded).	metre	805.00	813.00	718.00	2336.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
98	Providing and fixing 60 mm thick glazed fire resistant door shutters of 120 min Fire Rating conforming to IS:3614 (Part II) or EN1634-1:1999, tested and certified as per laboratory approved by Engineer-in-charge, with suitable mounting on door frame, consisting of vertical styles, top rail & side rail 60 mm x 60 mm wide and bottom rail of 110 mm x 60 mm made out of 1.6mm thick G.I. sheet (zinc coating not less than 120gm/m ²) duly filled mineral wool insulation having density min 96 kg/ m ³ and fixing with necessary stainless steel ball bearing hinges of size 100x89x3mm of approved make, including applying a coat of approved fire resistant primer or powder coating not less than 30 micron etc all complete as per direction of Engineer-in-charge (panelling to be paid for seperately).	sqm	561.00	561.00	519.00	1641.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
99	Providing and fixing glazing in fire resistant door shutters, fixed panels& partitions etc., with G.I. beading made out of 1.6 mm thick G.I. sheet (zinc coating not less than 120 gm/m ²) of size 20 x 33 mm screwed with M4 x 38 mm SS screws at distance 75 mm from the edges and 150 mm c/c , including applying a coat of approved fire resistant primer/ powder coating of not less than 30 micron on G.I. beading, & special ceramic tape of 5 x 20 mm size etc complete in all respect as per NBC 2016, IS 16231 (Part 3):2016 and as per direction of Engineer-in-charge with glass of required thickness having 120 minutes of fire resistance both integrity & radiation control (EW120) and minimum 20 minutes of insulation (EI20). The manufacturer have to give test report/certification of fire glass and the glass should have the stamp showing the value of E, EW & EI. The glass shall be tested in approved NABL accredited lab or by any other accreditation body which operates in accordance with ISO/IEC 17011 and accredits labs as per ISO/IEC 17025 for testing and calibration scopes shall be eligible. The maximum glazing size shall not be more than 1100x2200 mm (w x h) or 2.42 sqm.	sqm	29.00	28.00	28.00	85.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing bright /matt finished Stainless Steel handles of approved quality & make with necessary screws etc all complete.																							
100	100 mm	each	106.00	92.00	160.00	358.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Flush door hardware																							
101	Providing and fixing Stainless steel (SS 304) Mortice door lock with handles and matching to LOM provided lever handles of approved quality with necessary screws etc. complete.	each	1093.00	1771.00	1191.00	4055.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing stainless steel (Grade 304) tower bolts approved equivalent with necessary screws etc. complete.																							
102	150 x 10mm	each	1103.00	1196.00	1266.00	3565.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing SS (304)hanging floor door stopper, ISI marked, matt finish with necessary screws etc. complete.																							
103	Single rubber stopper	each	477.00	558.00	486.00	1521.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
104	3M Glass Film plain/ colored at All height and Level.Providing and fixing 3M Frosted Translucent, cast PVC, self-adhesive vinyl, special CRYSTAL-effect film to reproduce Sand-blasting effect on glass with customised designs, thickness of 2 mil (0.05mm) without adhesive & 3mil (0.8)with adhesive having minimum tensile strength of 3.5 pound/inch at 73 F(0.6 kg/cm at 23 C). Adhesion after 24hrs of installation should be 4 pounds/inch (0.7 kg/cm) on Acrylic, Glass Polycarbonate, all complete.with required materials of approved make, for all floor heights as per approved design, pattern and drawings and direction of Engineer-In-Charge.(Actual film area shall be measured in sqm up to decimal place for payment)(Basic rate of film is Rs.1055/sqm)	sqm	89.19	94.23	99.99	283.41				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
105	Supply & Fixing of Lead Lined Stainless steel Clean room door frames and shutters made of Stainless steel grade of 304 hairline finish, frame with 1.60mm (16SWG) thick hairline finish Stainless steel grade of 304 formed to Single/double rebate profile of size 100 mm x 58mm/ 143 x 58 mm, door frames with a single / multi Layer of Lead sheet varying thickness from 3mm /1mm to 2mm depends on radiation level, the shutter with 1.2 mm thick hairline finish Stainless steel grade of 304 formed to provide a 46mm thick fully flush, double skin door shell with Lock Seam joints at stile edges with a single / multi Layer of Lead sheet varying thickness from 3mm /1mm to 2mm depends on radiation level. The lead sheets extend the full width and height of the door. Lead thickness is to be equal to the shielding in the adjacent wall. Hardware can be provided with Stainless Steel Ball Bearing Butt Hinges 3 mm thick fixed flush to the frame and shutter etc., including overheads and contractor profit etc., complete for finished item of work in all floors	sqm	53.40	53.40	47.50	154.30				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Sub Head 7 : Steel Work																								
106	80x1.25 mm M.S. laths with 1.25 mm thick top cover	sqm	31.00	31.00	22.00	84.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
107	Providing and fixing ball bearing for rolling shutters.	each	4.00	4.00	2.00	10.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
108	Extra for providing mechanical device chain and crank operation for operating rolling shutters. Exceeding 10.00 sqm and upto 16.80 sqm in the area	sqm	31.00	31.00	22.00	84.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
109	Profile B Fixing with carbon steel galvanised dash fastener of required dia and size (to be paid for separately)	metre	11.00	5.20	11.00	27.20				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
110	Hot finished welded type tubes	kg	50.00	50.00	50.00	150.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
111	Hot finished seamless type tubes	kg	1183.20	1183.20	1183.20	3549.60				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
131	100mm High Vinyl coving with supporting of aluminium section, between wall and floor corners Rate shall include all material and labour complete. Homogeneous vinyl wall covering shall be in 1 mm thickness (minimum), weight less than 2000 gms/sqm as per EN 430, Fire rating class Bs2-d0 as per EN 13 501-1 , binder content of type -I as per ISO 10582, dimensional stability of ≤0.4 as per EN 434, color fastness rating of ≥6 degree as per EN 20105-802, Product should conform to Floor Score® Indoor Air Quality Certified (≤ 10 µg / m³ as per ISO 16000-6), anti-bacterial activity (> 99 % inhibits growth as per ISO 22196). The product should be homogeneous and single layered. The product shall have excellent chemical resistance as per EN 423. Installation - Installation of Vinyl Wall Covering 1.00mm thick over smooth wall surface including fixing with adhesive complete as per drawing & as directed by Engineer-in-charge. It is important to ensure the Wall on which the sheet is being pasted is smooth, flat, hard and free from moisture, grease etc	metre	977.16	977.16	715.03	2669.35				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
132	Providing and laying brick aggregate cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 brick aggregate) with 40mm brick aggregate to a required depth and filling layers of 150mm each in toilets (sunken floor) at all levels with contractor's material, labour, tools and plants including lead and lifts etc as per the directions of the Engineer-in-charge.	cum	558.28	558.20	558.28	1674.76				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Sub Head 9 : Roofing Work																								
Gypsum Plain Board																								
133	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimetre channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimetre of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimetre channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimetre channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with :	sqm	8437.00	8437.00	6189.00	23063.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
134	12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095 (Part I) :2011 (Board with BIS certification marks)	sqm	180.00	180.00	49.00	409.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
135	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	sqm	311.63	206.00	311.63	829.26				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing pre-coated galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete :																						
136	Ridges plain (500 - 600mm)	metre	37.29	16.73	37.29	91.31				-	-	-	-	-	-	-	-	-	-	-	-	-	-
137	Flashings/ Aprons.(Upto 600 mm)	metre	16.73	16.73	16.73	50.19				-	-	-	-	-	-	-	-	-	-	-	-	-	-
138	Gutter (600 mm over all girth)	metre	16.73	16.73	16.73	50.19				-	-	-	-	-	-	-	-	-	-	-	-	-	-
139	Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T,																						
	bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge.																						
	12.5 mm thick fully Perforated Gypsum Board tile made from plasterboard having glass fibre conforming to IS: 2095 part I, of size 595x595 mm, having perforation of 9.7x9.7 mm at 19.4 mm c/c with center borders of 48 mm and the side borders of 30 mm, backed with non woven tissue on the back side, having an NRC (noise Reduction Coefficient) of 0.79, with 50 mm resin bonded glass wool backing.	sqm	699.00	699.00	0.00	1398.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Metal Ceiling																						
	Providing and fixing GI Clip in Metal Ceiling System of 600x600 mm module which includes providing and fixing 'C' wall angle of size 20x30x20 mm made of 0.5 mm thick pre painted steel along the perimetre of the room with help of nylon sleeves and wooden screws at 300 mm center to centre, suspending the main C carrier of size 10x38x10 mm made of G.I steel 0.7 mm thick from the soffit with help of soffit cleat 37x27x25x1.6 mm, rawl plugs of size 38x12 mm and C carrier suspension clip and main carrier bracket at 1000 mm c/c. Inverted triangle shaped Spring Tee having height of 24 mm and width of 34 mm made of GI steel 0.45 mm thick is then fixed to the main C carrier and in direction perpendicular to it at 600 mm centers with help of suspension brackets. Wherever the main C carrier and spring T have to join, C carrier and spring T connectors have to be used. All sections to be galvanized @ 120 gms/sqm (both side inclusive), fixing with clip in tiles into spring T with :																						

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
140	GI Metal Ceiling Clip in plain Beveled edge global white color tiles of size 600x600 and 0.5 mm thick with 25 mm height, made of G I sheet having galvanizing of 100 gms/ sqm (both sides inclusive) and 20% perforation area with 1.8 mm dia holes and having NRC of 0.5, electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending and perforation.	sqm	4969.00	4864.00	3465.00	13298.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
141	Providing and fixing Heat Resistant Terrace Tiles (300 mm x 300 mm x 20 mm) with SRI (solar refractive index) > 78, solar reflection > 0.70 and initial emittance > 0.75 on waterproof and sloped surface of terrace, laid on 20 mm thick cement sand mortar in the ratio of 1:4 (1 cement : 4 coarse sand) and grouting the joints with mix of white cement & marble powder in ratio of 1:1, including rubbing and polishing of the surface upto 3 cuts complete, including providing skirting upto 150 mm height along the parapet walls in the same manner.	sqm	4780.00	4780.00	5288.00	14848.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Calcium Silicate Board																						
142	Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on interlocking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to fometre grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanized butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge. 8 mm thick fully perforated calcium silicate board made with Calcareous & Siliceous materials reinforced with cellulose fiber manufactured through autoclaving process to give stable crystalline structure with minimum compressive strength 225 kg/ sq. cm, bending strength 100 kg/sq. cm , of size 595x595 mm, having perforation of dia. 10 mm with minimum perforated area 18 % with non woven tissue on the back side, having an NRC (noise Reduction Coefficient) of 0.85, with 50 mm thick rockwool of 48 kg /cum backing.	sqm	10.00	10.00	10.00	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Mineral Fiber Tile False Ceiling																						
	Providing and fixing mineral fibre false ceiling tiles at all heights of size 595X595mm of approved texture, design and pattern. The tiles should have Humidity Resistance (RH) of 99%, Light Reflectance ? 85%, Thermal Conductivity k = 0.052 - 0.057 w/m K, Fire Performance as per (BS 476 pt - 6 &7)in true horizontal level suspended on interlocking T-Grid of hot dipped all round galvanized iron section of 0.33 mm thick (galvanized @120 gsm) comprising of main T runners of 15x32 mm of length 3000 mm, cross T of size 15x32mm of length 1200 mm and secondary intermediate cross T of size 15x32 mm of length 600 mm to form grid module of size 600x600 mm suspended from ceiling using galvanized mild steel item(galvanised@80gsm) 50 mm long 8mm outer diarm M-6 dash fasteners, 6 mm diarm fully threaded hanger rod up to 1000 mm length and L-shape level adjuster of size 85x25x2 mm, spaced at 1200 mm centre to centre along main "T". The system should rest on periphery walls /partitions with the help of GI perim wall angle of size24x24X3000 mm made of 0.40 mm thick sheet, to be fixed to the wall with help of plastic rawl plug at 450 mm centre to centre & 40 mm long dry wall S.S. screws. The exposed bottom portion of all T-sections used in false ceiling support system shall be pre-painted with polyester baked paint, for all heights.																						

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
143	The work shall be carried out as per specifications, drawings and as per directions of the engineer-in-charge. With 20 mm thick beveled tegular mineral fibre false ceiling tile (NRC 0.7)	sqm	1411.00	1411.00	2336.00	5158.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
144	Providing, Supplying & Installation of Microcell Polycarbonate 20mm thick (minimum) UV protected panel system which shall be uniform in color with an integral Microcell core. They should be manufactured with Vertical Standing Seam with standing seam height of 10-20mm at both sides of the panel. Panels shall be fixed on MS /Trusses purlins with continuous Structural Aluminum double wall I-profile Spacer together with snap-on connector. These connectors to interlock the panels shall have a 2-4 tooth grip-lock locking mechanism to ensure maximum uplift capability and shall pass a pullout load of min. 4000 N (4kN) when tested as per ISO 6892:1998 and IS 1608:2005. Panel shall be with additional End-cap/Aluminum U-Profile (mill finish) for ends.including glass wool 100 mm Above Panel System shall be fixed over structural steel trusses / MS purlin with 2 coats of Enamel paint etc. conforming to the detail technical specifications as per approved Architectural Drawings submitted by Vendor Items includes cost of 20mm thick Polycarbonate sheet roofing with all its elements(Louvers), accessories , fittings and fixtures, scaffolding, labour , all required machineries for fixing and all valid taxes i.e. sales tax, excise duty, custom duty etc. complete. The above work is to be carried out by a Specialized Agency, as approved by the Engineer-in-Charge.	sqm	4.00	4.00	4.00	12.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
145	Providing and laying of roofing shingle including preparation of surface as required for treatment of roofing shingles, underlaying membrane & nails consisting of following operations systems with nailing method: Applying a BITUMEN PRIME COATING is intended for preparation of the surface before installation of self-adhesive sealant tape waterproofing material width 5cm. The primer presents a mix of high-quality bitumen and specially selected organic solvents. It has an enhanced covering mass fraction of non-volatile substances 45-55% , relative viscosity 15-40s, consumption 0.25-0.35lit per sqm bucket volume 3,10,30 and bitumen primer should be allowed to dry for a minimum of 6 to 8 hours to ensure proper adhesion of subsequent layers including cleaning the surface before treatment.	sqm	1170.75	1170.75	1170.75	3512.25				-	-	-	-	-	-	-	-	-	-	-	-	-	-
146	Laying of HIP and Ridge/Starter SBS modified, high-end, factory-made ridge called HIP and Ridge/Starter of TECHNINICOL Brand with the help of the nailing method and ensure the standard area assumption base layer fiberclass 110, SBS bitumen type, Flow resistance at elevated temperature 100°C, 3.4±0.2 mm Thickness per layer, 5.5 kg per sqm weight, Installation method a/c and as directed and specified by the Engineer-in-Charge :	metre	742.52	742.52	742.52	2227.56				-	-	-	-	-	-	-	-	-	-	-	-	-	-
147	Applying High Definition, Laminated Asphalt-based roofing shingles called "Country Series of Shinglas Brand" (having 50 years warranty and weight of 12 kg per sqm) with the help of the nailing method. Shinglas Brand's "Country Series" roofing shingles offer long durability with a significant weight. The shingles should be securely nailed to the surface for proper fixation. Roofing shingles by TECHNINICOL fully comply with EN 544 – European standard for bitumen shingles knoswn for its strict requirements for the minimum mass of bitumen in products 1300 g/m² for laying roofing shingles and as directed and specified by the Engineer-in-Charge :	sqm	1170.75	1170.75	1170.75	3512.25				-	-	-	-	-	-	-	-	-	-	-	-	-	-
Sub Head 10 : Finishing Works																							
Internal Finishes																							
12mm cement plaster of mix :-																							
148	1:4 (1 cement : 4 fine sand) in addition cement compound fibre has to be added in the cement plaster	sqm	43812.42	43645.00	42392.68	129850.10				-	-	-	-	-	-	-	-	-	-	-	-	-	-
149	15mm cement plaster on the rough side of single or half brick wall of mix 1:6 (1 cement : 6 fine sand)	sqm	5622.00	5622.00	5658.00	16902.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
167	Extra for plastering exterior walls of height more than 10 m from ground level for every additional height of 3 m or part thereof.	sqm	50100.00	50100.00	47073.00	147273.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
168	18 mm thick plain cement mortar band in cement mortar 1:4 (1 cement : 4 fine sand): Moulded Band	cm/metre	3693.01	3693.01	3693.01	11079.03				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
169	Finishing walls with textured exterior paint of required shade : New work (Two or more coats applied @ 3.28 ltr/10 sqm) over and including priming coat of exterior primer applied @ 2.20kg/10 sqm	sqm	9982.29	9977.08	10028.39	29987.76				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
170	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm.	sqm	19733.41	19693.73	22932.00	62359.14				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
171	Add for plaster drip course/ groove in plastered surface or moulding to R.C.C. projections.	metre	2733.88	2733.88	2733.88	8201.63				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
172	Providing and finishing 24 gauge 19 mm size galvanised chicken wire mesh of approved make and design at junctions of RCC and brick work and other locations including necessary clips and "U" nails rawl plugs,screws etc. complete for all height as per specifications & direction of the Engineer-In-Charge	sqm	1459.48	1433.80	1459.48	4352.76				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Sub Head 11 : Road Work																								
173	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earthwith lead upto 50 metres.	sqm	10043.00	5379.00	6195.00	21617.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
174	Extra for compaction of earth work in embankment under optimum moisture conditions to give at least 95% of the maximum dry density (proctor density).	cum	5022.00	2690.00	2478.00	10190.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
175	Supplying and stacking at site. Good earth	cum	10043.00	5379.00	0.00	15422.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
176	Supplying, stacking and Spreading 6 mm thick red bajri, watering and rolling complete including preparation of the surface and rolling. With road roller/ hand roller	sqm	1738.00	1045.30	1334.50	4117.80				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
177	Supplying at site Angle iron post & strut of required size including bottom to be split and bent at right angle in opposite direction for 10 cm length and drilling holes upto 10 mm dia. etc. complete.	kg	2074.00	507.00	0.00	2581.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
178	75 mm thick back filling for pitching including supplying of required materials and consolidation etc. complete with : Stone aggregate 40 mm nominal size	sqm	131.00	0.00	0.00	131.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
179	Providing,laying and fixing RCC pipe NP2 class (light duty) in ground complete with RCC collars, jointing with cement mortar 1:2 (1 cement: 2 fine sand) including trenching and refilling etc as required . 150mm Dia	metre	150.00	130.00	270.00	550.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
180	300mm Dia	metre	300.00	70.00	135.00	505.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
190	Dry stone pitching 22.5 cm thick laid in courses and required profile with hammer dressed stones having no side less than 15 cm, with minimum depth of 20 cm including preparing the bedding surface etc. all complete. (Payment for Stone to be made separately).	sqm	1740.00	0.00	0.00	1740.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
191	Construction of dry lean cement concrete sub base over a prepared sub-grade with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per specifications, cement content not to be less than 150 kg/cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, for all leads & lifts, laid with a mechanical paver, compacting with 8-10 tonne vibratory roller, finishing and curing etc. complete as per direction of Engineer-in-charge.	cum	37.00	174.00	112.00	323.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
192	Providing and erecting 2.00 metre high temporary barricading at site; each panel of size 2.50 m x2.00 m made of 40x40x6 mm angle iron or 50x50x3 mm hollow MS tube posts/horizontal members/bracings covered with 1.63 mm thick MS sheet. The sheet shall be fixed with 30x5 mm MS flt by suitable welding/riveting. The panels shall be made so that gap of 50cm above the ground is available making overall height as 2.5 m. MS channel ISLC 75 @ 5.70 kg/m, 50 cm long shall be provided at the bottom having oval shaped holes of size 50x25 mm at both ends with 50 cm long MS angle 40x40x6 mm bracing. Suitable arrangement shall be made to fix the barricading to avoid from overturning by providing 250 mm long expansion fasteners at both ends. The work shall be executed as per drawing/direction of Engineer-in-Charge which includes writing and painting, arrangement for traffic diversion such as traffic signals during construction at site for day and night, glow lamps, reflective signs, marking, flags, caution tape as directed by the Engineer-in-Charge. The barricading provided shall be retained in position at site continuously including shifting of barricading from one location to another location as many times as required during the execution of the entire work till its completion. Rate include its maintenance for damages, painting, all incidentals, labour materials, equipments and works required to execute the job.	metre	800.00	800.00	762.00	2362.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	The barricading shall not be removed without prior approval of Engineer-in-Charge.																						
	Chequered precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand).																						
193	Dark shade pigment using ordinary cement	sqm	760.00	612.00	0.00	1372.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge.																						
194	60mm thick cement concrete paver block of M-35 grade with approved colour, design & pattern.	sqm	1768.00	84.00	380.00	2232.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
195	80 mm thick C.C. paver block of M-30 grade with approved color design and pattern.	sqm	7147.00	3717.00	6578.00	17442.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Rectangular type with openable circular lid																						
196	150 mm nominal size square 100 mm diameter of the inner hinged round grating	each	335.00	273.00	0.00	608.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
197	Providing and placing in position 100 mm thick factory made machine batched & machine mixed Precast RCC Rectangular Covers on drains of footpath of various sizes, of M-25 grade cement concrete for RCC work, including cost of centering, shuttering, reinforcement of 8 mm dia TMT bars of Fe 500 grade @ maximum 100mm c/c on both ways , neat cement punning on finished surface, properly encased on all edges with 1.6 mm thick , 100 mm wide MS sheet duly painted over priming coat , reinforcement to be welded at edges with MS sheet and providing 2 nos. 12 mm dia bar for hooks etc i/c cost of cartage, all leads & lift, handling at site etc. all complete as per direction of Engineer-in-Charge.	sqm	44.00	44.00	102.00	190.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Sub Head 12 : Pilework																								
198	Boring, providing and installation bored cast-in-situ reinforced cement concrete piles of grade M-30 of specified diameter and length below the pile cap, to carry a safe working load not less than specified, excluding the cost of steel reinforcement but including the cost of boring with bentonite solution and temporary casing of appropriate length for setting out and removal of same and the length of the pile to be embedded in the pile cap etc. by percussion drilling using Direct mud circulation (DMC) or Bailer and chisel technique by tripod and mechanical Winch Machine all complete, including removal of excavated earth with all its lifts and leads (length of pile for payment shall be measured up to bottom of pile cap).	metre	19443.00	7652.00	8228.00	35323.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
199	Thermo-Mechanically Treated bars of grade Fe-500D or more.	kg	686823.98	270306.90	290654.10	1247784.98				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
200	Initial test (Test Load 2.5 times the Safe capacity)	Per Test	1.00	1.00	1.00	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
201	Routine test (Test Load 1.5 times the Safe capacity)	Per Test	1.00	1.00	1.00	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
200A	Initial test (Test Load 2.5 times the Safe capacity)	Per Test	15.00	8.00	8.00	31.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
201A	Routine test (Test Load 1.5 times the Safe capacity)	Per Test	15.00	8.00	8.00	31.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
202	Integrity testing of Pile using Low Strain/ Sonic Integrity Test/ Sonic Echo Test method in accordance with IS 14893 including surface preparation of pile top by removing soil, mud, dust & chipping lean concrete lumps etc. and use of computerised equipment and high skill trained personal for conducting the test & submission of results, all complete as per direction of Engineer-in-charge	Per Test	16.00	8.00	9.00	33.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
note :- The inclusion of the above item in the schedule of work shall be judiciously decided by the technical sanctioning authority, keeping in view the quality control, type of soil strata & importance of the project.																								
Sub Head 13 : Aluminium & Glass Works																								

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
213	Providing and applying integral crystalline slurry of hydrophilic in nature for waterproofing treatment to the RCC structures like retaining walls of the basement, water tanks, roof slabs, podiums, reservoir, sewage & water treatment plant, tunnels / subway and bridge deck etc., prepared by mixing in the ratio of 5 : 2 (5 parts integral crystalline slurry : 2 parts water) for vertical surfaces and 3 : 1 (3 parts integral crystalline slurry : 1 part water) for horizontal surfaces and applying the same from negative (internal) side with the help of synthetic fiber brush. The material shall meet the requirements as specified in ACI- 212-3R-2010 i.e by reducing permeability of concrete by more than 90% compared with control concrete as per DIN 1048 and resistant to 16 bar hydrostatic pressure on negative side. The crystalline slurry shall be capable of self-healing of cracks up to a width of 0.50mm. The work shall be carried out all complete as per specification and the direction of the engineer-in-charge. The product performance shall carry guarantee for 10 years against any leakage.	sqm	2983.10	2787.10	3406.00	9176.20				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
214	Providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc consisting of following operations: (a) Applying a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with water proofing compound conforming to IS. 2645 and approved by Engineer-in-charge over the RCC slab including adjoining walls upto 300 mm height including cleaning the surface before treatment.(b) Laying brick bats with mortar using broken bricks/brick bats 25 mm to 115 mm size with 50% of cement mortar 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge over 20 mm thick layer of cement mortar of mix 1:5 (1 cement :5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge to required slope and treating similarly the adjoining walls upto 300 mm height including rounding of junctions of walls and slabs. (c) After two days of proper curing applying a second coat of cement slurry using 2.75 kg/ sqm of cement admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge.(d) Finishing the surface with 20 mm thick jointless cement mortar of mix 1:4 (1 cement :4 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge including laying glass fibre cloth of approved quality in top layer of plaster and finally finishing the surface with trowel with neat cement slurry and making pattern of 300x300 mm square 3 mm deep.(e) The whole terrace so finished shall be flooded with water for a minimum period of two weeks for curing and for final test."All above operations to be done in order and as directed and specified by the Engineer-in-Charge :	sqm	5586.25	4976.83	5556.25	16119.33				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
215	Providing and Placing in position suitable PVC water stops conforming to IS:12200 for construction/ expansion joints between two RCC members and fixed to the reinforcement with binding wire before pouring concrete etc. complete :	metre	411.00	226.00	411.00	1048.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
216	Providing and applying integral crystalline slurry of hydrophilic in nature for waterproofing treatment to the RCC structures like retaining walls of the basement, water tanks, roof slabs, podiums, reservoir, sewage & water treatment plant, tunnels / subway and bridge deck etc., prepared by mixing in the ratio of 5 : 2 (5 parts integral crystalline slurry : 2 parts water) for vertical surfaces and 3 : 1 (3 parts integral crystalline slurry : 1 part water) for horizontal surfaces and applying the same from negative (internal) side with the help of synthetic fiber brush. The material shall meet the requirements as specified in ACI- 212-3R-2010 i.e by reducing permeability of concrete by more than 90% compared with control concrete as per DIN 1048 and resistant to 16 bar hydrostatic pressure on negative side. The crystalline slurry shall be capable of self-healing of cracks up to a width of 0.50mm. The work shall be carried out all complete as per specification and the direction of the engineer-in-charge. The product performance shall carry guarantee for 10 years against any leakage.	sqm	205.91	55.51	205.91	467.33				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
217	For vertical surface two coats @ 0.70 kg per sqm	sqm	745.78	685.78	745.78	2177.34				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
218	Providing and fixing factory made precast RCC perforated drain covers, having concrete of strength not less than M-25, of size 1000 x 450x50 mm, reinforced with 8 mm dia four no longitudinal & 9 no cross sectional T.M.T. hoop bars, including providing 50 mm dia perforations @ 100 to 125 mm c/c, including providing edge binding with M.S. flats of size 50 mm x 1.6 mm complete, all as per direction of Engineer-in-charge.	each	170.00	112.00	0.00	282.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
Sub Head 15 : Structural Glazing And Aluminium Composite Panel																							
219	Providing and supplying aluminium extruded tubular and other aluminium sections as per the architectural drawings and approved shop drawings, the aluminium quality as per grade 6063 T5 or T6 as per BS 1474, including super durable powder coating of 60-80 microns conforming to AAMA 2604 of required colour and shade as approved by the Engineer-in-Charge. (The item includes cost of material such as cleats, sleeves, screws etc. necessary for fabrication of extruded aluminium frame work. nothing extra shall be paid on this account). The weight of aluminium extruded section shall be taken for purpose of payment.	kg	3607.05	3607.05	3095.30	10309.40				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Designing, fabricating, testing, protection, installing and fixing in position semi (grid) unitized system of structural glazing (with open joints) for linear as well as curvilinear portions of the building for all heights and all levels, including:																						
	Providing and supplying Spandrel Glass Panels comprising of 6 mm thick heat strengthened monolithic float glass of approved colour and shade with reflective soft coating on surface # 2 of approved colour and shade so as to match the colour and shade of the IGUs in the vision panels etc. ,all complete for the required performances as specified, as per the Architectural drawings, as per the approved shop drawings, as specified, and as directed by the Engineer- in Charge. (i) Coloured tinted float glass 6mm thick substrate with reflective soft coating on face # 2, having properties as visible Light transmittance (VLT) of 25 to 35 %, Light reflection internal 10 to 15%, light reflection external 10 to 20 %, shading coefficient (0.25- 0.28) and U value of 3.0 to 3.3 W/m2 K etc.The properties of performance glass shall be decided by technical sanctioning authority as per the site requirement																						
	a) Structural analysis & design and preparation of shop drawings for the specified design loads conforming to IS 875 part III (the system must passed the proof test at 1.5 times design wind pressure without any failure), including functional design of the aluminum sections for fixing glazing panels of various thicknesses, aluminium cleats, sleeves and splice plates etc. gaskets, screws, toggles, nuts, bolts, clamps etc., structural and weather silicone sealants, flashings, fire stop (barrier)-cum-smoke seals, microwave cured EPDM gaskets for water tightness, pressure equalisation & drainage and protection against fire hazard including:																						
	b) Fabricating and supplying serrated M.S. hot dip galvanised / Aluminium alloy of 6005 T5 brackets of required sizes, sections and profiles etc. to accommodate 3 Dimensional movement for achieving perfect verticality and fixing structural glazing system rigidly to the RCC/ masonry/structural steel framework of building structure using stainless steel anchor fasteners/ bolts, nylon separator to prevent bimetallic contacts with nuts and washers etc. of stainless steel grade 316, of the required capacity and in required numbers.																						
	c) Providing and filling, two part pump filled, structural silicone sealant and one part weather silicone sealant compatible with the structural silicone sealant of required bite size in a clean and controlled factory / work shop environment, including double sided spacer tape, setting blocks and backer rod, all of approved grade, brand and manufacture, as per the approved sealant design, within and all around the perimetre for holding glass.																						

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
227	<p>Stone Sand Blanket The stone sand blanket shall be laid over the top of the stone columns or below Raft for minimum 500mm thickness or as per the governing design criteria and will be compacted to a relative dry density of 85 percent Compaction (to be confirmed by field compaction test)shall be carried out with rollers with 10-12 MT capacity vibro roller. Stone / Sand shall be laid in layers of 150mm and compacted to achieve desired compaction.</p> <p>The Stone Sand Blanket shall be constructed with mixture of 75 mm and down stone aggregates and well graded medium to coarse sand of Fineness Modulus not less than 2.2.The proportions for mix ratio of 2:1 (2 Stone Aggregates: 1 sand).</p>	cum	3024.00	3129.00	3175.00	9328.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Initial Load Test (Single and Group Column Test)																						
228	Single Column Plate Load Test(to be carried out outside the raft foot print area)	nos.	0.00	1.00	1.00	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	
	Carrying out specified no of initial plate load tests on single columns (totalling to 9 no's)(as per clause 3.5 of IS 15284 part 1 and clause 7.4 of IS 15284 part 1) at specified locations as given by the Engineer in charge/client with necessary kentledge etc. complete in all respects and making a report thereof to confirm achievement of net SBC of 8.5 T/m2.The test should be carried out through a reputed agency (with prior approval of Engineer in charge)which needs to be approved by IIT/NIT, including the testing procedure and the test results. The test needs to be witnessed along with the representative of PMC, the Engineer in charge,the testing agency (contractor), and an authorized representative of IIT/NIT.																						
229	Group Column Plate Load Test (to be carried out outside the raft foot print area)	nos.	0.00	1.00	1.00	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	
	Carrying out specified no of initial plate load tests on a group of stone columns (totalling to16 no's)(as per clause 3.5 of IS 15284 part 1 and clause 7.4 of IS 15284 part 1) at specified locations as given by the Engineer in charge/client with necessary kentledge etc. complete in all respects and making a report thereof to confirm achievement of net SBC of 8.5 T/m2. The test should be carried out through a reputed agency (with prior approval of Engineer in charge)which needs to be approved by IIT/NIT, including the testing procedure and the test results. The test needs to be witnessed along with the representative of PMC, the Engineer in charge,the testing agency (contractor), and an authorized representative of IIT.																						
	Routine Load Test (Single and Group Column Test)																						
230	Single Column Plate Load Test	nos.	0.00	7.00	7.00	14.00				-	-	-	-	-	-	-	-	-	-	-	-	-	
	Carrying out specified no of routine plate load tests on single columns (for every 625 m2 consideration)(as per clause 3.5 of IS 15284 part 1 and clause 7.4 of IS 15284 part 1) at specified locations as given by the Engineer in charge/client with necessary kentledge etc. complete in all respects and making a report thereof to confirm achievement of net SBC of 8.5 T/m2. The test should be carried out through a reputed agency (with prior approval of Engineer in charge)which needs to be approved by IIT/NIT, including the testing procedure and the test results. The test needs to be witnessed along with the representative of PMC, the Engineer in charge,the testing agency (contractor), and an authorized representative of IIT.																						
231	Group Column Plate Load Test	nos.	0.00	3.00	3.00	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	
	Carrying out specified no of routine plate load tests on group of stone columns (for every 625 m2 consideration)(as per clause 3.5 of IS 15284 part 1 and clause 7.4 of IS 15284 part 1) at specified locations as given by the Engineer in charge/client with necessary kentledge etc. complete in all respects and making a report thereof to confirm achievement of net SBC of 8.5 T/m2.The test should be carried out through a reputed agency (with prior approval of Engineer in charge)which needs to be approved by IIT/NIT, including the testing procedure and the test results. The test needs to be witnessed along with the representative of PMC, the Engineer in charge,the testing agency (contractor), and an authorized representative of IIT.																						

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
258	DIRECTION ARROWS 300x400	each	87.00	85.00	45.00	217.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Exterior																						
259	Providing and fixing of main entrance sign , made of laser cut 2mm ,304 grade brush Stainless steel,and letters to be laser cut in black acylic partially inserted in SS cut outs, the plate to be fixed on existing wall with the help of SS studs																						
	1200X2400	each	2.00	2.00	1.00	5.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing of exterior signage, to be fixed on the Wall mount with the help of MS framework, Signage to be made of MS pipe frame work, cladded with 3mm Aluminium composite panel, duly cut by CNC router, and the letters to be laser cut,10mm casted clear acrylic,inserted in a cut out fitted on 4 mm 040 casted acrylic, the letters front to be 3M day and night electrocut vinyl, The signage shall illuminated with back lit LED, of PHILLIPS/GE make of atleast 5Yrs gurantee, (certificate to be provided, by the makers of LED), complete in all respects																						
260	organisation name in english 14000X560	each	1.00	1.00	0.00	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
261	organisation name in Local Language 14000X560	each	1.00	1.00	0.00	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
262	organisation name in english& Local Language in Main Entrance 14000X1200	each	1.00	1.00	0.00	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
263	Emergency Name Board in Main Entrance 9400 X 1200			1.00		1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
264	Emergency Name Board in Building 13000X460	each	1.00	1.00		2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
265	LOGO 2000 Dia	each	2.00	2.00	1.00	5.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
266	LOGO in Main Building 560 Dia	each	1.00	1.00		2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
267	organisation name in english& Local Language in Main building 13500X975	each	0.00	0.00	1.00	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
268	organisation name in english& Local Language in Main Entrance 15000X1200	each	0.00	0.00	1.00	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
269	Emergency Name Board in Building 8400X975	each	0.00	0.00	1.00	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing prohibition signage,made of aluminium composite panel, and all text and pictograms as screen printed and malamine coated, all fixtures in 304 grade SS, all design as per architects approval.																						
270	DEPARTMENT NAME PLATE 250X1000	each	11.00	11.00	11.00	33.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
271	MAIN DIRECTORY EXTERIOR with frame and 2 supporting posts 1200X2400	each	3.00	3.00	1.00	7.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
272	PARKING with frame and post 600x600	each	9.00	9.00	7.00	25.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
273	NO PARKING with frame and post 600x500	each	7.00	7.00	4.00	18.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
274	DIRECTION ARROWS EXTERIOR with frame and post 300x400	each	7.00	7.00	13.00	27.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Sub Haed 20 : Horticulture																						
	Grass Areas																						
275	Mixing earth and sludge or manure in the required proportion specified or directed by the Officer-in-charge	cum	1290.00	379.00	522.90	2191.90				-	-	-	-	-	-	-	-	-	-	-	-	-	-
276	Flooding the ground with water including making kiaries and dismantling the same.	sqm	4300.00	1262.00	1743.00	7305.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
277	Fine dressing the ground	sqm	4300.00	1262.00	1743.00	7305.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
278	Grassing with 'Selection no 1' grass including watering and maintenance of the lawn till the grass forms a thick lawn free from weeds and fit for mowing, including supplying good earth if needed. - In rows 5 cm apart in both directions	sqm	4300.00	1262.00	1743.00	7305.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	TREES																						
	Pit Preparation																						
	Digging holes in ordinary soil and refilling the same with the excavated earth mixed with manure or sludge in the ratio of 2:1 by volume (2 parts of stacked volume of earth after reduction by 20% : 1 part of stacked volume of manure after reduction by 8%) flooding with water, dressing including removal of rubbish and surplus earth, if any, with all leads and lifts (cost of manure, sludge or extra good earth if needed to be paid for separately).																						
279	Holes 1.2 m dia and 1.2 m deep	each	47.00	3.00	23.00	73.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
280	Holes 90 cm dia, and 90 cm deep	each	159.00	4.00	785.00	948.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and stacking																						

SL. no	Description of Item	Unit	Quantity				Rate			Amount												
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total			
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	
318	75mm bend	each	84.00	84.00	84.00	252.00				-	-	-	-	-	-	-	-	-	-	-	-	-
319	110 mm bend	each	210.00	210.00	246.00	666.00				-	-	-	-	-	-	-	-	-	-	-	-	-
	Shoe (Plain)																					
320	75 mm Shoe	each	84.00	84.00	84.00	252.00				-	-	-	-	-	-	-	-	-	-	-	-	-
321	110 mm Shoe	each	210.00	210.00	246.00	666.00				-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing unplasticised -PVC pipe clips of approved design to unplasticised - PVC rain water pipes by means of 50x50x50 mm hard wood plugs, screwed with M.S. screws of required length, including cutting brick work and fixing in cement mortar 1:4 (1 cement : 4 coarse sand) and making good the wall etc. complete.																					
322	75 mm	each	168.00	168.00	168.00	504.00				-	-	-	-	-	-	-	-	-	-	-	-	-
323	110 mm	each	420.00	420.00	492.00	1332.00				-	-	-	-	-	-	-	-	-	-	-	-	-
324	Providing and fixing to the inlet mouth of rain water pipe cast iron grating 15 cm diameter and weighing not less than 440 grams.	each	49.00	49.00	55.00	153.00				-	-	-	-	-	-	-	-	-	-	-	-	-
	Sub Head 23 : Sanitary Installations																					
	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast iron P or S trap, 10 Litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required:																					
325	White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests.	each	35.00	35.00	44.00	114.00				-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 Litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :																					
326	W.C. pan with ISI marked white solid plastic seat and lid	each	110.00	110.00	121.00	341.00				-	-	-	-	-	-	-	-	-	-	-	-	-
327	Providing and fixing white vitreous china extended wall mounting water closet of size 780x370x690 mm of approved shape including providing & fixing white vitreous china cistern with dual flush fitting,of flushing capacity 3 litre/ 6 litre (adjustable to 4 litre/ 8 litres),including seat cover, and cistern fittings, nuts, bolts and gasket etc complete.	each	30.00	30.00	50.00	110.00				-	-	-	-	-	-	-	-	-	-	-	-	-
328	Providing and fixing floor mounted, white vitreous china single piece, double traps syphonic water closet of approved brand/make, shape, size and pattern including integrated white vitreous china cistern of capacity 10 litres with dual flushing system, including all fittings and fixtures with seat cover, cistern fittings, nuts, bolts and gasket etc including making connection with the existing P/S trap, complete in all respect as per directions of Engineer-in-Charge.	each	35.00	35.00	39.00	109.00				-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:									-	-	-	-	-	-	-	-	-	-	-	-	-
329	White Vitreous China Surgeon type wash basin of size 660x460 mm with a pair of 15 mm C.P. brass pillar taps with elbow including operated levers	each	91.00	91.00	330.00	512.00				-	-	-	-	-	-	-	-	-	-	-	-	-
330	Providing and fixing wash basin with C.I. brackets, 15 mm dia CP Brass single hole basin mixer of approved quality and make, including painting of fittings and brackets, cutting and making good the walls wherever required:- (a) White Vitreous China Wash basin size 550x400 mm with a 15 mm CP Brass single hole basin mixer	each	201.00	201.00	200.00	602.00				-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
331	Washbasin Oval shape (T-2): Providing and fixing white vitreous china Table top wash basin size - 610*460*140mm, installed above granite / marble counter with 15 mm C.P. brass basin pillar tap, 32mm C.P. brass waste coupling of standard pattern, including 2 nos. angle valve with riser pipes, connectors, adapters, all fittings etc. cutting and making good the walls/slabs wherever required.	each	102.00	102.00	146.00	350.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
332	Flat back large urinals: Providing and fixing starwhite vitreous China flat back large urinals size - 375x390x590mm with self closing flush valve fittings, standard size C.P. brass flush pipe, spreaders with unions and clamps (all in C.P. brass) with waste fitting as per IS : 2556, and other couplings in C.P. brass, including all necessary fittings & fixtures complete with painting and making good the walls and floors wherever required.	each	43.00	43.00	63.00	149.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS: 13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required :									-	-	-	-	-	-	-	-	-	-	-	-	-	-
333	Kitchen sink with drain board 510x1040 mm bowl depth 200 mm	each	47.00	47.00	28.00	122.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing white vitreous china laboratory sink with C.I. brackets, C.P. brass chain with rubber plug, 40 mm C.P. brass waste and 40mm C.P. brass trap with necessary C.P. brass unions complete, including painting of fittings and brackets, cutting and making good the wall wherever required :									-	-	-	-	-	-	-	-	-	-	-	-	-	-
334	Size 450x300x150 mm	each	12.00	12.00	23.00	47.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
335	Size 600x450x200 mm	each	34.00	34.00	34.00	102.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
336	Providing and fixing CP Brass 32mm size Bottle Trap of approved quality & make and as per the direction of Engineer-in-charge.	each	201.00	201.00	200.00	602.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.									-	-	-	-	-	-	-	-	-	-	-	-	-	-
337	Semi rigid pipe 40 mm dia	each	12.00	12.00	25.00	49.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
338	Flexible Pipe 32 mm dia -	each	91.00	91.00	330.00	512.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing PTMT Bottle Trap for Wash basin and sink.									-	-	-	-	-	-	-	-	-	-	-	-	-	-
339	Bottle trap 31mm single piece moulded with height of 270 mm, effective length of tail pipe 260 mm from the centre of the waste coupling, 77 mm breadth with 25 mm minimum water seal, weighing not less than 260 gms	each	102.00	102.00	146.00	350.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
340	Bottle trap 38 mm single piece moulded with height of 270 mm, effective length of tail pipe 260 mm from the centre of the waste coupling, 77 mm breadth with 25 mm minimum water seal, weighing not less than 263 gms	each	34.00	34.00	34.00	102.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
341	C.P.Brass Sink Cock: Supplying, fixing testing and commissioning of C.P.Brass Sink cock With Extended Swivel Spout (Wall Mounted) type with all fittings and fixtures complete of approved quality conforming to IS standards.	each	93.00	93.00	85.00	271.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
342	Two way Bib cock: Supplying, fixing testing and commissioning of C.P.Brass two way bib cock with wall flange and aerator type with all fittings and fixtures complete of approved quality conforming to IS standards	each	175.00	175.00	210.00	560.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
343	C.P.Brass Health faucet : Supply, fixing, testing and commissioning of HAND SHOWER (Health Faucet) near EWC consisting of lrms. Long C.P. flexible tube with wall hook with all fittings and fixtures complete conforming to IS standards.	each	175.00	175.00	210.00	560.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount												
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total			
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	
344	Wall mixer 2 in 1: Supply, fixing, testing and commissioning of Wall Mixer 2 in 1 with Provison For Over Head Shower With 115mm Long Bend Pipe complete and wall flanges including bath spout, concealed body & exposed parts, connectors, adopters, fittings, fixtures, complete of approved design etc.	each	55.00	55.00	36.00	146.00				-	-	-	-	-	-	-	-	-	-	-	-	-
345	Providing and fixing PTMT towel ring trapezoidal shape 215 mm long, 200 mm wide with minimum distances of 37 mm from wall face with concealed fittings arrangement of approved quality and colour, weighing not less than 88 gms	each	110.00	110.00	99.00	319.00				-	-	-	-	-	-	-	-	-	-	-	-	-
346	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour. 600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms.	each	110.00	110.00	99.00	319.00				-	-	-	-	-	-	-	-	-	-	-	-	-
347	Providing and fixing of star white EWC and low level cistern of 6 Litre capacity , angle valve with riser pipe with fittings and seat cover and including of wall hung compact washbasin of size 46x36cm fixed to wall with brackets, 1 no.of angle valve with riser pipes, connectors, adopters, all fittings and one hinged rail of 76cm with one pair of mounting brackets and 5no grab rails of 60cm for support, faucet with spatula lever (without Bottle trap) with all fittings and fixtures complete, angle valve, riser / connector pipe, nuts, bolts, connector, adopter, check nuts etc including cutting and making good the walls and floors wherever required. (FOR PHYSICALLY CHALLENGED TOILET)	each	17.00	17.00	7.00	41.00				-	-	-	-	-	-	-	-	-	-	-	-	-
348	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	each	110.00	110.00	102.00	322.00				-	-	-	-	-	-	-	-	-	-	-	-	-
349	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing: Rectangular shape 1500x450 mm	each	37.00	37.00	52.00	126.00				-	-	-	-	-	-	-	-	-	-	-	-	-
350	Providing and fixing M.S. holder-bat clamps of approved design toCentrifugally cast spun iron/cast iron (spun) pipe embedded in and including cement concrete blocks 10x10x10cm of 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) including cost of cutting holes and making good the walls etc. :									-	-	-	-	-	-	-	-	-	-	-	-	-
351	For 100 mm dia. Pipe	each	329.00	329.00	315.00	973.00				-	-	-	-	-	-	-	-	-	-	-	-	-
351	For 75 mm dia. Pipe	each	413.00	413.00	385.00	1211.00				-	-	-	-	-	-	-	-	-	-	-	-	-
352	Cutting chases in brick masonry walls for following diametre sand cast iron/ centrifugally cast (spun) iron pipes and making good the same with cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 12.5 mm nominal size), including necessary plaster and pointing in cement mortar 1:4 (1 cement : 4 coarse sand) :									-	-	-	-	-	-	-	-	-	-	-	-	-
352	100 mm dia	metre	329.00	329.00	315.00	973.00				-	-	-	-	-	-	-	-	-	-	-	-	-
353	75 mm dia	metre	413.00	413.00	385.00	1211.00				-	-	-	-	-	-	-	-	-	-	-	-	-
354	Level Indicator : Supply and fixing in position the following Water Level Indicator with Tube connected to the tank at the side, pressure limit of 10 Kg / Cm2 and including including fittings, connectors, adopters etc. all effective proper connections.	each	10.00	10.00	7.00	27.00				-	-	-	-	-	-	-	-	-	-	-	-	-
355	Floor trap Grating : Supplying and fixing of Square & Round (125x125mm) aproximately Stainless Steel grating including GI hopper for connection of wash basin/ urinal with fittings, connectors & adopters.and all fittings etc., complete.	each	481.00	481.00	583.00	1545.00				-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
356	Floor Clean out : Providing and fixing of Stainless Steel floor clean out cover Square & Round (125x125mm) approximately plug with suitable for CI pipes in Toilet areas including fittings, flanges, connector, GI coupling etc.	each	50.00	50.00	87.00	187.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
357	Providing,Fixing wall mounted Double Coat hook on door complete.	each	145.00	145.00	295.00	585.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Sub Head 24 : Water Supply									-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.																						
	Internal work - Exposed on wall									-	-	-	-	-	-	-	-	-	-	-	-	-	-
358	15 mm nominal outer dia Pipes	metre	564.00	564.00	390.00	1518.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
359	20 mm nominal outer dia Pipes	metre	121.00	121.00	121.00	363.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
360	25 mm nominal outer dia Pipes	metre	240.00	240.00	210.00	690.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
361	32 mm nominal outer dia Pipes	metre	140.00	140.00	132.00	412.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
362	40 mm nominal outer dia Pipes	metre	280.00	280.00	233.00	793.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
363	50 mm nominal outer dia Pipes	metre	165.00	165.00	137.00	467.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, pressure rating Max 6Kg/cm2 and conforming to IS 15778, including all kind of pipe supports (GI fabricated or concrete pedestal) CPVC plain & brass threaded fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge.																						
	Internal work - Exposed on wall									-	-	-	-	-	-	-	-	-	-	-	-	-	-
364	65 mm nominal outer dia Pipes	metre	180.00	180.00	150.00	510.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
365	80 mm nominal outer dia Pipes	metre	240.00	240.00	220.00	700.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
366	100 mm nominal outer dia Pipes	metre	240.00	240.00	220.00	700.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge.																						
	Concealed work, including cutting chases and making good the walls etc.									-	-	-	-	-	-	-	-	-	-	-	-	-	-
367	15 mm nominal outer dia Pipes	metre	555.00	555.00	390.00	1500.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
368	20 mm nominal outer dia Pipes	metre	2347.00	2347.00	1761.00	6455.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
369	25 mm nominal outer dia Pipes	metre	357.00	357.00	566.00	1280.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
370	32 mm nominal outer dia Pipes	metre	193.00	193.00	399.00	785.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing insulation for hot water piping with elastomeric Class - O Nitrile Rubber Tubular Insulation & the same insulation with aluminum cladding 22 gauge for hot water piping. Before applying insulation, all pipe work and fittings shall be brushed and cleaned. Dust, dirt, mortar and oil shall be removed as per direction of Engineer-in-Charge.																						
371	20 mm tube inner dia Pipes	metre	325.00	325.00	290.00	940.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
372	25 mm tube inner dia Pipes	metre	25.00	25.00	65.00	115.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
373	35 mm tube inner dia Pipes	metre	31.00	31.00	45.00	107.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
374	42 mm tube inner dia Pipes	metre	110.00	110.00	10.00	230.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc.																						
	Internal work - Exposed on wall									-	-	-	-	-	-	-	-	-	-	-	-	-	-
375	25 mm nominal outer dia Pipes	metre	75.00	75.00	75.00	225.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
376	32 mm nominal outer dia Pipes	metre	75.00	75.00	75.00	225.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
377	40 mm nominal outer dia Pipes	metre	30.00	30.00	30.00	90.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
378	50 mm nominal outer dia Pipes	metre	30.00	30.00	30.00	90.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc.																						
379	25 mm dia nominal inner dia .Pipes	metre	20.00	20.00	95.00	135.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
380	32 mm dia nominal inner dia .Pipes	metre	20.00	20.00	70.00	110.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
381	40 mm dia nominal inner dia .Pipes	metre	1330.00	1330.00	560.00	3220.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
382	50 mm dia nominal inner dia .Pipes	metre	185.00	185.00	20.00	390.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
383	65 mm dia nominal inner dia .Pipes	metre	300.00	300.00	160.00	760.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
384	80 mm dia nominal inner dia .Pipes	metre	900.00	900.00	210.00	2010.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
410	With common burnt clay F.P.S.(non modular) bricks of class designation 7.5	each	11.00	11.00	11.00	33.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Painting G.I. pipes and fittings with synthetic enamel white paint with two coats over a ready mixed priming coat, both of approved quality for new work :																						
411	15 mm diametre pipe	metre	0.00	0.00	0.00	0.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
412	20 mm diametre pipe	metre	0.00	0.00	0.00	0.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
413	25 mm diametre pipe	metre	75.00	75.00	75.00	225.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
414	32 mm diametre pipe	metre	75.00	75.00	75.00	225.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
415	40 mm diametre pipe	metre	30.00	30.00	30.00	90.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
416	50 mm diametre pipe	metre	30.00	30.00	30.00	90.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Painting G.I. pipes and fittings with two coats of anti-corrosive bitumastic paint of approved quality																						
417	25 mm diametre pipe	metre	20.00	20.00	95.00	135.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
418	32 mm diametre pipe	metre	20.00	20.00	70.00	110.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
419	40 mm diametre pipe	metre	1330.00	1330.00	560.00	3220.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
420	50 mm diametre pipe	metre	185.00	185.00	20.00	390.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
421	65 mm diametre pipe	metre	300.00	300.00	160.00	760.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
422	80 mm diametre pipe	metre	900.00	900.00	210.00	2010.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and filling sand of grading zone V or coarser grade, allround the G.I. pipes in external work :																						
423	25mm diametre pipe	metre	20.00	20.00	95.00	135.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
424	32mm diametre pipe	metre	20.00	20.00	70.00	110.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
425	40mm diametre pipe	metre	1330.00	1330.00	560.00	3220.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
426	50 mm diametre pipe	metre	185.00	185.00	20.00	390.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
427	65 mm diametre pipe	metre	300.00	300.00	160.00	760.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
428	80 mm diametre pipe	metre	900.00	900.00	210.00	2010.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
428	100 mm diametre pipe	metre	0.00	0.00	0.00	0.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) :																						
429	15 mm nominal bore	each	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
430	20 mm nominal bore	each	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
431	25 mm nominal bore	each	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
432	32 mm nominal bore	each	75.00	75.00	80.00	230.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
433	40 mm nominal bore	each	35.00	35.00	21.00	91.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
434	50 mm nominal bore	each	90.00	90.00	25.00	205.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
434	65 mm nominal bore	each	20.00	20.00	20.00	60.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
435	80 mm nominal bore	each	20.00	20.00	20.00	60.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing C.I. double acting air valve of approved quality with bolts, nuts, rubber insertions etc. complete (The tail pieces,tapers etc if required will be paid separately.																						
436	50 mm nominal bore	each	4.00	4.00	4.00	12.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
437	80 mm nominal bore	each	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supply and fixing in position the following lever operated, full flow, quarter turn, Ball Valves of Forged Brass body and chrome plated brass ball with chrome plated steel handle with PVC sleeve and PTFE seal tested to 25 Kg / Cm2 pressure rating, conforming to BS : 5159 manufacturing standards,including fittings, connectors, adopters etc.all unions and effective proper connections.																						
438	15 mm nominal bore	each	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
439	20 mm nominal bore	each	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
440	25 mm nominal bore	each	30.00	30.00	30.00	90.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
441	32 mm nominal bore	each	10.00	10.00	10.00	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
442	40 mm nominal bore	each	25.00	25.00	25.00	75.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
443	50 mm nominal bore	each	10.00	10.00	10.00	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supply and fixing in position the following lever operated, full flow, Butterfly Valves of Cast Iron body, Ductile Iron Disc, with Nitrile integrally moulded rubber and pressure rating of Body- 10 Kg / Cm2 , Seat - 16 Kg / Cm2 conforming to IS :13095 manufacturing standards, including fittings, GI flanges, connectors, adopters etc. all unions and effective proper connections.																						
444	65 mm nominal bore	each	10.00	10.00	10.00	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
445	80 mm nominal bore	each	15.00	15.00	15.00	45.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
446	100 mm nominal bore	each	15.00	15.00	15.00	45.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
470	Supplying, fixing and commissioning of approved make & suitable model for Water Dispenser with purified normal hot and cold water outlets including all fittings and accessories complete.,	each	28.00	28.00	30.00	86.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
471	Providing, fixing, testing and commissioning of R.O. plant 1000 ltrs. Per hour flow rate having capacity to treat the raw water having TDS 1200 ppm and not less than 40%. The treated water should have TDS less than 100 ppm and hardness less than 50 ppm. The operating voltage to 230 volt AC +/- 10% alongwith required capacity pump and solenoid valves, dry run protection of pump,automatic tank level control, inbuilt auto flush timer for periodic flushing of membranes,hydro pneumatic tank, over voltage and over current protection with switch mode power supply system complete in all respects.,	each	2.00	2.00	2.00	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
472	Providing & fixing hot dip galvanized proprietary factory fabricated supports including GI/SS fasteners, GI nut, bolts & washers, GI clamps, etc complete including cutting & chasing in brick / concrete wall and making same good.	kg	325.00	325.00	325.00	975.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
473	Providing and laying Rubber Sheet of 6mm thick below polyethylene water storage tank	each	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
474	Providing, fixing, testing and commissioning of Booster pump Electro-coated cast iron parts, High efficient motor with Horizontal multistage centrifugal pump, power 0.9KW and flow of 2.4 cum/hr switch mode power supply system, including, connectors, fittings etc complete in all respects.,	each	10.00	10.00	10.00	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
Sub Head 25 : Drainage																							
	Providing, laying and jointing glazed stoneware pipes class SP-1 with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc. complete:																						
475	150 mm diameter	metre	25.00	25.00	25.00	75.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
476	200 mm diameter	metre	30.00	30.00	30.00	90.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
477	250 mm diameter	metre	60.00	60.00	60.00	180.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) all-round S.W. pipes including bed concrete as per standard design:																						
478	150 mm diameter S.W. pipe	cum	10.00	10.00	10.00	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
479	200 mm diameter S.W. pipe	cum	10.00	10.00	10.00	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
480	250 mm diameter S.W. pipe	cum	10.00	10.00	10.00	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) up to haunches of S.W. pipes including bed concrete as per standard design :																						
481	150 mm diameter S.W. pipe / RCC pipe	metre	10.00	10.00	10.00	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
482	200 mm diameter S.W. pipe / RCC pipe	metre	10.00	10.00	10.00	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
483	250 mm diameter S.W. pipe / RCC pipe	metre	10.00	10.00	10.00	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supplying and fixing in position best quality uPVC soil / waste pipes of various dia IS 13592:1992 - Type-B including UPVC specials connecting to the UPVC soil stacks and providing leak proof joints using adhesives including fixing to the wall with specials, MS clamp, teak wood plugs, brass screws, etc., and making connection to all sanitary fittings, dismantling masonry / RCC works wherever found necessary and making the good dismantled portion to the original condition, including testing for any leakages, etc., complete complying with standard specifications.																						
484	40mm Dia	metre	300.00	300.00	320.00	920.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
485	75mm Dia	metre	798.00	798.00	1100.00	2696.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
486	110mm Dia	metre	452.00	452.00	450.00	1354.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing square-mouth S.W. gully trap class SP-1 complete with C.I. grating brick masonry chamber with water tight C.I. cover with frame of 300 x300 mm size (inside) the weight of cover to be not less than 4.50 Kg and frame to be not less than 2.70 Kg as per standard design :																						
	180x150 mm size P type									-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
487	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	each	140.00	140.00	110.00	390.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :																						
488	150 mm diametre RCC pipe	metre	50.00	50.00	50.00	150.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
489	250 mm diametre RCC pipe	metre	50.00	50.00	50.00	150.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
490	300 mm diametre RCC pipe	metre	60.00	60.00	60.00	180.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Constructing brick masonry manhole in cement mortar 1:4 (1 cement : 4 coarse sand) with R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 coarse sand (zone- III) : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand (zone- III) : 8 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design :																						
	Inside size 90 x 80 cm and 45 cm deep including CI cover with frame (light duty) 455 x 610mm internal dimensions total weight of cover and frame to be not less than 38 Kg. (weight of cover 23 Kg. and weight of frame 15 Kg.), with FPS bricks with class designation 7.5																						
491	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	each	40.00	40.00	20.00	100.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Inside size 120x90 cm and 90 cm deep including C.I. cover with frame (medium duty) 500 mm internal diametre, total weight of cover and frame to be not less than 116 Kg (weight of cover 58 Kg and weight of frame 58 Kg) :																						
492	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	each	10.00	10.00	10.00	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Extra for depth for manholes: Size 90 x 80 cm																						
493	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	metre	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Size 120x90 cm																						
494	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	metre	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Constructing brick masonry circular type manhole 0.91 m internal dia at bottom and 0.56m dia at top in cement mortar 1:4 (1 cement :4 coarse sand), in side cement plaster 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with a floating coat of neat cement, foundation concrete 1:3:6 mix (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nosminal size), and making necessary channel in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nosminal size) finished with a floating coat of neat cement, all complete as per standard design :																						
	0.91 m deep with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560 mm internal diamr conforming to I.S. 12592, total weight of cover and frame to be nost less than 182 Kg., fixed in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nosminal size) including centering, shuttering all complete. (Excavation, foot rests and 12mm thick cement plaster at the external surface shall be paid for separately):																						
495	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	each	25.00	25.00	25.00	75.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Extra depth for circular type manhole 0.91m internal dia (at bottom) beyond 0.91 m to 1.67 m																						
496	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	metre	15.00	15.00	15.00	45.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
513	Supplying, filling, spreading & leveling stone boulders of size range 5 cm to 20 cm, in recharge pit, in the required thickness, for all leads & lifts, all complete as per direction of Engineer-in-charge.	cum	48.00	48.00	48.00	144.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
514	Supplying, filling, spreading & leveling gravels of size range 5 mm to 10 mm, in the recharge pit, over the existing layer of boulders, in required thickness, for all leads & lifts, all complete as per direction of Engineer-in-charge.	cum	8.00	8.00	8.00	24.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
515	Supplying, filling, spreading & leveling coarse sand of size range 1.5mm to 2 mm in recharge pit, in required thickness over gravel layer, for all leads & lifts, all complete as per direction of Engineer-in-charge.	cum	8.00	8.00	8.00	24.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
516	Gravel packing in tubewell construction in accordance with IS: 4097, including providing gravel fine/ medium/ coarse, in required gradin & sizes as per actual requirement, all complete as per direction of Engineer-in-charge.	cum	161.00	161.00	161.00	483.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
517	Providing and fixing factory made precast RCC perforated drain covers, having concrete of strength not less than M-25, of size 1000 x 450x50mm, reinforced with 8 mm dia four nos longitudinal & 9 nos cross sectional T.M.T. hoop bars, including providing 50 mm dia perforations @ 100 to 125 mm c/c, including providing edge binding with M.S. flats of size 50 mm x 1.6 mm complete, all as per direction of Engineer-in-charge.	each	48.00	48.00	48.00	144.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
518	Development of tube well in accordance with IS : 2800 (part I) and IS:11189, to establish maximum rate of usable water yield without sand content (beyond permissible limit), with required capacity air compressor, running the compressor for required time till well is fully developed, measuring yield of well by "V" notch method or any other approved method, measuring static level & draw down etc. by step draw down method, collecting water samples & getting tested in approved laboratory, i/c disinfection of tubewell, all complete, including hire & labour charges of air compressor, tools & accessories etc., all as per requirement and direction of Engineer-in-charge.	hour	8.00	8.00	8.00	24.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
519	Providing and fixing suitable size threaded mild steel cap or spot welded plate to the top of bore well housing/ casing pipe, removable as per requirement, all complete for borewell of: 200 mm dia	each	2.00	2.00	2.00	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
520	Providing and fixing M.S. clamp of required dia to the top of casing/ housing pipe of tubewell as per IS: 2800 (part I), including necessary bolts & nuts of required size complete. 150 mm clamp	each	2.00	2.00	2.00	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
521	Providing and fixing bail plug / bottom plug of required dia at the bottom of the pipe assembly as per IS: 2800 (Part-1). 150 mm dia	each	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
522	Supply, installation testing & commissioning of submersible pumping set suitable to operate on 410 volts 3 phase 50 HZ A.C. power supply including water proof joint free cable, motor control panel, 50 mm dia, G.I. pipe (medium class) column with fittings, clamps etc. complete in all respect as per details given below : (For Borewell) Discharge 300 LPM. Head 50 m HP/Load 6.0 (Approx)	each	2.00	2.00	2.00	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
523	Supplying and fixing Single headed external yard hydrant valve with 1 nos 63 mm dia instantaneous FM Gunmetal/Stainless Steel coupling and cast iron wheel, ISI marked, conforming to IS 5290 (type A) with blank Gunmetal/Stainless Steel cap and chain as required : Single headed Gunmetal	each	26.00	26.00	26.00	78.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
549	Earthing with G.I. earth plate 600mm x 600mm x 6mm thick including accessories, and proving masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	set	6.00	6.00	6.00	18.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
550	Providing and fixing 25mm x 5mm G.I. Strip in 40mm dia G.I pipe from earth electrode including connection with G.I. nut, bolt, spring, washer excavation and refilling etc. as required.	metre	60.00	60.00	60.00	180.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
551	Providing and fixing 25mm x 5mm G.I. strip on surface or in recess for connections etc. as required.	metre	60.00	60.00	60.00	180.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supplying and laying on one number XLPE insulated PVC sheathed Aluminium conductor armoured UG cable of 1.1 KV grade conforming to IS 7098/1988 with upto date ammendment of following size in the existing RCC/ HUME/ METAL/ GI/ CI/ Stoneware/ DWC pipe/ masonry open duct/ cable tray/ open in air etc. as required.																						
552	4 core, 25 sqmm. Aluminium armoured	metre	60.00	60.00	60.00	180.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
553	3.5 core, 50 sqmm. Aluminium armoured	metre	80.00	80.00	80.00	240.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
554	3 core, 10 sqmm. Aluminium armoured	metre	70.00	70.00	70.00	210.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
555	Supply and fixing in position 1m wide insulation mat made of elastomeric polymers material (Class - A) of 415V grade as per IS 15642-2006. Thickness of insulation mat shall be not less than 2mm to withstand 1.1 KV dielectric strength as per IS 15652:2006. It should be complete as per specifications and directions of Engineer-in-charge.	metre	20.00	20.00	20.00	60.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Sub Head 30 : Pipes & Accessories																						
	Providing laying, testing & commissioning of 'C' class heavy duty MS Pipe conforming to IS 1239/3589 i/c fittings like elbows, tees, flanges, tapers, nuts bolts, gaskets etc. in ground including welding, excavation & providing cement concrete blocks as supports, anticorrosive treatment with coaltar/asphalt tape as per IS 10221, refilling the trench etc. of following sizes complete as required.(For Underground)									-	-	-	-	-	-	-	-	-	-	-	-	-	-
556	200 mm. dia (wall thickness = 6.3 mm)	metre	30.00	30.00	30.00	90.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
557	150 mm. Dia	metre	20.00	20.00	20.00	60.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing, laying, testing & commissioning of 'C' class heavy duty MS pipe conforming to IS 3589/IS 1239 including Welding, fittings like elbows, tees, flanges, tapers, nuts bolts, gaskets etc. and fixing the pipe on the wall/ceiling with suitable clamp/support frame and painting with two or more coats of synthetic enamel paint of required shade complete as required. (Plant Room piping/Vertical Riser/Downcomer/Floor)																						
558	25 mm dia	metre	1650.00	1650.00	1600.00	4900.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
559	32 mm dia	metre	75.00	75.00	100.00	250.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
560	40 mm dia	metre	500.00	500.00	850.00	1850.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
561	50 mm dia	metre	450.00	450.00	500.00	1400.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
562	65 mm dia	metre	350.00	350.00	400.00	1100.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
563	80 mm dia	metre	350.00	350.00	325.00	1025.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
564	100 mm dia	metre	400.00	350.00	375.00	1125.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
565	150 mm dia	metre	995.00	750.00	450.00	2195.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supplying and fixing single headed internal hydrant valve with instantaneous Gunmetal/Stainless Steel coupling of 63 mm dia with cast iron wheel ISI marked conforming to IS 5290 (Type -A) with blank Gunmetal/Stainless Steel cap and chain as required :																						
566	Single headed Gunmetal	set	0.00	0.00	0.00	0.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
567	Single headed Stainless Steel	set	35.00	35.00	35.00	105.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supplying and fixing Single headed external yard hydrant valve with 1 no 63 mm dia instantaneous FM Gunmetal/Stainless Steel coupling and cast iron wheel, ISI marked, conforming to IS 5290 (type A) with blank Gunmetal/Stainless Steel cap and chain as required :																						
568	Single headed Gunmetal	set	10.00	10.00	10.00	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
569	Single headed Stainless Steel	set	0.00	0.00	0.00	0.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
610	150 mm dia	nos.	6.00	6.00	6.00	18.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
611	80 mm dia	nos.	4.00	4.00	4.00	12.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
612	100 mm dia	nos.	4.00	4.00	4.00	12.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supply, fixing, testing and commissioning of screwed type brass/bronze lever operated ball valve of full flow with stainless steel ball (AISI 304 & spindle AISI 410) with setting & gland of superior quality having minimum working pressure of 16 Kg/sqcm.																							
613	25 mm Dia	nos.	35.00	35.00	35.00	105.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
614	Providing and fixing 25 mm dia inspection & testing assembly with gun metal ball valve, gun metal sight glass ,Reducer ,union, G.I PIPE. connection to drain pipe/riser.	set	21.00	21.00	21.00	63.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
615	Providing & fixing cast iron 100 mm dia. Foot valve with nuts, bolts, 1.5 mm thick CAF gasket complete with all accessories (To be provided into UG Fire Water Tanks).	each	2.00	2.00	2.00	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing, fixing water flow metre on test line complete with all accessories for flow indication , monitoring & testing of fire pumps with bypass arrangement including piping & bypass valves.									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
616	150 mm dia	each	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
617	Supply and fixing of 4 nos G.I round bottom FIRE BUCKET of 9 LTR. Capacity field with sand including proper supporting /mounting arrangement MS Angle Iron Frame painted by fire red colour over 2 coats of red oxide paint and written with white paint FIRE complete in all respects as per direction of Engineer Incharge .	each	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Sub Head 31 : Fire Extinguisher																							
	Providing, storing, handling, shifting, installation, testing and commissioning of halon free portable fire Extinguishers as described below:																							
	Concealed work, including cutting chases and making good the walls etc.																							
618	Providing and fixing of 4.5 Kg. carbon-di-oxide type fire extinguishers consisting of welded M.S. cylindrical body, squeeze lever discharge valve fitted with pressure indicating guase internal discharge tube 30 cms long high pressure discharge hose, discharge nozzle, suspension bracket conforming to IS:15683 finished externally with re enamel paint and fixed to wall with brackets complete with internal charge.	nos.	11.00	11.00	11.00	33.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
619	Providing and fixing 6.0 Kg. ABC Powder type fire extinguishers consisting of welded M.S. cylindrical body, squeeze lever discharge valve fitted with pressure indicating guase internal discharge tube 30 cms long high pressure discharge hose, discharge nozzle, suspension bracket conforming to IS:15683 finished externally with re enamel paint and fixed to wall with brackets complete with internal charge.	nos.	90.00	90.00	120.00	300.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
620	Water CO2 type of 9 lit.Fire Extinguisher with Gun metal cap and nozzle complete in all respects including wall suspension bracket and conforming to IS: 15683.	nos.	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
621	Providing, fixing, testing and commissioning of 50 Litres (trolley mounted) Mechanical Foam type Fire Extinguisher. In HP Mild Steel Cylinders ISI marked TAC approved fitted with pressure indicating gauge, internal tube, squeeze lever type valve fully charged complete in all respects including wall suspension bracket / trolley mounted and conforming to IS:910 .	nos.	3.00	3.00	3.00	9.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
622	Providing, fixing, testing and commissioning of CO2 type Fire Extinguisher of capacity 22.5 Kg filled with Co2 Gas as per IS 15222 with controll discharge mechanism fitted with Hose, Horn & TROLLEY confirms to IS 2878 bearing ISI mark. Co2 Cylinder as per IS 7285.	nos.	3.00	3.00	3.00	9.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
623	Providing and fixing 2 Kg capacity clean agent-HFC 236FA Stored Pressure type fire extinguisher ISI marked under IS:15683 complete with imported manufactured by 3M, with Zero Ozone Depelition Potential and Very Low Global Warming Potential of 1 with 20 Years Blue Sky Warantee against any regulatory Bans and Restrictions.	nos.	10.00	10.00	10.00	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
624	Providing and fixing Fire related signages printed on photoluminescent U1000 aluminium sheet of 1.0 mm (+-10%) containing Lumigen II as base chemical, covered under UV stablized coating and of appropriate size including fixing on wall, door, ceiling etc. with proper clamps, hangers, cleats, anchor fasteners etc.	Square Inch	36000.00	36000.00	32400.00	104400.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
Sub Head 32 : UPS Room Gas Flooding System / Electrical Panel Flooding System																							
GAS SUPPRESSION SYSTEM																							
625	Supply Installation testing and commissioning of FK-5-1-12 based fire suppression system. The fire suppression system shall include and not be limited to gas release control panel, CCOE approved seamless cylinders, discharge valve (with solenoid or pneumatic actuator) as the case may be, discharge pipe, non-return valve and all other accessories required to provide a complete operation system meeting applicable requirements of NFPA 2001 or ISO standards and installed in compliance with all applicable requirements of the local codes and standards. The system shall be VdS or FM/UL listed. The system shall be designed with minimum design concentration of 4.2 % as applicable to Class-A & C fire. The cylinders shall be super-pressurized with dry Nitrogen to 25 bar / 34.5 bar / 42 Bar.. The FK-5-1-12 gas shall be comply with the following. UL listed.	nos	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
626	120 ltrs. Seamless CylinderCCOE Approved, complete with a safety burst disc & Safety cap	nos	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
627	EXTINGUISHING Gas agent to be filled in above Gas cylinders,	kgs	500.00	500.00	500.00	1500.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
628	Electrical cum Manual Actuator	nos	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
629	Local manual actuator	nos	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
630	2" Flexible discharge hose	nos	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
631	Discharge pressure switch, WP(2-3/4" outlet), Lat.	nos	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
632	Brass nozzle degree NPT - India	nos	30.00	30.00	28.00	88.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
633	Cylinder bracket assembly for each cylinder as per above capacity.	nos	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
634	Supply installation, testing and commissioning of C.S seamless piping and Fittings All piping shall be Schedule 40 seamless pipes complying with grade B and all fitting shall be of ASTM A-105	LOT	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
635	Supply installation, testing and commissioning of 2 Zone CONVENTIONAL Gas release panel with batteries to connect Manual abort/Release switches, multisensor detector, Hooter cum strobe.	nos	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
636	Supply installation, testing and commissioning of intelligent analog addressable photo thermal detector with base and junction box and other accessories required	nos	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
637	Supply installation, testing and commissioning of 2C x 1.5 sqmm PVC sheather armored FRLS cable with suitable clamps	metres	25.00	25.00	25.00	75.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
638	Supply installation, testing and commissioning of Manual release switch	nos	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
639	Supply installation, testing and commissioning of Manual abort switch	nos	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
640	Supply installation, testing and commissioning of addressable horn cum strobe	nos	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
641	Supply installation, testing and commissioning of RI on surface MS box having two LED,metallic cover complete.	nos	25.00	25.00	25.00	75.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
642	Modules for integrating with Fire Detection system with all connections.	nos	25.00	25.00	25.00	75.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
Electrical Panel Fire suppression System																							
642	Supply, installation of Cylinder Valve Assembly (2.5 lb / 1 Kg - capacity), Cylinder with Single Outlet Valve, F -K-5-1-12 Fire Suppression Fluid (2.5 lbs) 1 Kg, Cylinder bracket (1), Rubber Grommets - 6mm, Plastic Loop Clamps with accessories, EOL Adapter wih Pressure Guage with Accessories etc.,	nos	2.00	2.00	2.00	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
643	Supply, installation of Cylinder Valve Assembly (5 lb capacity/ 2 kgs Capacity), Cylinder with Single Outlet Valve, F-K-5-1-12, Fire Suppression Fluid (2.5 lbs) / 2 kgs Cylinder bracket (1), Rubber Grommets - 6mm, Plastic Loop Clamps with accessories, EOL Adapter wih Pressure Guage with Accessories, etc.,	nos	3.00	3.00	3.00	9.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
644	Supply, installation of Cylinder Valve Assembly (10 lb capacity/ 4 kgs Capacity), Cylinder with Single Outlet Valve, F-K-5-1-12, Fire Suppression Fluid (10 lbs) / 4 kgs Cylinder bracket (1), Rubber Grommets - 6mm, Plastic Loop Clamps with accessories, EOL Adapter wih Pressure Guage with Accessories, etc.,	nos	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
645	Supplying, installation, testing & commissioning of Heat detection tube (UL approved)	metre	120.00	120.00	120.00	360.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
646	Supplying, installation, testing & commissioning of intelligent addressable thermal detector with rate of rise cum fixed temperature thermistor complete with base as required.	nos	10.00	10.00	10.00	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
647	Providing & fixing of pressure switch in M.S. pipe line including connection etc. as required.	nos	10.00	10.00	10.00	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
648	Supply, installation of Audio Visual Alarm	nos	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Sub Head 33 : Passive Fire Stopper									-	-	-	-	-	-	-	-	-	-	-	-	-	-
	PASSIVE FIRE SYSTEM - FLOOR OPENING									-	-	-	-	-	-	-	-	-	-	-	-	-	-
649	Providing Fire stop mortar system CP 636 , with minimum 2 hours fire rating when tested in accordance with UL 1479/ASTM-E 814 standards, for horizontal openings in floors or slabs after passing service lines like cables/cable bundles, cable trays etc. The mortar shall be a light weight cementitious product and shall carry test certificate in accordance with IEC 60068-2-57:1999-11 (Environmental Testing) as per Part 2-57: Test for Vibration-Time-history method and VERTEQII for seismic zone 4. The product shall be age tested as per Dafstb and DIBT standards. The product shall carry test certificate for mold resistance rating of 0 as determined by ASTM G21-96. The product shall be age tested as per Dafstb and DIBT standards. The system shall be UL listed & classified and product shall bear the UL and FM approval logo on the packing. If none of UL test certificate comply with actual application, an EJ document prepared by a qualified personnel and based on nearest third party tested & approved systems like UL test certificates & in accordance with IFC guidelines shall be produced by manufacturer. A firestop submittal shall be produced by manufacturer , in accordance with approved passive fire protection method statement, for technical approval. Firestop installation shall be done by Hilti Accredited Firestop Speciality Contractor (HAFSC) and in accordance with Hilti guidelines and UL system test certificates or approved EJ document. Firestop Speciality Contractor needs to submit work completion certificate along with installation report through Hilti documentation Software CFS DM for periodic inspection & maintenance purpose. The gaps around inaccessible or complicated openings shall be sealed with expanding firestop foam Hilti CP 620 and shall be paid under separate heads and as mentioned below. Any report submittal with Installation pictures should be done using CFS-DM Software, which shall be charged extra.	sqm	15.00	15.00	15.00	45.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
650	Provide rodent and termite proof Fire Barriers Hilti CFS COS (Composite Sheet) system for 2 hours fire rating when tested in accordance with ASTM E 814/UL 1479 standards. The Composite Sheet 3.81 mm thick, bonded with organic/inorganic fire-resistive elastomeric #SS 304 (Stainless steel) sheet. One side it should be bonded with 26 gauge #SS 304 (Stainless steel) sheet and the other side it should be reinforced with hexagonal shaped #SS 304 (Stainless steel) wire mesh and covered with aluminum foil for the penetrants and the big opening. The small gaps left around the penetrants should be closed with Intumescent sealant FS One max of Hilti make, or with Fire rated Moldable Putty CP 619T of Hilti make, which should be soft & moldable to any shape, to give complete L Rating. This system is to seal all fire rated horizontal in Floor made of concrete, masonry, metal, gypsum partition, after passing service lines like cables/cable bundles, cable trays etc. The system shall be UL listed & classified and product shall bear the UL & FM approval logo on the packing If none of UL test certificate comply with actual application, an EJ document prepared by a qualified personnel and based on nearest third party tested & approved systems like UL test certificates & in accordance with IFC guidelines shall be produced by manufacturer. A firestop submittal shall be produced by manufacturer, in accordance with approved passive fire protection method statement, for technical approval. Firestop installation shall be done by Hilti Accredited Firestop Speciality Contractor (HAFSC) and in accordance with Hilti guidelines and UL system test certificates or approved EJ document. Firestop Speciality Contractor needs to submit work completion certificate along with installation report through Hilti documentation Software CFS DM for periodic inspection & maintenance purpose. The gaps along/around cables penetrants shall be sealed with intumescent sealant Hilti FS One Max. In case of repenetration requirement, Hilti intumescent based speed sleeve CP 653BA of appropriate size shall be used and shall be paid under separate heads and as mentioned below. Any report submittal with Installation pictures should be done using CFS-DM Software, which shall be charged extra.	sqm	7.50	7.50	10.00	25.00				-	-	-	-	-	-	-	-	-	-	-	-	-	
651	Providing Pre-formed block CFS BL made from intumescent polyurethane material for temporary or permanent firestop sealing around cables, cable bundles and conduits. Surface burning characteristics according UL 723 (ASTM E84-01): Flame spread index 10 and smoke development index 15. The sound transmission classification for this product according ASTM E 90 is 52 (STC Rating). The density is 0.27 g/cm³ and the expansion temperature (intumescent activation) is around 392, °F (200°C). Seismic tested on mechanical systems like UL test certificates & in accordance with IFC guidelines shall be produced by manufacturer. A firestop submittal shall be produced by manufacturer, in accordance with approved passive fire protection method statement, for technical approval. Firestop installation shall be done by Hilti Accredited Firestop Speciality Contractor (HAFSC) and in accordance with Hilti guidelines and UL system test certificates or approved EJ document. Firestop Speciality Contractor needs to submit work completion certificate along with installation report through Hilti documentation Software CFS DM for periodic inspection & maintenance purpose.	sqm	20.00	20.00	24.00	63.99				-	-	-	-	-	-	-	-	-	-	-	-	-	-
Sub Head 34 : Fire Alarm and Dection System																							
652	Supplying, installation, testing and commissioning of micro processor based intelligent addressable main fire alarm panel, central processing unit with the following loop modules and capable of supporting not less than 240 devices (including detectors) and minimum 120 detectors per loop and loop length up to 2 km, network communication card, minimum 320 character graphics/ LCD display with touch screen or other keypad and minimum 4000 events history log in the non volatile memory (EPROM), power supply unit (230 ± 5% V, 50 hz), 48 hrs back-up with 24 volt sealed maintenance free batteries with automatic charger. The panel shall have facility to connect printer to printout log and facility to have seamless integration with analog/digital voice evacuation system (which is part of the schedule of work under SH: PA System) and shall be complete with all accessories. The panel shall be compatible for IBMS system with open protocol BACnet/ Modbus over IP complete as per specifications.	set	2.00	2.00	2.00	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
653	Two Loop Panel.	set	0.00	0.00	0.00	0.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
654	Supplying, installation, testing & commissioning of central graphical fire alarm management system to centrally monitor and operate the fire alarm system complete as required.	nos	1.00	1.00	1.00	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
655	Supplying, installation, testing & commissioning of repeater panel with 320 character/ Touch screen LCD display with inbuilt reset, acknowledge and silence switches complete as required.	nos	1.00	1.00	1.00	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
656	Supplying, installation, testing & commissioning of intelligent analog addressable photothermal detector complete with mounting base complete as required.	nos	1330.00	1330.00	1225.00	3885.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
657	Supplying, installation, testing & commissioning of response indicator on surface/recessed MS Box having two LED, metallic cover complete with all connections etc as required.	each	731.00	731.00	623.00	2085.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
658	Supplying, installation, testing & commissioning of fault isolator complete with base as required.	nos	75.00	75.00	65.00	215.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
659	Supplying, installation, testing & commissioning of intelligent aspiration detector for area coverage of minimum 5000 sq.ft. complete as required.	each	10.00	10.00	10.00	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
660	Supplying, installation, testing & commissioning of intelligent addressable thermal detector with rate of rise cum fixed temperature thermistor complete with base as required.	each	27.00	27.00	30.00	84.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
661	Supplying, installation, testing & commissioning of addressable fire control module complete as required.	each	3.00	3.00	3.00	9.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
662	Supplying, installation, testing & commissioning of addressable phone control module complete as required.	each	2.00	2.00	2.00	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
663	Supplying, installation, testing & commissioning of addressable beam detector with short circuit isolator (inbuilt or separate) complete with emitter and receiver including connections with remote test features etc complete as required.	each	8.00	8.00	8.00	24.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
664	Supplying, installation, testing & commissioning of intelligent addressable duct detector including suitable Photo detector complete with base as required.	each	35.00	35.00	35.00	105.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
665	Supplying, installation, testing & commissioning of addressable manual call point complete as required.	each	35.00	35.00	35.00	105.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
666	Supplying, installation, testing & commissioning of addressable horn cum strobe complete as required.	each	35.00	35.00	35.00	105.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
667	Supplying, installation, testing & commissioning of fire fighter telephone handset complete as required.	each	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
668	Supplying, installation, testing & commissioning of fire fighter phone jack complete as required.	each	35.00	35.00	35.00	105.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
669	Supplying & laying of 2x1.5 sqmm fire alarm armoured cable, 600/1000V rated with annealed copper conductor having XLPE insulation, steel wire armouring & FRLS outer sheath complete as required.	metre	10500.00	10500.00	11500.00	32500.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supplying and fixing of following sizes of STEEL conduit alongwith the accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required.									-	-	-	-	-	-	-	-	-	-	-	-	-	-
670	20mm dia	metre	0.00	0.00	0.00	0.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
671	25mm dia	metre	25.00	25.00	25.00	75.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
672	Supply, Installation, Testing and Commissioning of UL/Vds/LPCB/EN approved Addressable Monitor Module with IP66 casing containing input/output for third party integration including potential free contacts with inbuilt isolators. Shall be UL / EN54 certified.	nos	20.00	20.00	20.00	60.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount															
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total						
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)				
673	Supplying, installing, testing and commissioning approved make Addressable Relay Module for AHU, Access Control, Lifts, Staircase Pressurization, Fire Suppression & other Third Party Outputs for CAUSE AND EFFECT MATRIX For effective Smoke management . The relay module shall provide contact rated at 24v DC, 2A. The device shall have an LED which shall blink in normal state & get steady on activation to monitor the heath status of the device. Addressing shall be with user friendly rotary decimal switches. Module shall be supplied with mounting plate from OEM for ease of installation & maintenance. The device shall comply UL approval & FM APPROVED	nos	10.00	10.00	5.00	25.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
Total Bill no-3 Fire fighting works									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
4	Bill no-4 STP, ETP & PUMPS								-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
Sub Head 35 : Sewage Treatment Plant 100KLD									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
674	Designing, Fabricating, Supplying, Installation & Commissioning 100 KLD STP: Fabrication and Supply of mechanical, electrical and instrumentation including Fine Screen Chamber, Tube settler, Equalization Tank, Collection Tank 1, Collection Tank 2 Bio Mound 1 & Bio Mound 2 Treated Water Tank Submersible Sewage pump to transfer fluid between EQT-BM1Submerssble Slurry Pump to transfer slurry between TS-VCB Submerssble sewage Pump to transfer fluid between CT1-BM2 Submersible clear water pump to transfer fluid between CT2-TWT Bio Mound Media 212 cum (lateratite/Basaltic/red clay origin media with technology provider specified agregate sizing), Jute 250gsm @every 0.5m inside BM media, Plantation/Saplings @2sqm each. 40 no etc.,Slurry Pump TS-VCB; Submersible Slurry Pump; (1W); Make:- Kirloskar/Equivalent; with Piping , NRVs, Cabling & Other Instrumentation as Applicable Sewage Pump EQT-BM1; Submersible Sewage Pump; 5 cum/hr @ 8-10 m head; (1W+1S); Make:- Kirloskar/Equivalent; with Piping , NRVs, Cabling & Other Instrumentation as Applicable Sewage Pump CT1-BM2; Submersible Sewage Pump; 5 cum/hr @ 8-10 m head; (1W+1S); Make:- Kirloskar/Equivalent; with Piping , NRVs, Cabling & Other Instrumentation as Applicable Clear Pump CT2-TWT; Submersible Clear Water Pump; 5 cum/hr @ 8-10 m head; (1W+1S); Make:- Kirloskar/Equivalent; with Piping , NRVs, Cabling & Other Instrumentation as Applicable Distributor System in UPVC inclusive fittings; MOC:- UPVC; 62sqm Tube settler Packing; MOC:- PVC; 3cum Fine Screen; MOC:- SS 304; Slot Size:- 5 mm 1 lot Mechanical Flow rm; Line Size :-2 inch; 1 no (Civil construction works will be paid under relevant civil items seperately).	each	1.00	0.00	1.00	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
675	Supplying on site fresh Garden soil (free from stones rubbish like dried grass roots, other such materials) for excavation area of depth of 30 cms.(consolidated thickness).(As per P&G DSR 2022-23 Items of garden work,Sr no36a), Supplying on site well decomposed Farnyard Manure for excavation area of depth of 30 cms. (Consolidated thickness). (As per P&G DSR 2022-23 Items of garden work,Sr no36b), Providing on site required variety of lawn (free from weeds /diesease etc.) Cynadon/ paspalum/ selection for 1 sqm. area dibbling distance 5 cms. apart e/c. (As per P&G DSR 2022-23 Items of garden work,Sr no46), Excavation for planting lawn/ shrub/ flower bed/ hedges/ edges/ canna bed in earth, soil of all types, soft murum, including removing the excavated material up to a distance of 50 rms. for a depth of 30 cms.(As per P&G DSR 2022-23 Items of garden work,Sr no3), Filling fresh garden soil / silt & manure in excavated area of depth 30cms. (As per P&G DSR 2022-23 Items of garden work,Sr no13), Mixing garden soil/silt & manure thoroughly well, watering previous night. Planting required plant species, lawn grass as directed etc. complete for required depth 30 cms. for planting lawn/ shrub/ flower bed/ hedges/ edges/ canna bed/ ground cover. (1/10 of semiskilled labour)(As per P&G DSR 2022- 23 Items of garden work,Sr no23), Maintainance of Newly Developed lawn Area. For First 30 days Only (Paspallum/ selection)(As per P&G DSR 2022-23 Items of garden work,Sr no28)	sqm	162.00	0.00	162.00	324.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
676	Supply, Installation and Testing of Tube settler Packing	cum	10.00	0.00	10.00	20.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
677	Providing supplying CAMUS Cultures and Catalyst; Patent nos 414339 (Mite Ecology for Treatment of Organic Liquids (METROL process) & On site demonstration as per the Vendors all as specified including MOU with technology expert Operation and Maintenance During DLP period(1 year) 1. Operatores:- 2 nos 2. Quarterly Site Visit :- 4 nos 3. Compliance Water Test Reports (quarterly) for raw water and treated water for parametre COD, BOD,TSS, pH:- 8 nos	kg	300.00	0.00	300.00	600.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Sub Head D 36 : Effluent Treatment Plant									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
678	Designing, Fabricating, Supplying, Installation & Commissioning 25 KLD ETP: Fabrication and Supply of mechanical, electrical and instrumentation including SCREEN CHAMBER Mesh with ss 304 Grade, EQUILIZATION TANK, NEUTRALIZATION TANK WITH PH DOSING, COAGULATION TANK WITH FLOCCULANT DOSING, FLOCCULANTATION TANK WITH FLOCCULANT DOSING, PRIMARY TUBE setTLER, nothing extra will be paid in this regard. (Civil construction works will be paid under relevant civil items seperately).interconnecting valves, Pressure Gauge, Air Rotarms, Level Switches etc. and electrical instruments like Motors, Distribution board, Cabling power etc., including all necessary fittings,labour etc to complete. Rate includes Mechanical, electrical & plumbing works, all Materials, necessary fittings, all labour charges, Transportaion, Taxes, Lead, Lift etc complete. Excluding civil works, nothing extra will be paid. (Civil construction works will be paid under relevant civil items seperately).	each	1.00	1.00	1.00	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Sub Head 37 : Pumps (Potable, Drainage, Sewage & Waste Water Treatment Plant)									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
679	Hydro pneumatic System for Multiple Overhead tank filling Supply, installation & commissioning of 1 nos Skid Mounted Factory Assembled Hydropneumatic System (with three pumps) with Vertical Multi Stage Centrifugal Pump for Clear Water with 50Hz, 380-500V, 2 Pole, IP 55 Enclosure Class, Class F Insulation, IE5 efficiency class motor along with HMI 300 Screen, integrated VFD & PI controller (IP 55 Protection) with each pump and the system shall come with multi master pump.Integrated VFD with following harmonic filters should be considered Harmonics IEC/EN 61000-3-12 Up to 7.5 kW (5.5 kW low speed);Category C1 according to EN 61800-3, corresponding to CISPR 11, class B (residential area) Above 7.5 kW (5.5 kW low speed); Category C3 according to EN 61800-3, corresponding to CISPR 11, class System. Pump shall be CI with CED quoted- Head & Base, SS 316 -Shaft and all other components will be with SS 304, Mechanical Seal (Balance Cartridge SiC vs SiC face) . System should supply with isolation valves at suction & Delivery sides and NRV at the discharge (Made of Brass/SS/POM) & 2 no. branded pressure transmitter of adequate. pressure rating (4-20mA) as per the requirement, CED coated suction & Delivery manifolds, CED Coated Base Frame along with 1 no 100L 10 Bar Pressure Tank. The pump performance curve shall be complying with the tolerance according to ISO 9906:2012, 3B. Per Pump Flow Rate -13.5 m3/hr (2W+1S), Head-50m	set	1.00	1.00	1.00	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
680	Supply installation & Commissioning of 100L 10Bar Pressure hydro pneumatic tank shall be of butyl bladder diaphragm type with pre-pressurized air/nitrogen. It shall be capable of handling the designed effective system protection (ESP) Volume to protect pump and operating controls by ensuring that the actual pump operation, tank shall have a maximum operating pressure of 10 bars/16 Bar depending on the pump shutoff head and shall be able to handle a maximum liquid temperature of 90 DegC/70 DegC respectively.	nos	2.00	1.00	1.00	4.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
681	Drainage Pump Supply installation & Commissioning of submersible drainage pump (1W+1S) for each sump with 3 Ph 380-415V 2 Pole Motor with CI or SS 304-Casing, SS 304 or DI/CI -Impeller, SS 304/SS 410- Shaft, Mechanical Seal suitable for handling 10-12mm soft solid.	set	2.00	1.00	2.00	5.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
682	Sewage Pump Supply installation & Commissioning of submersible drainage pump (1W+1S) for each sump with 3 Ph 380-415V 2 Pole Motor with CI - Casing, DI/CI -Impeller, SS 304/SS 410- Shaft, Mechanical Seal suitable for handling 65mm soft solid or pump shall be with grinder system as per the requirement	set	2.00	1.00	1.00	4.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
WATER TREATMENT PLANTS 5000 LPH										-	-	-	-	-	-	-	-	-	-	-	-	-	-
683	Water Treatment Plant Supply, installation, testing, commissioning of water treatment plant consisting of PH CORRECTION DOSING SYSTEM FILTER FEED PUMP MULTIGRADE FILTER ACTIVATED CARBON FILTER IRON REMOVAL FILTER WATER SOFTENER NAOCL DOSING SYSTEM WATER METRE MCC PANEL WITH CABLES Complete etc.,	set	1.00	0.00	0.00	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
WATER TREATMENT PLANTS 12000 LPH										-	-	-	-	-	-	-	-	-	-	-	-	-	-
684	Water Treatment Plant Supply, installation, testing, commissioning of water treatment plant consisting of PH CORRECTION DOSING SYSTEM FILTER FEED PUMP MULTIGRADE FILTER ACTIVATED CARBON FILTER IRON REMOVAL FILTER WATER SOFTENER NAOCL DOSING SYSTEM WATER METRE MCC PANEL WITH CABLES Complete etc.,	set	0.00	1.00	1.00	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
Sub Head 38 : Solar Hot Water Systems										-	-	-	-	-	-	-	-	-	-	-	-	-	-
685	Supplying, installation, testing and Commissioning of 1000 Litres per day Flat Collector type Solar Water heating system alongwith hot water tank made of stainless steel and insulated with PU foam (Heat Exchanger type) including making suitable cement concrete foundation etc on top of terrace, also having 2no 2KW heating coils and insulated plumbing arrangement between solar panel to tank but excluding plumbing works to input side of panel and output side of hot water tank, complete as required	each	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
686	Supplying, installation, testing and Commissioning of Hot water storage cum mixing tank of following capacities made up of MS sheets, with all necessary nozzles like cold water inlet, hot water outlet, return water inlet, drain, air vent, safety valve-1no, man hole of 450 mm of 10mm thickness (for tanks above 1000lt capacity), internal epoxy painting, external coated with primer and 2 coats of enamel paint, tank insulation with rock wool insulation of 50mm thick wool, with chicken wire mesh, 24 swg aluminium cladding, base channel box type stand of 500mm height, suitable pressurized system of 5Kg/cm2(g) working pressure 1000lt capacity with 4 mm thk for shell	each	5.00	5.00	5.00	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
Total Bill no-4 STP,ETP,Solar & Pumps										-	-	-	-	-	-	-	-	-	-	-	-	-	-
Bill no-5 HVAC works										-	-	-	-	-	-	-	-	-	-	-	-	-	-
Sub Head 39 : Air cooled Chiller										-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
	The impeller shall be of bronze or gunmetal. This shall be shrouded type with machined collars. Wear rings, where fitted to the impeller, shall be of the same material as the impeller. The impeller surface shall be smooth finished for minimum frictional loss. The impeller shall be secured to the shaft by a key																							
	The shaft shall be of stainless steel and shall be accurately machined. The shaft shall be balanced to avoid vibrations at any speed within the operating range of the pump.																							
	The shaft sleeve shall be of bronze or gunmetal. This shall extend over the full length of the stuffing box or seal housing. The sleeve shall be machined all over and ground on the outside.																							
	The bearings shall be ball or roller type suitable for the duty involved. These shall be grease lubricated and shall be provided with grease nipples/cups. The bearings shall be effectively sealed against leakage of lubricant.																							
	The shaft seal shall be stuffing box type unless otherwise specified, so as to allow minimum leakage compatible with the operation of the seal. The stuffing box shall be of adequate length and shall be packed with graphite asbestos or any other suitable material for the operating temperature. A drip well shall be provided beneath the seal.																							
	In the case of HSC pumps, the same shall be directly coupled to the motor shaft through, a flexible coupling protected by a coupling guard. In case of mono block pumps with solid casing, the motor and pumps shall be on a common shaft.																							
690	Supply,Installation,Testing and Commissioning of chilled water pump (2 working +1 Standby) having a capacity of 687 USGPM each With 35 mts. w.g. total head.	nos	3.00	0.00	3.00	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
691	Supply,Installation,Testing and Commissioning of chilled water pump (2 working +1 Standby) having a capacity of 790 USGPM each With 35 mts. w.g. total head.	nos	0.00	3.00	0.00	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
692	Supply, Installation, Testing and Commissioning of 1000 Litres Capacity PVC Tank (Sintex) insulated with 50mm Thick, 24 kg/cum density TF quality EPS thermocole insulation, covered with Aluminium Cladding including all accessories like Overflow, Drain valve, make-up Float valve, Air Vent arrangement etc as per specification.	nos	1.00	1.00	1.00	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supplying, Installation,Testing and Commissioning of separator For Chiller & hot water pipes of MS sheet construction finished with epoxy paint and provided with automatic air vents. The capacity of the air separator must be compatible with the chilled water system capacity. Main chilled water header pipe size and Hot water header pipes are below.									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
693	i) 250 mm dia NB	nos	1.00	1.00	1.00	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Sub Head 41 : Low side Installation Work																								

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
713	AHU 7.0 TR COOLING @ 2800 CFM (5100 CMH) With 60 mm of STP Including Flexible Fire Retadant Canvass	nos	0	0	1	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
714	AHU 7.0TR COOLING @ 2800 CFM (4757 CMH) With 60 mm of STP Including Flexible Fire Retadant Canvass	nos	0	3	0	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
715	AHU 6.0TR COOLING @ 2400 CFM (4077 CMH) With 60 mm of STP Including Flexible Fire Retadant Canvass	nos	2	0	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
716	AHU 6.0TR COOLING @ 2400 CFM (4077 CMH) With 65 mm of STP Including Flexible Fire Retadant Canvass	nos	0	2	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
717	AHU 6.0 TR COOLING @ 2400 CFM (4077 CMH) With 50 mm of STP Including Flexible Fire Retadant Canvass	nos	0	0	3	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
718	AHU 5.0TR COOLING @ 2000 CFM (4077 CMH) With 65 mm of STP Including Flexible Fire Retadant Canvass	nos	1	0	0	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
719	AHU 5.0TR COOLING@ 2000 CFM(3398 CMH) with 60 mm of STP Including Flexible Fire Retadant Canvass	nos	0	1	1	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
720	AHU 4.0TR COOLING @ 1600 CFM (2718 CMH) with 60 mm of STP Including Flexible Fire Retadant Canvass	nos	1	0	0	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supply, Installation, Testing and commissioning of factory built Ceiling Suspended chilled water double skin Air handling units made of 25 mm thick panels consisting of pre plasticized G.I. casing of thickness 0.8mm outside layer and 0.8mm inside layer with polyurethane foam (PUF) insulation factory injected between them by injection moulding machine, complete with blower section with blower suitable for static pressure as required, minimum 2 bend GSS/PVC eliminators,cooling coil section with aluminium finned copper tubes (tubes thickness not less than 0.5 mm) cooling coil of 4 row Coil ,10 Micon filter section with 50 mm thick metal viscous/ washable synthetic type air prefilters, 5 Microns Fine Filters, belt drive package with TEFC drive motor of efficiency class IE3 suitable for 415 ± 10% V, 50Hz, 3 Phase AC supply suitably designed for variable frequency drive applications, drain connections, stainless steel (18G) drain pan with PUF insulation, necessary vibration isolation arrangement etc. complete as per specification and of following capacities. The Maximum face velocity across coil is 155MPM , Maximum outlet air velocity is 610 MPM . The Maximum face velocity across filters : - Ordinary filters : 155MPM / Micro-veefilters : 155MPM and the Chilled Water temperature Out Temperature is 12. Deg C , Chilled Water temperature In Temperature is : 7 Deg C .																						
721	CSU 25 TR COOLING @ 2800 CFM With 50 mm STP Including Flexible Fire Retadant Canvass	nos	2	0	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
722	CSU 20 TR COOLING @ 8000 CFM With 50 mm STP Including Flexible Fire Retadant Canvass	nos	0	2	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
723	CSU 18.5TR COOLING @ 7400 CFM With 60 mm STP Including Flexible Fire Retadant Canvass	nos	0	0	2	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
724	CSU 9.5 TR COOLING @ 3800 CFM With 60 mm STP Including Flexible Fire Retadant Canvass	nos	0	0	2	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
725	CSU 8.0TR COOLING @ 3200 CFM With 55 mm STP Including Flexible Fire Retadant Canvass	nos	0	1	0	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
726	CSU 7.0TR COOLING @ 2800 CFM With 55 mm STP Including Flexible Fire Retadant Canvass	nos	1	1	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
727	CSU 7.0 TR COOLING @ 2800 CFM With 50 mm STP Including Flexible Fire Retadant Canvass	nos	0	0	1	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
728	CSU 6.0TR COOLING @ 2400 CFM With 55 mm STP Including Flexible Fire SRetadant Canvass	nos	1	0	0	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
729	CSU 5.5TR COOLING @ 2200 CFM With 55 mm STP Including Flexible Fire Retadant Canvass	nos	1	0	0	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
730	CSU 5.5TR COOLING @ 2200 CFM With 55 mm STP Including Flexible Fire Retadant Canvass	nos	0	2	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
731	CSU 5.5 TR COOLING @ 2200 CFM With 100 mm STP Including Flexible Fire Retadant Canvass	nos	0	1	1	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
732	CSU 5.0 TR COOLING @ 2000 CFM With 100 mm STP Including Flexible Fire Retadant Canvass	nos	2	0	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
733	CSU 4.5TR COOLING @ 1800 CFM with 100 mm of STP Including Flexible Fire Retadant Canvass	nos	1	3	0	4.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supply, installation, testing and commissioning of Chilled water complete with one ball valve with strainer at the inlet, one ball valve and 3-way motorised valve and balancing valve at the outlet, copper tubes and fittings, corded remote control with On/Off, thermostat and fan three speed functions, in- built condensate drain pump and mounting arrangement complete as per specifications. Capacities of the FCUs: (Chilled Water temperature Out Temperature is 12 Deg C , Chilled Water temperature In Temperature is : 7 Deg C.																						
734	FCU 1.0TR COOLING @ 400CFM Including Flexible Fire Retadant Canvass	nos	58	31	5	94.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
735	FCU 1.5TR COOLING @ 600CFM Including Flexible Fire Retadant Canvass	nos	100	62	59	221.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
736	FCU 2.0TR COOLING @ 800CFM Including Flexible Fire Retadant Canvass	nos	26	67	81	174.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
737	FCU 2.5TR COOLING @ 1000CFM Including Flexible Fire Retadant Canvass	nos	8	21	3	32.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
738	FCU 3.0TR COOLING @ 1200CFM Including Flexible Fire Retadant Canvass	nos	4	3	7	14.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
739	FCU 3.5TR COOLING @ 1400CFM Including Flexible Fire Retadant Canvass	nos	5	6	1	12.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
740	FCU 4.0TR COOLING @ 1600CFM Including Flexible Fire Retadant Canvass	nos	1	4	7	12.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supply, installation, testing and commissioning of Dx system Hi wall Splite air conditioning 3 STAR rated suitable for operation on 230V ±10% single phase 50Hz with Rotary compressor,Refrigerant capable to perform Cooling & Heating,with remote controll																						
741	Dx 1.0 TR	nos	10	14	1	25.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
742	Dx 1.5 TR	nos	3	12	14	29.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
743	Dx 2.0 TR	nos	9	5	5	19.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supply, installation, testing and commissioning of Direct drive Long Casing Tube Axial fans for Lift lobby and Lift Well fresh air pressurization complete with Pre Galvanised Steel (minimum 275 GSM Zinc coated)/MS Powder Coated Casing with spun flanges (welding of flanges is not permitted to avoid corrosion and pitting of casing), adjustable pitch die cast aluminium impeller (Hub and Aerofoil blades) and IE3,VFD Compatible motors. Casing position shall be as per the job requirement and shall be marked on the fan assembly.The complete fan assembly with its casing, impeller and motor (not only motor or one of the item) shall be sourced from one manufacturer.Axial fan should be licensed to bear AMCA seal for air performance and sound performance or must be demonstrated in AMCA accredited laboratory as per AMCA publication. Fire Rated Fans The complete assembly must have certificate of consistency of performance by BSI and must bear CE marking & Manufacturing Factory should be LEED certified Platinum Rated Green Building. (note: Fan Diarm should not exceed 1250 & speed should not exceed 960 RPM) Scope: Price include fan with IE3 motor, 1no Birdscreen, 1 no Mounting set ,Vibrartion isolator.																						
744	Tube Axial Fan -43750 CFM @ 35 mm STP	nos	1	1	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
745	Tube Axial Fan -30100 CFM @ 35 mm STP	nos	1	1	2	4.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
746	Tube Axial Fan -15050 CFM @ 35 mm STP	nos	2	2	0	4.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
747	Tube Axial Fan -6900 CFM @ 35 mm STP	nos	8	8	6	22.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
748	Tube Axial Fan -6600 CFM @ 35 mm STP	nos	0	0	3	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supply , installation , testing & commissioning of Cicular / cabinet type inline Toilet Exhaust fans. Casing position shall be as per the job requirement and shall be marked on the fan assembly. The fan assembly along with motors for Isolations																							
749	Inline Exhaust Fan - 1200 CFM @ 10 mm STP	nos	6	6	0	12.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
750	Inline Exhaust Fan - 1050 CFM @ 15 mm STP	nos	0	0	12	12.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
751	Inline Exhaust Fan - 750 CFM @ 15 mm STP	nos	0	0	8	8.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
752	Inline Exhaust Fan - 700 CFM @ 15 mm STP	nos	0	0	12	12.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
753	Inline Exhaust Fan - 600 CFM @ 10 mm STP	nos	14	14	0	28.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
754	Inline Exhaust Fan - 560 CFM @ 20 mm STP	nos	0	0	1	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
755	Inline Exhaust Fan - 450 CFM @ 10 mm STP	nos	2	2	0	4.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
756	Inline Exhaust Fan - 400 CFM @ 15 mm STP	nos	1	1	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
757	Inline Exhaust Fan - 300 CFM @ 15 mm STP	nos	1	1	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
758	Inline Exhaust Fan - 250 CFM @ 10 mm STP	nos	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
759	Inline Exhaust Fan - 200 CFM @ 15 mm STP	nos	1	1	2	4.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
760	Inline Exhaust Fan - 150 CFM @ 15 mm STP	nos	4	4	0	8.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
761	Inline Exhaust Fan - 100 CFM @ 10 mm STP	nos	1	1	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
762	Cabinet Inline Exhaust Fan - 5250 CFM @ 35 mm STP	nos	1	1	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
763	Cabinet Inline Exhaust Fan - 5950 CFM @ 35 mm STP	nos	1	1	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
764	Cabinet Inline Exhaust Fan - 4000 CFM @ 35 mm STP	nos	0	0	1	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
765	Cabinet Inline Exhaust Fan - 4900 CFM @ 35 mm STP	nos	0	0	2	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supply , installation , testing & commissioning of cabinet type inline Smoke Exhaust fans. Casing position shall be as per the job requirement and shall be marked on the fan assembly. The fan assembly along with motors for Isolations									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
766	Cabinet Inline Exhaust Fan - 2950 CFM @ 20 mm STP	nos	2	2	0	4.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
767	Cabinet Inline Exhaust Fan - 1750 CFM @ 20 mm STP	nos	1	1	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
768	Cabinet Inline Exhaust Fan - 1700 CFM @ 20 mm STP	nos	0	0	1	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
769	Cabinet Inline Exhaust Fan - 1650 CFM @ 20 mm STP	nos	1	1	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
770	Cabinet Inline Exhaust Fan - 1600 CFM @ 20 mm STP	nos	0	0	1	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
771	Cabinet Inline Exhaust Fan - 1400 CFM @ 20 mm STP	nos	0	0	3	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
772	Cabinet Inline Exhaust Fan - 1350 CFM @ 20 mm STP	nos	1	1	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
773	Cabinet Inline Exhaust Fan - 1300 CFM @ 20 mm STP	nos	0	0	1	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
774	Cabinet Inline Exhaust Fan - 1250 CFM @ 20 mm STP	nos	1	1	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
775	Cabinet Inline Exhaust Fan - 1200 CFM @ 20 mm STP	nos	1	1	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
776	Cabinet Inline Exhaust Fan - 1000 CFM @ 20 mm STP	nos	2	2	1	5.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
777	Cabinet Inline Exhaust Fan - 700 CFM @ 20 mm STP	nos	0	0	1	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
778	Cabinet Inline Exhaust Fan - 400 CFM @ 20 mm STP	nos	0	0	1	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
779	Cabinet Inline Exhaust Fan - 300 CFM @ 20 mm STP	nos	0	0	1	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supply , installation , testing & commissioning of cabinet type inline Fresh air fans. Casing position shall be as per the job requirement and shall be marked on the fan assembly. The fan assembly along with motors for Isolations									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
780	Cabinet Inline Fresh Air Fan - 2950 CFM @ 20 mm STP	nos	2	2	0	4.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount												
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total			
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	
781	Cabinet Inline Fresh Air Fan - 2000 CFM @ 20 mm STP	nos	1	1	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-
782	Cabinet Inline Fresh Air Fan - 1750 CFM @ 20 mm STP	nos	1	2	0	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-
783	Cabinet Inline Fresh Air Fan - 1700 CFM @ 20 mm STP	nos	0	0	1	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-
784	Cabinet Inline Fresh Air Fan - 1650 CFM @ 20 mm STP	nos	1	1	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-
785	Cabinet Inline Fresh Air Fan - 1600 CFM @ 20 mm STP	nos	0	0	1	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-
786	Cabinet Inline Fresh Air Fan - 1400 CFM @ 20 mm STP	nos	0	0	3	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-
787	Cabinet Inline Exhaust Fan - 1350 CFM @ 20 mm STP	nos	1	1	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-
788	Cabinet Inline Exhaust Fan - 1300 CFM @ 20 mm STP	nos	0	0	1	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-
789	Cabinet Inline Exhaust Fan - 1250 CFM @ 20 mm STP	nos	1	1	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-
790	Cabinet Inline Exhaust Fan - 1200 CFM @ 20 mm STP	nos	1	1	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-
791	Cabinet Inline Exhaust Fan - 1000 CFM @ 20 mm STP	nos	0	0	1	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-
792	Cabinet Inline Exhaust Fan - 700 CFM @ 20 mm STP	nos	0	0	1	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-
793	Cabinet Inline Exhaust Fan - 400 CFM @ 20 mm STP	nos	0	0	1	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-
794	Cabinet Inline Exhaust Fan - 300 CFM @ 20 mm STP	nos	0	0	1	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-
795	Supply, installation ,testing and commissioning of Strip heater, Pan Humidifier with Siemens controller (digital) for controlling and maintaining the RH of 45% TO 50% and its include of drain tray, all necessary accessories with one number of stand by heater.																					
795A	Strip heater-5 kW	nos	3.00			3.00				-	-	-	-	-	-	-	-	-	-	-	-	-
795B	Strip heater-5.5kW	nos		1.00		1.00				-	-	-	-	-	-	-	-	-	-	-	-	-
795C	Strip heater-6 kW	nos	1.00	2.00	2.00	5.00				-	-	-	-	-	-	-	-	-	-	-	-	-
795D	Strip heater-7 kW	nos		1.00	1.00	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-
795E	Strip heater-15 kW	nos	1.00			1.00				-	-	-	-	-	-	-	-	-	-	-	-	-
795F	Strip heater-17 kW	nos		1.00		1.00				-	-	-	-	-	-	-	-	-	-	-	-	-
795G	Strip heater-18.5 kW	nos			1.00	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-
795H	Pan Humidifier 25 LITRES	nos	5.00	5.00	4.00	14.00				-	-	-	-	-	-	-	-	-	-	-	-	-
	INSULATED CHILLED WATER PIPING(Nitrile rubber insulation) Supplying, laying/ fixing, testing and commissioning of following nominal sizes of chilled water piping inside the building (with necessary clamps, vibration isolators and fittings but excluding valves, strainers, gauges etc.) duly insulated with following closed cell elastometric nitrile rubber of minimum 45 Kg / cu m density, thermal conductivity 0.037 W/MK or better at 20 deg mean temperature class 'O' insulation applied by suitable adhesive complete including repairing of damage to building etc. as per specifications and as required complete in all respect. note: The Pipes of sizes 150mm & below shall be M.S. 'C' class as per IS : 1239 and pipes size above 150mm shall be welded black steel pipe heavy class as per IS: 3589, from minimum 6.35mm thick M.S. Sheet for pipes upto 350 mm dia. and from thick MS sheet for pipes of 400 mm dia and above.minimum 7mm thick MS sheet for pipes of 400 mm dia and above.																					
	<u>Chilled water pipes</u>									-	-	-	-	-	-	-	-	-	-	-	-	-
796	250mm dia.(32 mm thick insulation)	metre	57	57.00	70.00	184.00				-	-	-	-	-	-	-	-	-	-	-	-	-
797	200mm dia.(32 mm thick insulation)	metre	102	107.00	14.00	223.00				-	-	-	-	-	-	-	-	-	-	-	-	-
798	150mm dia. (32 mm thick insulation)	metre	136	70.00	106.00	312.00				-	-	-	-	-	-	-	-	-	-	-	-	-
799	125mm dia.(32 mm thick insulation)	metre	75	52.00	78.00	205.00				-	-	-	-	-	-	-	-	-	-	-	-	-
800	100mm dia. (32 mm thick insulation)	metre	231	258.00	369.00	858.00				-	-	-	-	-	-	-	-	-	-	-	-	-
801	80mm dia.(32 mm thick insulation)	metre	483	294.00	311.00	1088.00				-	-	-	-	-	-	-	-	-	-	-	-	-
802	65mm dia(32 mm thick insulation)	metre	383	370.00	246.00	999.00				-	-	-	-	-	-	-	-	-	-	-	-	-
803	50mm dia(32 mm thick insulation)	metre	536	571.00	1118.00	2225.00				-	-	-	-	-	-	-	-	-	-	-	-	-
804	40mm dia. (32 mm thick insulation)	metre	431	378.00	354.00	1163.00				-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
805	32 mm dia(19 mm thick insulation)	metre	846	649.00	607.00	2102.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
806	25 mm dia(19 mm thick insulation)	metre	1309	1368.00	1444.00	4121.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
807	20mm dia(Pipe only)	metre	685	275.00	41.00	1001.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supplying, laying/ fixing, of following nominal sizes of chilled water piping inside and Exposed of the building duly insulated with Class O Nitrile Rubber with 45 +/- 5 kg/cum density insulation of Pre formed pipe section Covered with aluminium cladding for all pipes, fittings, valves, unions, etc. Insulation Thickness																							
808	20mm dia X 56 mm Thick	metre	685	275.00	43.00	1003.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	<u>Control Valves For Chiller pipes</u>																							
	Supplying, fixing, testing and commissioning of following valves, strainers, gauges in the chilled water plumbing duly insulated to the same specifications as the connected piping and adequately supported as per specifications.																							
	<u>3-WAY CONTROL VALVE</u> Supply, installation, testing & commissioning of 3-Way modulating type control Valve, with Brass body, Stainless Steel ball with special structure,800 kPa working pressure, 90 Deg C maximum operating temperature;Single piece;Threaded connections; Valves shall be inclusive of actuator and Room thermostat with three speed operation as per specification. The given price including of necessary pipe connections.																							
809	100mm dia	nos	0	0	3	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
810	80mm dia	nos	2	0	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
811	65mm dia	nos	2	6	5	13.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
812	50mm dia	nos	8	5	8	21.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
813	40mm dia	nos	11	7	10	28.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
814	32mm dia	nos	0	2	3	5.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	<u>BUTTERFLY VALVE (MANUAL) with C I body SS Disc, Nitrile Rubber Seal & O- Ring PN 16 pressure rating for chilled water/hot eater circulation as specified</u>																							
815	250mm dia	nos	2	2	2	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
816	150mm dia	nos	6	6	6	18.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
817	125mm dia	nos	3	3	6	12.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
818	100mm dia	nos	27	27	14	68.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
819	80mm dia	nos	21	15	12	48.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
820	65mm dia	nos	23	45	51	119.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
821	50mm dia	nos	50	32	57	139.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
822	40mm dia	nos	66	42	60	168.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
823	32mm dia	nos	0	14	0	14.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	<u>Y - STRAINER of Ductile CI Body flanged ends with stainless steel strainer for chilled / hot water circulation including insulation as specified</u>																							
824	150mm dia	nos	3	3	3	9.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
825	125mm dia	nos	3	3	1	7.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
826	80mm dia	nos	2	0	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
827	65mm dia	nos	2	6	6	14.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
828	50mm dia	nos	8	5	10	23.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
829	40mm dia	nos	11	7	10	28.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
830	32mm dia	nos	0	2	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
864	supply and erection of UL-555 Standeds with CBRI certified Fusible link fire dampers of atleast 120 minutes fire rating. Constructed with 16G GI outer casing and multiblades type out of 16 G -GI -3v grooved blades with bras bush and spindles on both the ends of the fire dampers. FOR fusible link fire dampersUL. Stamped fusible linkshall be fitted with proper spring mechanism .For motorized fire dampers actuators shall be factory fitted and shall furnish test certificates for satisfactory operation of each dampers actuators with be spring return model along with control panels. the actuator torque shall be suitable for the fire damper size.	sqm	6.05	6.38	1.60	14.03				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supply & Installation of Stainless steel matt SS304 grade Ceiling Suspended type Laminar Air Flow Unit with Suitable HEPA Filters(0.3 micron)									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
865	1.Size - 8'x8'	nos	4.00	4.00	4.00	12.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
866	2.Size - 8'x6'	nos	1.00	1.00	1.00	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	<u>Air Terminal :</u>									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
867	Supplying, fixing testing commissioning of supply air diffusers of powder coated aluminium with aluminium volume control dampers with anti smudge ring & removable core.	sqm	9.00	8.00	0.74	17.74				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
868	Supplying, fixing testing commissioning of Return air diffusers of powder coated aluminium without volume control dampers with anti smudge ring & removable core.	sqm	7.00	6.00	0.00	13.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
869	Supplying & fixing of powder coated extruded aluminium Supply Air Grills with aluminium volume control dampers as per specifications	sqm	13.96	17.13	20.49	51.58				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
870	Supplying & fixing of powder coated extruded aluminium Return Air Grills with louvers but without volume control dampers complete as required.	sqm	111.44	104.01	142.53	357.98				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supplying & fixing of powder coated extruded aluminium Fresh Air Invisible grille as per specifications/ Sizes as per Tender Drawings.									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
871	i) 400mm Height	sqm	0.4	0.36	0.40	1.16				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
872	ii) 350mm Height	sqm	0.12	0.12	0.40	0.64				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
873	iii) 300mm Height	sqm	0.84	0.84	0.40	2.08				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
874	iv) 250mm Height	sqm	1.09	1.09	2.10	4.28				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
875	iv) 200mm Height	sqm	0.5	0.47	0.40	1.37				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
876	v) 150mm Height	sqm	0.12	0.12	0.00	0.24				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
877	vi) 100mm Height	sqm	0.1	0.03	0.00	0.13				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supplying & fixing of powder coated extruded aluminium Fresh Air grille with collar damper as per specifications/ Sizes as per Tender Drawings.									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
878	100mm Height	sqm	0	0.00	0.10	0.10				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
879	150mm Height	sqm	2.65	2.65	2.80	8.10				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
880	200mm Height	sqm	0.3	0.28	0.00	0.58				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supplying & fixing of powder coated extruded aluminium Exhaiut Air Invisible grille with collar damper as per specifications/ Sizes as per Tender Drawings.									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
881	i) 100mm Height	sqm	0.1	0.10	0.00	0.20				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
882	ii) 150mm Height	sqm	0.3	0.27	0.30	0.87				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
883	iii) 200mm Height	sqm	0.1	0.04	0.00	0.14				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
884	iv) 250mm Height	sqm	2.3	2.03	3.00	7.33				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
885	v) 300mm Height	sqm	1.2	1.20	1.80	4.20				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount															
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total						
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)				
900	Supply, Receiving, Unloading, Storing, Shifting, Installation, Testing & Commissioning of indoor type floor mounted, dust, damp and vermin proof, cubicle HT. rming Panel made out of 14 gauge CRCA sheet steel complete with 5Amp electronic trivector rm, C.T.'s of 800/5Amp, 0.5 Class, 10VA Burden, and P.T.'s of 11KV/ /3, 110V/ /3, 100 VA conforming to relevant IS Standards and complete as required. H.T. rming cubicle along with C.T.'s, P.T.'s and trivector rm shall be got tested and approved from local electricity supply authority. The GA drawing shall be got approved by ELECTRICITY SUPPLY AUTHORITY before fabrication.	set	1	0	1	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	33 KV H.T. METREING PANEL (INDOOR TYPE):																								
901	Supply, Receiving, Unloading, Storing, Shifting, Installation, Testing & Commissioning of indoor type floor mounted, dust, damp and vermin proof, cubicle HT. rming Panel made out of 14 gauge CRCA sheet steel complete with 5Amp electronic trivector rm, C.T.'s of 800/5Amp, 0.5 Class, 10VA Burden, and P.T.'s of 33KV/ /3, 110V/ /3, 100 VA conforming to relevant IS Standards and complete as required. H.T. rming cubicle along with C.T.'s, P.T.'s and trivector rm shall be got tested and approved from local electricity supply authority. The GA drawing shall be got approved by ELECTRICITY SUPPLY AUTHORITY before fabrication.	set	0	1	0	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	H.T. SINGLE PANEL BOARD																								
	11 KV HT VCB Single Breaker Panel Board (Indoor Type) (1 set Incomming / Outgoing)																								
	Supply, Receiving, Unloading, Shifting, Installation Testing & Commissioning of 11 KV Single Breaker Vacuum Circuit Breaker Panel Board as 1 Incomming/Outgoing shall be metal clad floor mounting complete as per specification and as described.																								
	800 A Vacuum circuit breaker of (350 MVA)18.3 KA rmS for 3 second rupturing capacity for at 11 KV rated, totally enclosed,air insulated metal clad housing, floor mounting, horizontal isolation, vermin proof, fully interlocked horizontal drawout type having isolation features and control devices complete with the following.																								
	Manually and motor operated, spring charged (release closing mechanism) trip free type, triple pole truck mounted draw out, vacuum circuit breaker, incorporating mechanical as well as electrical ON/OFF indication. Spring charge/discharge mechanical indication"OFF" push buttons for emergency trip (shrouded) test/service position limit switches with 6 nos/6 NC breaker auxilliary contacts in service position, 24 Volts DC shunt trip coil and strip heater to prevent moisture absorption.																								
	INCOMING / OUTGOING PANEL - 1 no																								
	800 A Vacuum circuit breaker of (350 MVA) 18.3 KA rmS for 3 second rupturing capacity for at 11 KV rated, totally enclosed,air insulated metal clad housing, floor mounting, horizontal isolation, vermin proof, fully interlocked horizontal drawout type having isolation features and control devices complete with the following.																								
	3 nos Single Phase double core current transformer 800/5 Amp epoxy cast insulated class of insulation E.																								
	Core 1-15VA burden class 1.0 for metreing.																								
	Core 2-15VA burden class 5P10 for protection.																								
	P.T.'s of 11KV/1.732, 110V/1.732, 100VA with suitable rating H.T. & L.T. fuse conforming to relevant IS Standards and complete as required.																								
	One no numerical microprocessor based three phase over current (IDMT element) (2 O/C+1E/F) with earth fault relay with instantaneous elements.																								
	1 no Anti Pumping device.																								
	1 no Circuit breaker control switch for electrical (T/N/C).																								
	1 no limit switch for test & service position.																								

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
908	630 KVA DG set with suitable capacity of Day Oil Tank describe as above	set	4	4	4	12.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	DG Synchronization cum Changeover Panel.																						
	Supply, Erection, Testing & Commissioning of DG Control panel with D.G. Synchronizing controller & Micro PLC, this will be floor mounted, free standing, compartmentalized, indoor duty, dust proof, vermin proof, front operated, electrical panel fabricated, painted and manufactured exactly as per specifications laid in this document and will be complete with the main and auxiliary bus bars, interconnection, earth terminals, earth bus and will be powdered coated finished. All the busbar joint shall be protected by clip on type sleeve. The DG control panel shall use all draw out 3 position withdrawn type breakers suitable for 415 V AC, 3 phase, 50 Hz, 4 wire supply system and will have fault level of 50 KA or as required as per consultant approval. The panel will be made as per detailed specifications and drawings forming part of this document. (Under no case temperature of LT Panel shall be more at any point of the panel, otherwise necessary exhaust fan shall be have to provided) Bus bar calculations considering temperature derating, enclosure derating, sleeving derating must be done and submitted for checking.																						
	The DG vendor shall make complete protection curves and discrimination chart for relay settings and shall adjust all these readings at site. The bus bar size shall not be less than the ampere sizes mentions after derating. The bidder will show exact calculations & compare the figure of 0.66 and final calculations will be adopted for more stringent condition. each incomer shall have surge protection device. The PCC panel will comprise of the following :																						
	each incoming / outgoing breaker shall have microprocessor release with adjustable over current, short circuit & earth fault protection with instantaneous as mentioned in specification. The Panel will be made as per detailed specifications & drawings forming part of this document. Fault level of panel shall be 50 KA.																						
	All the MCCB up to 250 Amp shall have thermal release with adustable overload, short circuit & earth fault protection and above shall have microprocessor release with adjustable overload, short circuit & earthfault protection. The panel shall be manufactured as per BOQ, tech specification and drawing. Fault level of panel shall be 50 KA.																						
	One set of PLC with required accessories for AMF, Load Management, Interlocking and synchronizing through synchronizing relay. PLC shall be with PC, Monitor, required software to monitoring the all parametres for Synchronizing Panel & Main L.T. Panel.																						
	Incomer:																						
	2 nos 1250A incomer and each incomer breaker feeder + 1 outgoing 2500A: (For 630 KVA D.G. set)-																						
	ACB FP Electrically operated horizontal drawout type Air Circuit Breaker microprocessor based releases for O/C, S/C & earth fault protection with instantaneous including 200 Amps TP Neutral Contactor. (50 KA)																						
	One set of Generator control relay for each D.G. set with accessories for AMF, Synchronizing.																						
	1 no digital ammetre, ammetre selector switch, digital voltmeter, Voltmeter selector switch.																						
	1 no Load Manager EM 6400 with RS 485 port Suitable for BMS compatible																						
	1 no REF relay																						
	Annosunciation window to cover LLOP, HWT, OIL Pressure, U/V, O/V, U/F, O/F, O/C, E/F, REF relay faults shall be provided. 2 nos phase reversal relay shall be provided.																						

SL. no	Description of Item	Unit	Quantity				Rate			Amount											
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total		
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)
923	Supply of Shock treatment chart duly mounted on a wooden frame with glass on, as required in 2 languages (Hindi & English).	nos.	8	8	8	24.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
924	Supply of Rubber mat 1000 mm. Wide to withstand 11 KV dielectric strength as per latest IS 15652-2006.	metre	8	8	8	24.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Main LT PANEL																				
	Supply, Erection, Testing & Commissioning of Main LT panel. this will be floor mounted, free standing, compartmentalized, indoor duty, dust proof, vermin proof, front operated, electrical panel fabricated, painted and manufactured exactly as per specifications laid in this document and will be complete with the main and auxiliary bus bars, interconnection, earth terminals, earth bus and will be powdered coated finished. All the busbar joint shall be protected by clip on type sleeve. The DG control panel shall use all draw out 3 position withdrawn type breakers suitable for 415 V AC, 3 phase, 50 Hz, 4 wire supply system and will have fault level of 50 KA or as required as per consultant approval. The panel will be made as per detailed specifications and drawings forming part of this document. (Under no case temperature of LT Panel shall be more at any point of the panel, otherwise necessary exhaust fan shall be have to provided) Bus bar calculations considering temperature derating, enclosure derating, sleeving derating must be done and submitted for checking.																				
	each incoming / outgoing breaker shall have microprocessor release with adjustable over current, short circuit & earth fault protection with instantaneous as mentioned in specification. The Panel will be made as per detailed specifications & drawings forming part of this document. Fault level of panel shall be 50 KA.																				
	All the MCCB up to 250 Amp shall have thermal release with adustable overload, short circuit & earth fault protection and above shall have microprocessor release with adjustable overload, short circuit & earthfault protection. The panel shall be manufactured as per BOQ, tech specification and drawing. Fault level of panel shall be 50 KA.																				
	4 sets trip circuit healthy indicating lamp (one set for each incoming breaker).																				
	4 sets auto trip indicating lamp (one set for each incoming breaker).																				
	2 set of CT's one of 2500/ 5Amp ratio for APFC relay.																				
	4 nos. over & under frequency relay																				
	4 nos of Undervoltage & Overvoltage Protection.																				
	4 nos Reverse power relay.																				
	4 nos 6 window annosunciator with complete accessories.																				
	4 nos TVSS (Type I + II) with required earthing.																				
	4 no's,phase sequence relay																				
	4 no's,Maximun demand controller																				
	2 set of 2Amps MCB																				
	BUSCOUPLER																				
	1 no 2500Amp FP Electrically operated horizontal drawout type Air Circuit Breaker as buscoupler with interlocking arrangement with incomers. (50 KA)																				
	1 sets of indicating lamps for ON & OFF for bus coupler.																				
	BUSBARS																				
	2500 Amp TPN busbars of aluminium																				
	OUTGOING																				

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
940	Above 120 sq. mm and upto 400 sq. mm	metre	95	95	135	325.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 11 KV grade of following size in the existing masonry open duct as required.																							
941	Above 120 sq. mm and upto 400 sq. mm	metre	80	80	75	235.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
942	Providing and fixing H.T. danger notice plate of 250 mm X 200 mm, made of mild steel, at least 2 mm thick, and vitreous enameled white on both sides, and with inscription in single red colour on front side as required.	metre	6	6	6	18.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
943	Providing and fixing M.V. danger notice plate of 200 mm X 150 mm, made of mild steel at least 2 mm thick, vitreous enameled white on both sides, and with inscription in single red colour on front side as required.	each	15	15	15	45.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
944	Supplying and fixing cable route marker with 10 cm X 10 cm X 5 mm thick G.I. plate with inscription there on, bolted /welded to 35 mm X 35 mm X 6 mm angle iron, 60 cm long and fixing the same in ground as required.	each	25	25	25	75.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Constructing brick masonry chamber for underground C.I. inspection chamber and bends with bricks in cement mortar 1:4 (1 cement : 4 coarse sand) C.I. cover with frame (light duty) 455x610 mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg), R.C.C. top slab with 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand), finished smooth with a floating coat of neat cement on walls and bed concrete etc. complete as per standard design :																							
945	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	each	10	15	15	40.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
946	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	each	11	25	25	61.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Extra for depth beyond 45 cm of brick masonry chamber									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
947	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	metre	5	5	5	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
948	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	metre	2	2	2	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete.									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
949	150 mm dia. R.C.C. pipe	metre	265	295	350	910.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
950	250 mm dia. R.C.C. pipe	metre	5	5	5	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
951	300 mm dia. R.C.C. pipe	metre	135	143	150	428.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	HDPE PIPE FOR LV SERVICES									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. in the existing trench, complete as required.									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
952	200 mm dia (OD-200 mm & ID-175 mm nominal)	metre	5	5	5	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
953	160 mm dia (OD-160 mm & ID-135 mm nominal)	metre	5	5	5	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
954	90 mm dia (OD-90 mm & ID-76 mm nominal)	metre	8	8	8	24.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
955	Preparation of necessary drawings getting approval arranging rule - 63 inspection and obtaining safety certificate for from CEIG	LS	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
956	Any other government approval and certificate / clearance if required	LS	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
967	Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	set	46	46	46	138.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
968	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	set	45	45	45	135.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
969	Providing and fixing 25 mm x 5 mm copper strip on surface or in recess for connections etc. as required.	metre	400	400	680	1480.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
970	Providing and fixing earth bus of 50 mm x 5 mm copper strip on surface for connections etc. as required.	metre	162	162	162	486.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
971	Providing and fixing 25 mm X 5 mm G.I. strip on surface or in recess for connections etc. as required	metre	6212	6212	6212	18636.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
972	Providing and fixing 50 mm X 5 mm G.I. strip on surface or in recess for connections etc. as required	metre	336	346	356	1038.38				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
973	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface/ recessed conduit/ submain wiring/ cable as required.	metre	900	900	900	2700.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
974	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing etc. as required.	metre	450	450	450	1350.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
975	Providing and fixing 4.00 mm dia copper wire on surface or in recess for loop earthing as required.	metre	100	102	100	302.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
976	Providing and fixing of lightning conductor finial, made of 25 mm dia 300 mm long, G.I. tube, having single prong at top, with 85 mm dia 6 mm thick G.I. base plate including holes etc. complete as required.	each	2	2	2	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
977	Providing and fixing G.I. tape 20 mm X 3 mm thick on parapet or surface of wall for lightning conductor complete as required. (For horizontal run)	metre	300	306	300	906.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
978	Providing and fixing G.I. tape 20 mm X 3 mm thick on parapet or surface of wall for lightning conductor complete as required. (For Vertical run)	metre	200	204	200	604.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
979	Providing and fixing testing joint, made of 20 mm X 3 mm thick G.I. strip, 125 mm long, with 4 nos. of G.I. bolts, nuts, chuck nuts and spring washers etc. complete as required.	each	10	10	10	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
980	Providing and laying G.I. tape 32 mm X 6 mm from earth electrode directly in ground as required.	metre	420	428	420	1268.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
981	Jointing copper / G.I. tape (with another copper/ G I tape, base of the finial or any other metallic object) by riveting / nut bolting/ sweating and soldering etc as required.	set	7	7	7	21.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
982	Providing and fixing 6.00 mm dia copper wire on surface or in recess for loop earthing as required.	set	1123	1123	1123	3369.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
983	Providing and fixing 10.00 mm dia copper wire on surface or in recess for loop earthing as required.	set	107	107	10	224.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
984	Supply, Installation, Testing & Commissioning of Earthing Junction Box size - 400mm x 300mm x 80mm made out of 16 SWG CRCA sheet with seven tank process & powder coating, earthing link (32mm x 6mm copper strip with suitable knockout holes) front door with glass as complete as required.	set	10	10	10	30.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Sub Head 45 : Photo Voltaic On Grid Solar Work																								
985	Supply, Installation, Testing and Commissioning of ongrid Solar Photovoltaic Power Plant conforming to MNRE specifications as amended, consisting of Mono/Poly Crystalline silicon solar cells, net metering facility, necessary protections, earthing, mounted on Aluminium/GI structure of suitable strength with following components complete as required:- a) Solar Photovoltaic Module of capacity 330 Wp or above, manufactured in India, conforming to IS 14286/IEC 61215, IS/IEC 61730-Part-1, IS/IEC 61730-Part-2. Solar Photovoltaic Module conversion efficiency shall not be less than 16.5%. PV modules used in solar power plants/ systems must be warranted for their output peak watt capacity, which should not be less than 90% at the end of 10 years and 80% at the end of 25 years. b) Power Conditioning Unit (PCU) of 350-800 V DC Input voltage range and 400 V AC, three phase, 4 wire, 50Hz +/- 2.5 Hz, output voltage suitable to generate AC Power with efficiency not less than 97%, total harmonic distortion less than 3% and suitable for ambient temperature from 0 to 50 degree C. The PCU shall adjust the voltage and frequency level to suit the Grid Voltage Frequency. c) Data Monitoring System complete with accessories.	KWp	125	125	125	375.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	d) Fixing of Array junction box & Main junction box with IP 65 protection and termination arrangement for incoming and outgoing cable along with glands, lugs and other accessories etc. as required. e) Lightning and surge voltage protection. f) Connections & Interconnections by supplying & fixing required size XLPE insulated copper conductor 1.1 kV grade armoured power and control cables between solar modules, main power cable to grid supply PCU unit along with supplying & fixing of necessary channel/conduit lugs and other accessories etc. as required.									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Sub Head 46 : Internal Electrification																								
	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sqmm FRLS PVC insulated copper conductor single core cable in surface / recessed medium Class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sqmm FRLS PVC insulated copper conductor single core cable etc. as required.									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
986	Group C	Point	2465	2473	2245	7183.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
987	Wiring for twin control light point with 1.5 sqmm FRLS PVC insulated copper conductor single core cable in surface / recessed medium Class PVC conduit, 2 way modular switch, modular plate, suitable GI box and earthing the point with 1.5 sqmm. FRLS PVC insulated copper conductor single core cable etc. as required.	Point	57	42	37	136.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Wiring for group controlled (looped) light point/fan point/exhaust fan point/ call bell point (without independent switch etc.) with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed PVC conduit, and earthing the point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable etc. as required.									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
988	Group C	Point	2170	2159	2094	6423.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
989	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 3 pin 5/6 A modular socket outlet and 5/6 A modular switch, connections etc. as required.	each	402	408	377	1187.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
990	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 2 nos. 3 pin 5/6 A modular socket outlet and 2 nos. 5/6 A modular switch, connections etc. as required. (For light plugs to be used in non residential buildings).	each	395	406	483	1284.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
991	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 A modular socket outlet and 15/16 A modular switch, connections etc. as required.	each	1257	1264	1158	3679.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
992	Supplying & fixing suitable size GI box with modular plate and cover in front on surface or in recess including providing and fixing 25 A modular socket outlet and 25 A modular SP MCB, "C" curve including connections, painting etc. as required.	each	5	2	5	12.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
993	Supplying and fixing 20 A, 240 V, SPN Industrial type socket outlet, with 2 pole and earth, metal enclosed plug top alongwith 20 A "C" curve, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. as required.	each	10	2	10	22.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
994	Supplying and fixing 30 A, 415 V, TPN Industrial type socket outlet, with 4 pole and earth, metal enclosed plug top alongwith 30 A "C" curve, TPMCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. as required.	each	7	4	7	18.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
995	Wiring for light/ power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel/PVC conduit alongwith 1 no 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	metre	10	25	10	45.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
996	Wiring for light/ power plug with 4X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel/PVC conduit alongwith 2 nos. 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	metre	393	389	396	1178.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required									-	-	-	-	-	-	-	-	-	-	-	-	-	-
	CIRCUIT / SUBMAIN WIRING									-	-	-	-	-	-	-	-	-	-	-	-	-	-
997	2x1.5 sq mm + 1x1.5 sq mm earth wire	metre	18042	18015	13560	49617.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
998	2x2.5 sq mm + 1x2.5 sq mm earth wire	metre	15000	14908	20435	50343.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
999	2x4 sq mm + 1x4 sq mm earth wire	metre	31516	31505	23765	86786.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1000	2x6 sq mm + 1x6 sq mm earth wire	metre	2886	2886	823	6595.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1001	2x10 sq mm + 1x6 sq mm earth wire	metre	150	150	150	450.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1002	2x16 sq mm + 1x6 sq mm earth wire	metre	25	26	20	71.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1003	4x2.5 sq mm + 2x2.5 sq mm earth wire	metre	20	21	24	65.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1004	4 X 4 sq. mm + 2 X 4 sq. mm earth wire	metre	425	446	425	1296.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1005	4 X 6 sq. mm + 2 X 6 sq. mm earth wire	metre	515	541	515	1571.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1006	4x10 sq mm + 2x6 sq mm earth wire.	metre	712	748	712	2172.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1007	4x16 sq mm + 2x6 sq mm earth wire.	metre	25	21	10	56.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.									-	-	-	-	-	-	-	-	-	-	-	-	-	-
1008	5/6 A switch	each	74	34	79	187.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
1009	2 way 5/6 A switch	each	7	3	10	20.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1010	15/16 A switch	each	840	816	617	2273.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1011	3 pin 5/6 A socket outlet	each	7	2	10	19.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1012	6 pin 15/16 A socket outlet	each	192	187	253	632.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1013	Telephone socket outlet	each	9	4	10	23.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1014	TV antena Socket Outlet	each	25	26	25	76.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1015	Bell push	each	10	8	9	26.80				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supplying and fixing following size/ modules, GI box along with modular base and cover plate for modular switches in recess etc as required.									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1016	1 or 2 Module (75mmX75mm)	each	316	316	316	948.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1017	3 Module (100mmX75mm)	each	15	15	15	45.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1018	4 Module (125mmX75mm)	each	12	12	12	36.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1019	6 Module (200mmX75mm)	each	11	11	11	33.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1020	8 Module (125mmX125mm)	each	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1021	12 Module (200mmX150mm)	each	9	2	10	21.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	each	10	6	10	26.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1023	Supplying and drawing co-axial TV cable RG-6 grade, 0.7 mm solid copper conductor PE insulated, shielded with fine tinned copper braid and protected with PVC sheath in the existing surface/ recessed steel/ PVC conduit as required.	metre	2000	2000	2000	6000.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1024	20 mm dia	metre	5557	5557	5200	16314.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1025	25 mm dia	metre	8771	8771	8300	25842.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1026	32 mm dia	metre	1359	1359	1250	3968.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1027	Supplying and fixing call bell/ buzzer suitable for single phase, 230 V, complete as required.	each	7	5	7	19.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1028	Supplying and fixing modular blanking plate on the existing modular plate & switch box excluding modular plate as required.	each	272	271	272	815.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1029	Providing and fixing circular/ Hexagonal cast iron or M.S. sheet box for ceiling fan clamp, of internal dia 140 mm, 73 mm height, top lid of 1.5 mm thick M.S. sheet with its top surface hacked for proper bonding, top lid shall be screwed into the cast iron/ M.S. sheet box by means of 3.3 mm dia round headed screws, one lock at the corners. Clamp shall be made of 12 mm dia M.S. bar bent to shape as per standard drawing.	each	20	20	20	60.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supplying and fixing of following sizes of STEEL conduit alongwith the accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required.									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1030	20mm dia	metre	20	20	25	65.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1031	25mm dia	metre	35	15	30	80.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1032	32mm dia	metre	50	30	15	95.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
II	Sub Head 47 : Distribution Board									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	MCB DB									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount												
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total			
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	
	OUTGOING																					
	10 nos 63 Amp TPN Moulded Case Circuit Breaker																					
	1 Lot of control / power wiring.																					
	(PTTA Type panels are considered)																					
	All MCCB's shall be of 35 KA breaking capacity.																					
1061	Lift Panel described as above	set	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-
	EMERGENCY LIGHT PANEL- (MAIN BLOCK)																					
	INCOMING																					
	1 no 63 Amp FP Moulded case Circuit Breaker																					
	1 set of phase indicating lamps (R, Y & B) and shall be protected by 2 amps SP MCB's.																					
	1 set of ON / OFF indicating lamps and shall be protected by 2 amps SP MCB's.																					
	1 no 63 Amps Digital MFM metre with CT's metre with RS 485 port and should communicate on Modbus RTU with 3 no. 63/5 amps 15 VA, CL 1 secondary CTs to measure and display.																					
	BUS BAR																					
	100 Amp FP copper busbar with heat shrinkable insulation sleeve.																					
	OUTGOING																					
	18 nos 25 Amp DP Miniature Circuit Breaker																					
	05 nos 40A DP Miniature Circuit Breaker.																					
	01 no 40A FP Miniature Circuit Breaker.																					
	1 Lot of control / power wiring.																					
	(PTTA Type panels are considered)																					
	All MCCB's shall be of 35 KA breaking capacity.																					
1062	Emergency Light Panel described as above	set	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-
	MAIN UPS PANEL- (2 x 160 KVA) - MAIN BLOCK																					
	INCOMING																					
	02 nos 800Amp FP Moulded Case Circuit Breaker																					
	02 nos 630Amp FP Moulded Case Circuit Breaker																					
	2 set of phase indicating lamps (R, Y & B) and shall be protected by 2 amps SP MCB's.																					
	2 set of ON / OFF indicating lamps and shall be protected by 2 amps SP MCB's.																					
	2 nos 630 Amps Digital MFM metre with CT's metre with RS 485 port and should communicate on Modbus RTU with 3 nos. 630/5 amps 15 VA, CL 1 secondary CTs to measure and display.																					
	BUS BAR																					
	1000 Amp TPN Copper bus bar with heat shrinkable insulation sleeve.																					
	OUTGOING																					
	03 nos 1000 Amp FP Air Circuit Breaker																					
	03 nos 125 Amp FP Moulded Case Circuit Breaker																					
	03 nos 63 Amp FP Moulded Case Circuit Breaker																					
	1 Lot of control / power wiring.																					

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
	All MCCB's shall be of 35 KA breaking capacity.																							
1065	RADIOLOGIST PANEL described as above	set	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	UTILITY PANEL																							
	INCOMING																							
	1 no 160 Amp FP Moulded Case Circuit Breaker																							
	1 set of phase indicating lamps (R, Y & B) and shall be protected by 2 amps SP MCB's.																							
	1 set of ON / OFF indicating lamps and shall be protected by 2 amps SP MCB's.																							
	1 no 160 Amps Digital MFM metre with CT's metre with RS 485 port and should communicate on Modbus RTU with 3 no. 160/5 amps 15 VA, CL 1 secondary CTs to measure and display.																							
	BUS BAR																							
	160 Amp TPN aluminium busbar with heat shrinkable insulation sleeve.																							
	OUTGOING																							
	04 nos 125 Amp FP Moulded Case Circuit Breaker																							
	02 nos 63 Amp TPN Miniature Circuit Breaker																							
	1 Lot of control / power wiring.																							
	(PTTA Type panels are considered)																							
	All MCCB's shall be of 35 KA breaking capacity.																							
1066	Utility Panel described as above	set	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	EXTERNAL LIGHTING PANEL																							
	INCOMING																							
	1 no 63 Amp FP (10 KA Ics) Moulded Case Circuit Breaker.																							
	1 no 0 to 500 Volt digital voltmeter with inbuilt selector switch.																							
	1 no 63 Amp digital ammeter with inbuilt selector switch and CT's.																							
	1 set of phase indicating lamps with Single Pole MCB.																							
	1 set of ON / OFF indicating lamps with Single Pole MCB.																							
	1 set 24 Hrs TSQ Timer																							
	1 set 63 Amp, 4P Contactor & A/M switch and Push Button.																							
	BUS BARS																							
	100 Amp TPN aluminium busbar.																							
	OUTGOING																							
	12 nos 25 Amp DP MCB.																							
	04 nos 40 Amp DP MCB.																							
	04 nos 40 Amp FP MCB.																							
1067	Panel described as above	set	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	PHE PANEL																							
	INCOMING																							
	1 no 125 Amp FP Moulded Case Circuit Breaker.																							
	2 set of phase indicating lamps (R, Y & B) and shall be protected by 2 amps SP MCB's.																							

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
1078	800 A, Isc= 50kA for 1 sec	metre	70	70	70	210.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1079	1000 A, Isc= 50kA for 1 sec	metre	70	70	70	210.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	END FEED UNIT-																						
	Supplying, installation, testing & commissioning of following capacity End Feed Unit for the existing Air Insulated Compact Type bus trunking/ rising mains for use on 3 phase 4 wire 415 volts, 50Hz A.C. supply made with 1.6mm thick steel sheet enclosure (IP54) duly powder coated with provision of MCCB/ACB (but without MCCB/ACB) complete with necessary joints including clamping brackets, angle iron bracket, steel fasteners, connecting to earthing system etc. as required.																						
1080	400 A, Isc= 30kA for 1 sec	set	2	2	2	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1081	800 A, Isc= 50kA for 1 sec	set	2	2	2	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1082	1000 A, Isc= 50kA for 1 sec	set	2	2	2	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	TAP OFF UNIT																						
	Supplying, installation, testing & commissioning of following capacity Plug In/ tap off box on the existing Air Insulated Compact Type bus trunking/ rising mains for use on 3 phase 4 wire 415 volts, 50Hz A.C. supply made with 1.6mm thick steel sheet enclosure (IP54) duly powder coated with provision of MCCB/ACB (but without MCCB/ACB) complete etc. as required.																						
1083	125 A, Isc= 15kA for 1 sec	each	26	22	18	66.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1084	200 A, Isc= 25kA for 1 sec	each	4	2	8	14.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1085	250 A, Isc= 30kA for 1 sec	each	12	12	18	42.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1086	400 A, Isc= 35kA for 1 sec	each	2	2	2	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Providing and fixing following rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required.																						
1087	100 A, 16 KA,FP MCCB	each	1	1	3	5.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1088	150 A, 16 KA,TPMCCB	each	29	25	18	72.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1089	200 A.36KA.FPMCCB	each	4	2	8	14.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1090	250 A.36KA.FPMCCB	each	14	14	18	46.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1091	250 A.50KA.FPMCCB	each	4	2	2	8.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1092	400 A.50KA.FPMCCB	each	2	2	2	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1093	800 A.50KA.TPMCCB	each	2	2	2	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	BUSDUCT																						
1094	Supply and erection of Busbar Trunking-3 Ph., 4-wire, 415V, 50-Hz. Busduct shall be fabricated out of 14 SWG CRCA Sheet with adequate sizing, double earthing and ventilation grills, vermin proof Degree of protection IP-55 Busbar Rating - Electrolytic grade Aluminium 2500A.TPN (From TRANSFORMER & DG to MV panel)	metre	70	70	70	210.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
III	Sub Head 48 : Light Fixtures & Fans																						
1095	Supplying and fixing brass batten/ angle holder including connection etc. as required.	each	10	5	8	23.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
1096	Installation, testing and commissioning of ceiling fan, including wiring the down rods of standard length (upto 30 cm) with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable, including providing and fixing phenolic laminated sheet cover on the fan box etc as required.	each	217	217	116	550.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1097	Installation of exhaust fan upto 450mm in the existing opening, including making the hole to suit the size of the above fan, making good the damage, connection, testing, commissioning etc as required.	nos	2	8	0	10.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1098	Extra for fixing the louvers/ shutters complete with frame for a exhaust fan of all sizes.	each	221	234	225	680.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1099	Supply, Testing & Commissioning of 300 mm, 230 v A.C. exhaust fan in the existing opening including making good the damage, connection testing, commissioning etc as required.	nos	117	117	125	359.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1100	Supply, Testing & Commissioning of 150 mm, 230 v A.C. exhaust fan in the existing opening including making good the damage, connection testing, commissioning etc as required.	nos	104	117	121	342.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1101	Supply, Installation, Testing and Commissioning of 1200 mm sweep, BEE 5 star rated, ceiling fan with Brush Less Direct Current (BLDC) Motor, class of insulation: B, 3 no. blades, 30 cm long down rod, 2 no. canopies, shackle kit, safety rope, copper winding, Power Factor not less than 0.9, Service Value (CMM/W) minimum 6.85, Air delivery minimum 215 CMM, 350 RPM (tolerance as per IS : 374-2019), THD less than 10%, remote or electronic regulator unit for speed control and all remaining accessories including safety pin, nut bolts, washers, temperature rise=75 degree C (max.), insulation resistance more than 2 mega ohm, suitable for 230 V, 50 Hz, single phase AC Supply, earthing etc. complete as required.	nos	217	217	114	548.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1102	Supply, Installation, Testing & Commissioning of 400 mm, 230 v A.C.wall/cabin fan including fixing the bracket, making connection etc as required.	nos	372	371	398	1141.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1103	Supply, Installation, Testing & Commissioning of IP20 Recessed 10W LED Downlighter made of pressure die cast aluminum housing. Fixture should have minimum efficacy at System level (not Chip Level) >=110 lumens/watt with Minimum system Lumens 1000 with maximum system wattage of 9W. Life of fixture (Including Driver) : 50000 burning Hrs. @ L70B50 Lumen maintenance, CCT of 300K/4000K/5700K/6500K (SDCM<5), CRI >80, PF >0.95, working temp range - 0°C < Ta < 45°C, and operating Voltage Range of 240 VAC. It should has a Minimum Internal Surge Protection of 2.5KV. Electronic Switchable ballast. The fixture design should comply with EMC / EMI compliance along with BIS certification for LED Driver & Luminaire.Luminaire manufacture shall provide LM79report from NABL accredited lab & LM80 report issued by LED manufacturer.	nos	131	132	164	427.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
1104	Supply Installation, testing & commissioning of Integral Mirror light LED 2 ft luminaire made of CRCA housing and PC diffuser (Diffuser-non yellowing type). The luminaire should have a LEDs with colour consistency SDCM ≤ 5, CRI ≥ 80 and CCT of 3000K/400K/5700K/6500K. Luminaire shall be designed to emit at least minimum 2000 system lumens at a system efficacy of at-least 120 lumen/watt. Power consumption should not be more than 12W (±5%). The Life of fixture (Including Driver):50000 burning Hrs. @ L70B50 Lumen maintenance @ design ambient temp 45 deg C. The electronic driver used shall have a power factor ≥0.95 and THD ≤10%, suitable for an operating voltage range of 140-270V AC, Current Ripple ≤5%, Internal surge protection should be minimum 4KV, electrical insulation class should be Class I & driver should be of Class B serviceability. The luminaire shall be IP20 & IK02 compliant. The minimum dimensions (±5mm) of the batten shall be 44mm(±5mm) X 51mm (±5mm)X 585mm(±5mm). Luminaire manufacturer must have NABL accredited lab to conduct LM79, Type test as per IS10322 & "FAT" before dispatch as per IS 10322. The the successful bidder must submit the NABL accreditation certificate for Luminaire manufacturer along with Technical bid. The LED Luminaire & it's driver both should be BIS registered.	nos	82	91	98	271.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1105	Supply, Installation, Testing & Commissioning of 18W to 22W LED downlight recess IP20 Downlighter made of pressure die cast aluminum housing. Fixture should have minimum efficacy at System level (not Chip Level) ≥110 lumens/watt with Minimum system Lumens 1500 with maximum system wattage of 13.5W. Life of fixture (Including Driver) : 50000 burning Hrs. @ L70B50 Lumen maintenance, CCT of 3000K/4000K/5700K/6500K (SDCM<5), CRI >80, PF >0.95, working temp range - 0°C < Ta < 45°C, and operating Voltage Range of 240 VAC. It should has a Minimum Internal Surge Protection of 2.5KV. Electronic Switchable ballast. The fixture design should comply with EMC / EMI compliance along with BIS certification for LED Driver & Luminaire.Luminaire manufacture shall provide LM79report from NABL accredited lab & LM80 report issued by LED manufacturer.	nos	171	183	252	606.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1106	Supply, Installation, Testing & Commissioning of surface mounted Linear Batten 40W 4ft luminaire of CRCA housing and PC diffuser (Diffuser-non yellowing type). The luminaire should have a color consistency SDCM ≤ 5, CRI ≥ 80 and CCT of 3000K/4000K/5700K/6500K.The luminaire shall be compliant with IP20 classification. Luminaire shall be designed to emit at least 4000 nominal lumens at a system efficacy of minimum 120 lumen/watt. Power consumption should not be more than 36W. The luminaire shall have CRI≥80. The Life of fixture (Including Driver):50000 burning Hrs. @ L70B50 Lumen maintenance @ design ambient temp 45 deg C. The electronic driver used shall have a power factor ≥0.95 @ full load and THD ≤10% @ full load and suitable for an operating voltage range of 140-270V AC. Ripple ≤5% and surge protection should be minimum 4KV, electrical insulation class should be Class I & driver should be of Class B serviceability. Driver should have high & low voltage cut off with auto restart @140-270V. The LED driver should comply to IEC61000-3-2 ed.3.2, 2009 for Harmonics, IEC61347 -2 -13, 2006 in Conjunction with IEC61347-1 ed.2.0, 2007 for Electrical Safety, CISPR 15/ EN 55015 (9 KHz to 30MHz) for RFI, EMI/EMC, IEC 62384 for driver performance test.	each	611	598	535	1744.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	The luminaire driver shall be of the same make/manufacturer/brand as that of LED luminaires. The luminaire driver shall have efficiency of ≥85%. The LED luminaire manufacturer should have NABL accredited lab to conduct type test, factory acceptance test.																						

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
1107	Supply, Installation, Testing & Commissioning of 36W to 40W 2X2 LED flat panel for surface mounting which provides soft-light and glare free symmetrical illumination.CRCA powder coated white after phosphochromate treatment and High transmittance polystyrene opal diffuser. High efficiency long life LED package in integral module with system lumen efficacy of >110 lm/W and viewing angle of 120° to ensure better uniformity.Powered by built-in Isolated, SELV Output electronic LED driver (SMPS based constant current supply) with Output Short-circuit protection, Surge protection & other reliability test. CRI >80, Color temperature 3000K/4000K/5700K/6500K, THD <20% and PF >0.95,IP20, IK03.Lumen output of 4650 lumens.Life class of 50,000 hrs @ L70, Operating Temperature:-10 TO +45 DEG.C; Input Supply Voltage Range:140-270 V, Frequency :50-60 HZ; Internal Surge Protection:3 KV. The luminaire shall be designed so as to ensure L70B50 @ 30K Hrs.@ 45 Degree Ambient. The electronic driver used shall have a power factor >0.95 and THD <10% The fixture should comply with the pararms as per IS10322. Similar to SM367 LED42S-6500 G6 L54W54 PSU OD	each	891	922	882	2695.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1108	Supply, Installation, Testing and Commissioning of integral driver LED 5W wall light with a system lumen output of 40 lumens and a minimum system efficacy of 10 lm/W. The luminaire shall have a rated system lifetime of 25,000 burning hours at L70. The luminaire should have a color temperature of 3000K/4000K/5700K/6500K and CRI > 75. The luminaire shall meet IP67 rating with THD < 20% and PF > 0.9. The luminaire shall have polycarbonate diffuser.	each	16	16	0	32.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1109	Supply, Installation, Testing & Commissioning of 20W wall mounted 4ft luminaire of CRCA housing and PC diffuser (Diffuser-non yellowing type). The luminaire should have a LEDs with colour consistency SDCM ≤ 5, CRI ≥ 80 and CCT of 3000K/4000K/5700K/6500K. Luminaire shall be designed to emit at least 2000 nominal lumens at a system efficacy of at-least 120 lumen/watt. Power consumption should not be more than 16W (±5%). The Life of fixture (Including Driver):50000 burning Hrs. @ L70B50 Lumen maintenance @ design ambient temp 45 deg C. The electronic driver used shall have a power factor ≥0.95 and THD ≤10%, suitable for an operating voltage range of 140-270V AC, Current Ripple ≤5%, Internal surge protection should be minimum 4KV, electrical insulation class should be Class I & driver should be of Class B serviceability.The luminaire should be at least IP20 & IK02 rated. Luminaire manufacturer must have In-house NABL accredited lab to conduct LM79, Type test as per IS10322 & "FAT" before dispatch as per IS 10322. The LED Luminaire & it's driver both should be BIS registered.	nos	220	257	288	765.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1110	Supply, Installation, Testing & Commissioning of 20W 2X2 Recess LED flat panel for which provides soft-light and glare free symmetrical illumination.CRCA powder coated white after phosphochromate treatment and High transmittance polystyrene opal diffuser. High efficiency long life LED package in integral module with system lumen efficacy of >95 lm/W and viewing angle of 120° to ensure better uniformity.Powered by built-in Isolated, SELV Output electronic LED driver (SMPS based constant current supply) with Output Short-circuit protection, Surge protection & other reliability test. CRI >80, Color temperature 3000K/4000K/5700K/6500K, THD <20% and PF >0.95,IP20, IK03.Lumen output of 2400 lumens.Life class of 50,000 hrs @ L70, Operating Temperature:-10 TO +45 DEG.C; Input Supply Voltage Range:140-270 V, Frequency :50-60 HZ; Internal Surge Protection:3 KV.	nos	964	988	815	2767.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
1111	Supply, Installation, Testing & Commissioning of Surface mounted 10/12 watt LED type Bulk-head fitting 1100lm made up of pressure die-cast aluminium housing and Polyester Powder coated with High quality polycarbonate diffuser in opal finish for glare free light distribution.High efficiency long life LED module with SMD LED package efficacy of >110 lm/W. Powered by integral electronic LED driver with CCT 3000K/4000K/5700K/6500K, CRI>80,THD<10%, PF>0.9, IP66, IK 09, Life class of 50,000 hrs @ L70, Operating Temperature: 0 TO +45 DEG.C; Input Supply Voltage Range:140-270 V, Frequency :50-60 HZ. Driver Safety requirement standards:IS 15885, Test Report to be submitted, Photobiological Safety norms: IS 16108, test Certificate to be submitted, Certification: LM79 for Luminaire, Lm80 for LED Source.	nos	138	138	114	390.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1112	Supply, Installation, Testing & Commissioning of Surface mounted 10 watt LED vertical downlighter having dia of 130mm(± 3mm) & height of 60mm(± 3mm) delivering minimum system lumen output of 1000 lumens (±5%) and system wattage of 10W (±5%) & with a minimum system efficacy of 100 lm/W. The luminaire should have a color temperature of 3000K/4000K/5700K/6500°K, CRI≥80 and SDCM≤5. The driver shall have THD≤10% (@full Load) and PF ≥ 0.95 (@full load). The luminaire housing should made of pressure die-cast aluminum. The fixture should comply with the params as per IS10322. The luminaire shall have impact resistance of IK02 & ingress protection of IP20. Luminaire manufacturer must have In-house NABL accredited lab to conduct LM79, Type test as per IS10322 & "FAT" before dispatch as per IS 10322. The the successful bidder must submit the NABL accreditation certificate for Luminaire manufacturer along with Technical bid. The LED Luminaire should be BIS registered.	nos	160	160	152	472.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1113	Supply, Installation, Testing & Commissioning of Recess mounted 70 watt LED High bay vertical downlighter complete with all accessories and replaceable electronic driver, directly on false ceiling including connection with 1.5 sqmm FR PVC insulated copper conductor cable and earthing the body etc. as required.	each	34	34	33	101.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1114	Supplying, Installation, Testing and Commissioning of Microwave technology based occupancy sensor having high performance, non regulating programmable type, suitable for connected load upto 10Amp , for mounting height up to 2.6 m and for 5m X 20m coverage area along with necessary fixing arrangements i/c programming at site etc. complete as required.	each	2	2	0	4.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1115	Supply, Installation, Testing & Commissioning of Aviation obstruction light with Light Emitting Diodes (LEDs) similar to Bajaj make cat no BGAV 302 LED or its equivalent as per approved list of make complete with all accessories as required.	each	2	2	0	4.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
IV	Sub Head 49 : Cable, Cable Tray & Termination																							
1	Supply, Installation, Testing & Commissioning of following sizes of 1.1KV grade multistranded copper conductor PVC insulated cable including termination complete as required in existing cable tray / existing conduit.																							
1116	1C x 6 sqmm PVC Insulated cu wire including termination etc.	metre	26	29	25	80.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1117	1C x 10 sqmm PVC Insulated cu wire including termination etc.	metre	5	5	5	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1118	1C x 16 sqmm PVC Insulated cu wire including termination etc.	metre	7	7	7	21.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1119	1C x 25 sqmm PVC Insulated cu wire including termination etc.	metre	215	237	205	657.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1120	1C x 50 sqmm PVC Insulated cu wire including termination etc.	metre	21	23	21	65.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1121	1C x 95 sqmm PVC Insulated cu wire including termination etc.	metre	7	11	11	29.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1122	1C x 120 sqmm PVC Insulated cu wire including termination etc.	metre	315	347	309	971.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supply of following sizes of 1.1KV grade copper conductor XLPE insulated PVC sheathed (Heavy duty) armoured cable conforming to relevant IS. (Cable shall be purchased only after approval of cable schedule by architect / consultant).																							

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
1123	4 core, 16 sq. mm. Cu. Armoured Cable	metre	408	408	350	1166.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1124	4 core, 10 sq. mm. Cu. Armoured Cable	metre	483	483	580	1546.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1125	4 core, 6 sq. mm. Cu. Armoured Cable	metre	1997	1997	1812	5806.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1126	3 core, 6 sq. mm. Cu. Armoured Cable	metre	5	20	0	25.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supply of following sizes of 1.1KV grade aluminium conductor XLPE insulated PVC sheathed (Heavy duty) armoured cable conforming to relevant IS. (Cable shall be purchased only after approval of cable schedule by architect / consultant).																							
1127	4C x 2.5 sqmm.	metre	1730	1817	1029	4575.50				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1128	4C x 4 sqmm.	metre	257	257	230	744.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1129	4C x 6 sqmm	metre	1805	1805	3199	6809.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1130	4C x 10 sqmm	metre	1272	1272	490	3034.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1131	4C x 16 sqmm	metre	977	977	930	2884.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1132	3.5C x 25 sqmm	metre	9234	9234	6614	25082.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1133	3.5C x 35 sqmm	metre	473	473	450	1396.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1134	3.5C x 50 sqmm.	metre	569	569	715	1853.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1135	3.5C x 70 sqmm	metre	294	294	598	1186.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1136	3.5C x 95 sqmm.	metre	473	473	28	974.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1137	3.5C x 120 sqmm.	metre	133	133	63	329.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1138	3.5C x 150 sqmm.	metre	15	10	53	78.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1139	3.5C x 185 sqmm.	metre	1598	1598	1960	5156.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1140	3.5C x 240 sqmm.	metre	1911	1911	3525	7347.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1141	3.5C x 300 sqmm.	metre	3912	3912	5979	13803.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supply & making end termination with brass compression gland & aluminium lugs for following size of FRLS insulated and FRLS sheathed aluminium conductor cable of 1.1KV grade as required.																							
1142	2 X 6 sq. mm (19mm) For copper armoured cable	set	62	62	58	182.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1143	4 X 6 sq. mm (25mm) For copper armoured cable	set	66	66	58	190.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1144	4 X 10 sq. mm (25mm) For copper armoured cable	set	32	32	28	92.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1145	4 X 16 sq. mm (28mm) For copper armoured cable	set	17	17	15	49.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1146	4 X 25 sq. mm (28mm) For aluminium armoured cable	set	250	244	218	712.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1147	3.5 X 35 sqmm (32 mm) For aluminium armoured cable	set	11	11	9	31.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1148	3.5 X 50 sqmm (35 mm) For aluminium armoured cable	set	45	45	43	133.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1149	3½ X 70 sq. mm (38mm) For aluminium armoured cable	set	12	12	12	36.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1150	3½ X 95 sq. mm (45mm) For aluminium armoured cable	set	4	4	4	12.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1151	3½ X 120 sq. mm (45mm) For aluminium armoured cable	set	6	6	6	18.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1152	3.5 X 150 sqmm (50 mm) For aluminium armoured cable	set	4	5	4	13.25				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1153	3½ X 185 sq. mm (57mm) For aluminium armoured cable	set	53	53	52	158.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1154	3½ X 240 sq. mm (63mm) For aluminium armoured cable	set	33	33	31	97.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1155	3½ X 300 sq. mm (70mm) For aluminium armoured cable	set	55	55	52	162.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on cable tray as required.																							
1156	Upto 35 sq. mm (clamped with 1mm thick saddle)	metre	12169	12270	9870	34309.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1157	Above 35 sq. mm and upto 95 sq. mm (clamped with 25x3mm MS flat clamp)	metre	316	316	356	988.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1158	Above 95 sq. mm and upto 185 sq. mm (clamped with 25/40x3mm MS flat clamp)	metre	450	450	575	1475.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1159	Above 185 sq. mm and upto 400 sq. mm (clamped with 40x3mm MS flat clamp)	metre	2450	2450	4865	9765.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount															
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total						
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)				
1183	150 mm wide x 50 mm depth x 1.6 mm thickness.	nos	115	121	115	351.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1184	300 mm wide x 50 mm depth x 1.6 mm thickness.	nos	70	73	70	213.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1185	450 mm wide x 50 mm depth x 2.0 mm thickness.	nos	56	58	56	170.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1186	600 mm wide x 50 mm depth x 2.0 mm thickness.	nos	10	12	5	27.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1187	750 mm wide x 62.5 mm depth x 2.0 mm thickness.	nos	200	210	200	610.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1188	900 mm wide x 62.5 mm depth x 2.0 mm thickness.	nos	5	6	10	21.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
	Supplying and installing following size of perforated Hot Dipped Galvanised Iron cable tray "Tee" (galvanisation not less than 50 microns) with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with G.I. suspenders including G.I. bolts & nuts, etc. as required.																								
1189	100 mm wide x 50 mm depth x 1.6 mm thickness.	nos	25	26	25	76.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1190	150 mm wide x 50 mm depth x 1.6 mm thickness.	nos	166	175	166	507.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1191	300 mm wide x 50 mm depth x 1.6 mm thickness.	nos	40	42	40	122.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1192	450 mm wide x 50 mm depth x 2.0 mm thickness.	nos	142	149	142	433.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1193	600 mm wide x 50 mm depth x 2.0 mm thickness.	nos	16	16	16	48.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1194	750 mm wide x 62.5 mm depth x 2.0 mm thickness.	nos	30	32	30	92.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1195	900 mm wide x 62.5 mm depth x 2.0 mm thickness.	nos	5	6	5	16.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
	Supplying and installing following size of perforated Hot Dipped Galvanised Iron cable tray "Cross member"(galvanisation not less than 50 microns) with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with G.I. suspenders including G.I. bolts & nuts, etc as required.																								
1196	100 mm wide x 50 mm depth x 1.6 mm thickness.	nos	25	26	25	76.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1197	150 mm wide x 50 mm depth x 1.6 mm thickness.	nos	5	29	5	39.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1198	300 mm wide x 50 mm depth x 1.6 mm thickness.	nos	4	4	4	12.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1199	450 mm wide x 50 mm depth x 2.0 mm thickness.	nos	7	7	2	16.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1200	600 mm wide x 50 mm depth x 2.0 mm thickness.	nos	4	4	2	10.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1201	750 mm wide x 62.5 mm depth x 2.0 mm thickness.	nos	10	10	10	30.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1202	900 mm wide x 62.5 mm depth x 2.0 mm thickness.	nos	5	5	2	12.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
	Supplying and installing following size of perforated Hot Dipped Galvanised Iron cable tray "Reducer"(galvanisation not less than 50 microns) with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with G.I. suspenders including G.I. bolts & nuts, etc as required.																								
1203	100 mm wide x 50 mm depth x 1.6 mm thickness.	nos	10	10	12	32.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1204	150 mm wide x 50 mm depth x 1.6 mm thickness.	nos	169	200	169	538.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1205	300 mm wide x 50 mm depth x 1.6 mm thickness.	nos	44	45	44	133.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1206	450 mm wide x 50 mm depth x 2.0 mm thickness.	nos	20	20	12	52.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1207	600 mm wide x 50 mm depth x 2.0 mm thickness.	nos	9	9	9	27.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1208	750 mm wide x 62.5 mm depth x 2.0 mm thickness.	nos	30	32	30	92.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
1209	900 mm wide x 62.5 mm depth x 2.0 mm thickness.	nos	6	5	5	16.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
V	Sub Head 50 : Raceway & Junction Board																								

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
1226	Supply, Installation, Testing & Commissioning of Network Resource Interface, 4 channels network audio source, 32 dry contacts in and 8 try contacts out for Fire Alarm Interface	set	5	5	5	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1227	Supplying, installation, testing & commissioning of 1.5/3/6W ceiling speaker complete as required.	each	208	214	208	630.24				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1228	Supplying, installation, testing & commissioning of 1.5/3/6W metal box ceiling/wall speakers complete as required.	each	126	130	126	381.78				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1229	Supplying, installation, testing & commissioning of ceiling/wall mounted loud speaker, 3/1.5 Watt in ABS enclosure complete as required.	each	5	4	0	9.12				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1230	Supply, Installation, Testing and Commissioning of 12 Watt volume controller with G.I. Box, modular plate etc as complete as required.	set	5	5	5	15.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1231	Supplying and drawing of cable Fire Retardant PVC insulated copper conductor cable in the existing surface / recessed steel conduit of following pairs, cores and size including connections and interconnections etc. as required. speaker cable Single pair, 2-core, 1.5 sqmm	metre	5647	5647	5647	16941.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1232	Supplying and fixing 25 mm dia MS flexible pipe with PVC coating along with all ancillaries and accessories like coupler etc. as required.	each	1291	1291	1291	3873.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1233	Supply, Installation, Testing and Commissioning of 42" MS Rack Suitable to house the above required equipments, With Glass Door, Side Openable, Cooling arrangement, Wheels and brakes and as per technical specification.	set	8	8	8	24.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1	ELV AND ICT SYSTEM Sub Head 52 : Passive (Data, Wifi & Networking System)																						
1234	Supply, Insatllation, Testing & Commissioning of Category 6A cable as per Specification	Box 305metre	52	52	52	155.41				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1235	Supply, Insatllation, Testing & Commissioning of Category 6A UTP Patch Panel Blank Tool Less 24 Port	nos	35	35	35	105.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1236	Supply, Insatllation, Testing & Commissioning of Category 6A UTP Keystone Jack Tool Less 180D	nos	316	316	316	948.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1237	Supply, Installation, Testing and Commissioning of Category 6A U/UTP Patch Cord LSZH 01M	nos	316	316	316	948.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1238	Supply, Installation, Testing and Commissioning of Category 6A U/UTP Patch Cord LSZH 02M	nos	316	316	316	948.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1239	Supply, Insatllation, Testing & Commissioning of UK Face Plate Plain 01 Port	nos	316	316	316	948.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1240	Supply, Insatllation, Testing & Commissioning of Category 6A UTP Keystone Jack Tool Less 180D	nos	316	316	316	948.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1241	Supply, Insatllation, Testing & Commissioning of 6 Core Singlemode OS2 Central Loose Tube Armoured External Cable	metre	3500	3500	3500	10500.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1242	Supply, Insatllation, Testing & Commissioning of Sliding Module Type Fibre Patch Panel Rack Mount	nos	35	35	35	105.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1243	Supply, Insatllation, Testing & Commissioning of Blank Adaptor Plate	nos	35	35	35	105.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
1244	Supply, Insatllation, Testing & Commissioning of SC 3 Port Duplex Adaptor Plate	nos	70	70	70	210.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1245	Supply, Insatllation, Testing & Commissioning of SC Singlemode Duplex Adaptor	nos	70	70	70	210.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1246	Supply, Insatllation, Testing & Commissioning of SC/PC Singlemode OS2 1.5m LSZH Pigtail	nos	70	70	70	210.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1247	Supply, Insatllation, Testing & Commissioning of SC/PC-LC/PC Singlemode OS2 3m Duplex LSZH Patch Cord	nos	70	70	70	210.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1248	Supply, Insatllation, Testing & Commissioning of 42U Rack with 2000W Panel AC Solution with all accessories. Loaded with all Accessories like PDU ,Sliding Shelf, Cable Manager, Mounting Kits, Castor set.	nos	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1249	Supply, Insatllation, Testing & Commissioning of 12U Rack with all accesories	nos	35	35	35	105.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1250	Supply, Insatllation, Testing & Commissioning of 40mm PVC Conduit Pipe	nos	5698	5698	5698	17094.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1251	Supply, Insatllation, Testing & Commissioning of 50mm PVC Flexible Pipe	nos	100	100	100	300.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1252	Supply, Insatllation, Testing & Commissioning of HDPE Pipe 32mm	nos	200	200	200	600.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
II	Sub Head 53 : Active ICT (Access Control, Display, IP Based CCTV Camera &Telephone)																						
1253	Supply, Insatllation, Testing & Commissioning of Latest 802.11ax Wi-Fi 6 Dual Band indoor AP, with 1.7 Gbps access throughput.	nos	28	28	28	84.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1254	Supply, Insatllation, Testing & Commissioning of 24 X 1G RJ-45 PoE+ Ports with 370W power budget 2 x 10G Copper Ports and 4 x 10G SFP+ slots, upgradable to support up to 740watt PoE by additional power supply.	nos	28	28	28	84.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1255	Supply, Installation, Testing and Commissioning of 24 X 1/10G SFP+ Ports, RAM - 2GB, Flash 2 GB with 3 year warranty and support.	nos	7	7	7	21.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1256	Supply, Insatllation, Testing & Commissioning of Next Generation Firewall with Anti-Virus, IPS, Anti-BOT & Anti-Spam, Application Control and URL Filtering features from Day-1 with 3 years manufacturer's warranty support, should be in leaders quadrant in Gartner report. The the quoted appliance should be in line with the technical specification with 3 years warranty.	nos	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1257	Supply, Insatllation, Testing & Commissioning of Wireless access controller for Max 256 Access Points with high reliability.	nos	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1258	Supply, Installation, Testing and Commissioning of 43" 4K UHD (3840x2160) commercial display, Ready resolution, Brightness- 400 Nits and operating Hours- 24x7 or better, with 2K HDR, Dolby Audio, Built in Wifi and Chromecast, Built in web browser, HDMI CEC, HDMI ARC, Built-in Bluetooth Ver.4, 20W built in speakers, HDMI 2.0 X 3, AV X 1, USB 2.0 X 1, RJ45 X 1, Headphone Out x 1, SPDIF Out x 1	nos	21	21	21	63.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
1259	Supply, Installation, Testing and Commissioning of 13th Generation Intel® Core™ i5 processor, Windows 11 Professional, Intel® UHD Graphics 730,8 GB DDR4 RAM,512 GB SSD Solid State Drive, 125 USB Black Wired Keyboard, 1 VGA; 1 HDMI-out 1.4b, 21.5 Inch display with 3 year Warranty and support.	nos	176	176	176	528.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1260	Supply, Installation, Testing and Commissioning of Laser Jet/Ink jet colour office printer with 3 year warranty and support. Minimum print speed 40 perminute , processor speed 600 MHZ and more., network interface, wireless & wireline, usb port with redundant tray with 3 year warranty and support.	nos	26	26	26	78.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1261	Supply, Installation, Testing and Commissioning of Dome 3 MP resolution; H.265 Codec; 1/2.8" CMOS ; Shutter Speed of 1/8s ~ 1/32,000s; 2.8mm Fix Lens; 3DNR;BLC;HLC;WDR 120 dB;40 Mtr IR, Analytics -,Analytics - : Tampering, Motion Detect Aluminum housing; SD Card Slots 256GB; IP67; IK10; TLS1.2 only; AES- 256;SSH / Telnet closed; sFTP by default; PCIDSS compliance; ONVIF Profile S,T & G; Certificates- CE, FCC, RoHS, BIS,UL, 05 Yrs OEM Warranty, OEM Authorization, OEM should have factory in India since 2012	nos	110	110	110	330.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1262	Supply, Installation, Testing and Commissioning of 64ch NVR with ARM Processor, Embedded Linux;8 SATA up to 80 TB inbuilt storage supported ,3 x USB,Mamimum 16 user;2 Way Audio;LAN x 1, WAN x 1, 2 x HDMI, 1 VGA;RAID 5, Network throughput 160 Mbps ,Support redundancy Failover N+1, 16ch PoE, RS485 Supported,RS232 Supported,e-SATA Supported,Certificates - CE,FCC,RoHS,BIS,UL	nos	2	2	2	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1263	Supply, Installation, Testing and Commissioning of IP Based voice Communication System with 04 Port Voicemail ,04 Port FXS ,04 Port FXO ,4 PRI Trunk lines (30x4 Ch) Circuit with CLIP Facility, 200 IP users, 01 Nos. Conference facility, Speed Dial, Music on Hold, Internal/ External ring difference ,Call Barring, Call Pickup- Redundant server in Active-Active or Active -Standby mode with 3 Year Warranty and support.	nos	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1264	Supply, Installation, Testing and Commissioning of IP Phone with 128X48 with 2 line Keys, 4 menu keys, 2 SIP accounts, supporting temperature from -5 C to 45 C With 3 year Warranty and support.	nos	30	30	30	90.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
Total Bill no-6 Electrical system										-	-	-	-	-	-	-	-	-	-	-	-	-	-
7	Sub Head 54 : Lift System																						
1265	Supplying, installation, testing & commissioning of 26 Passenger lift (G+6) (1632 Kg) Gearless with Machine Room having speed of 1 MPS in the existing lift shaft at the site. The Size of Lift Well (2500 X 3050 mm) Lift Car Inside Size (1400x2550mm),Pit depth 1600mm with Stainless steel -Hairline finish for Lift & Car ceiling and floor.The type of the car entrance and Landing entrance production is power operated two panel centre opening sliding door with stainless steel (hairline finish).The type of Landing door frame is Stainless Steel(hairline finish).The clear opening of door is 1200mm x 2000mm.The control system are Microprocessor based simplex selective collective control with /without attendant of AC 415 V 3 PHASE 50 Hz WITH VOLTAGE VARIATION OF + 5 ~ - 10 % of Power supply for traction & 220 V 1 PHASE 50 Hz OF + 5 ~ - 10 % for Cabin lighting The rate shall include Necessary Labour,fitings, annual maintainance ,etc to complete. including cost and conveyance of all material, accessories, labour charges, transportation, lead & lift ,tax,erection at site complete for finished item of work.	each	4.00	4.00	0.00	8.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
1266	26 Passenger (1632 Kg) Gearless with Machine Room having speed of 1 MPS - (G+5) - Bed Lift	each	0.00	0.00	4.00	4.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supplying, installation, testing & commissioning of 26 Passenger lift (G+6) (1632 Kg) Gearless with Machine Room having speed of 1 MPS in the existing lift shaft at the site. The Size of Lift Well (2500 X 3050 mm) Lift Car Inside Size (1400x2550mm),Pit depth 1600mm with Stainless steel -Hairline finish for Lift & Car ceiling and floor.The type of the car entrance and Landing entrance production is power operated two panel centre opening sliding door with stainless steel (hairline finish).The type of Landing door frame is Stainless Steel(hairline finish).The clear opening of door is 1000mm x 2000mm.The control system are Microprocessor based simplex selective collective control with /without attendant of AC 415 V 3 PHASE 50 Hz WITH VOLTAGE VARIATION OF + 5 ~ - 10 % of Power supply for traction & 220 V 1 PHASE 50 Hz OF + 5 ~ - 10 % for Cabin lighting The rate shall include Necessary Labour,fitings, annual maintainance ,etc to complete. including cost and conveyance of all material, accessories, labour charges, transportation, lead & lift ,tax,erection at site complete for finished item of work.																						
1267	26 Passenger (1632 Kg) Gearless without Machine Room having speed of 1 MPS - (G+6) - Passanger Lift	each	2.00	2.00	0.00	4.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1268	26 Passenger (1632 Kg) Gearless without Machine Room having speed of 1 MPS - (G+5) - Passanger Lift	each	0.00	0.00	4.00	4.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supplying, installation, testing & commissioning of Good lift (G+6) (2000 Kg) Gearless with Machine Room having speed of 1.5 MPS in the existing lift shaft at the site. The Size of Lift Well (2500 X 3050 mm) Lift Car Inside Size (1400x2550mm),Pit depth 1600mm with Stainless steel -Hairline finish for Lift & Car ceiling and floor.The type of the car entrance and Landing entrance production is power operated two panel centre opening sliding door with stainless steel (hairline finish).The type of Landing door frame is Stainless Steel(hairline finish).The clear opening of door is 1500mmX2000mm.The control system are Microprocessor based simplex selective collective control with /without attendant of AC 415 V 3 PHASE 50 Hz WITH VOLTAGE VARIATION OF + 5 ~ - 10 % of Power supply for traction & 220 V 1 PHASE 50 Hz OF + 5 ~ - 10 % for Cabin lighting The rate shall include Necessary Labour,fitings, annual maintainance ,etc to complete. including cost and conveyance of all material, accessories, labour charges, transportation, lead & lift ,tax,erection at site complete for finished item of work.																						
1269	Good Lift (2000 Kg) Gearless with Machine Room having speed of 1.5 MPS - (G+6)	each	2.00	2.00	0.00	4.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supplying, installation, testing & commissioning of 13 Passenger lift (G+5) (884 Kg) Gearless with Machine Room having speed of 1 MPS in the existing lift shaft at the site. The Size of Lift Well (2500 X 3050 mm) Lift Car Inside Size (1400x2550mm),Pit depth 1600mm with Stainless steel -Hairline finish for Lift & Car ceiling and floor.The type of the car entrance and Landing entrance production is power operated two panel centre opening sliding door with stainless steel (hairline finish).The type of Landing door frame is Stainless Steel(hairline finish).The clear opening of door is 1000mm x 2000mm.The control system are Microprocessor based simplex selective collective control with /without attendant of AC 415 V 3 PHASE 50 Hz WITH VOLTAGE VARIATION OF + 5 ~ - 10 % of Power supply for traction & 220 V 1 PHASE 50 Hz OF + 5 ~ - 10 % for Cabin lighting The rate shall include Necessary Labour,fitings, annual maintainance ,etc to complete. including cost and conveyance of all material, accessories, labour charges, transportation, lead & lift ,tax,erection at site complete for finished item of work.																						
1270	13 Passenger (884 Kg) Gearless with Machine Room having speed of 1 MPS - (G+5) - Passanger Lift	each	0.00	0.00	1.00	1.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Total Bill no-7 Lift works									-	-	-	-	-	-	-	-	-	-	-	-	-	-
8	Bill no-8 Allied works																						

SL. no	Description of Item	Unit	Quantity				Rate			Amount											
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total		
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)
Sub Head 55 : Medical Gas Pipeline System																					
OXYGEN SYSTEM																					
1271	Supplying, installation and commissioning of 2 x 10 size manifold extendable type complete with middle frame with chain for individual cylinder along with non Return Valves for every cylinder and copper pig tail pipes.	set	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-
1272	Supplying, installation and commissioning of 3 Sources of Fully automatic control panel for Oxygen Having a min. flow out put of over 1650 lpm at 4.2 bar pressure complying to HTM 02-01/NFPA/DIN std.	set	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-
1273	Supplying, installation and commissioning of 2+2 Cylinder Emergency Oxygen arrangement using a high flow Regulator and quick release and adopt mechanism using O2 outlet and NRV	set	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-
1274	Supplying, installation and commissioning of Surface mounted Gas Outlets- Front loading complying to HTM- 02-01 / NFPA / DIN standard with matching probe (suitable for F/M or hose pipe).	nos.	315	315	300	930.00				-	-	-	-	-	-	-	-	-	-	-	-
1275	Supplying, installation and commissioning of Oxygen flow metres (metal body) with reusable humidifier with Pr relief valve 0-15 LPM (Indigenous)	nos.	249	249	262	760.00				-	-	-	-	-	-	-	-	-	-	-	-
1276	Supplying, installation and commissioning of Oxygen Conversion Kit with Hose Assembly	nos.	7	7	6	20.00				-	-	-	-	-	-	-	-	-	-	-	-
NITROUS OXIDE SYSTEM																					
1277	Supplying, installation and commissioning of 2 x 4 size manifold extendable type complete with middle frame with chain for individual cylinder along with non Return Valves for every cylinder and copper pig tail pipes.	set	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-
1278	Supplying, installation and commissioning of Fully Automatic control panel for N2O having a min. flow out put of 250 lpm or more at 4.2 bar pressure (Indigenous)	set	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-
1279	Supplying, installation and commissioning of Single cylinder Emergency N2O arrangement using a high flow Regulator and quick release and adopt mechanism using N2O outlet and NRV	set	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-
1280	Supplying, installation and commissioning of Surface mounted Gas Outlets- Front loading complying to HTM- 02-01 / NFPA 99/ DIN standard with matching in Probe	nos.	17	17	8	42.00				-	-	-	-	-	-	-	-	-	-	-	-
1281	Supplying, installation and commissioning of H.P. tubing having anti static core as per ISO	metre.	35	35	20	90.00				-	-	-	-	-	-	-	-	-	-	-	-
1282	Supplying, installation and commissioning of N2O Conversion Kit with Hose Assembly	nos.	7	7	5	19.00				-	-	-	-	-	-	-	-	-	-	-	-
CARBON DI OXIDE SYSTEM																					
1283	Supplying, installation and commissioning of 2 x 4 size manifold extendable type complete with middle frame with chain for individual cylinder along with non Return Valves for every cylinder and copper pig tail pipes.	set	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-
1284	Supplying, installation and commissioning of Fully Automatic control panel for CO2 having a min. flow out put of 250 lpm or more at 4.2 bar pressure (Indigenous)	set	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-
1284	Supplying, installation and commissioning of Single cylinder Emergency CO2 arrangement using a high flow Regulator and quick release and adopt mechanism using CO2 outlet and NRV	set	1	1	2	4.00				-	-	-	-	-	-	-	-	-	-	-	-
1285	Supplying, installation and commissioning of Surface mounted Gas Outlets- Front loading complying to HTM- 02-01 / NFPA 99/ DIN standard with matching probe.	nos.	12	12	2	26.00				-	-	-	-	-	-	-	-	-	-	-	-
1286	Supplying, installation and commissioning of CO2 Conversion Kit with Hose Assembly	nos.	4	4	2	10.00				-	-	-	-	-	-	-	-	-	-	-	-
VACUUM SYSTEM																					

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
1287	Supplying, Installaing and commissioning of Duplex Rotary vane vacuum pump each having over 300m3/h capacity with suitable sized Bacterial Filter, interconnecting pipes, NRV, Exhaust, Silencer and Two Receiver of 2*2000 liters capacity.	set	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1288	Supplying, Installaing and commissioning of Surface mounted Gas Outlet Complying to HTM- 2022/ NFPA 99/ DIN standard with matching probe for vacuum.	nos.	292	292	295	879.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1289	Supplying, Installaing and commissioning of Ward Vacuum Unit with Regulator, Collection Jar of 600 ml with Bracket (Indigenous).	nos.	247	247	262	756.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1290	Supplying, Installaing and commissioning of Theatre Suction Unit, trolley mounted with 2 no 2000 ml Collection Jars (Indigenous)	nos.	13	13	5	31.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1291	Supplying, Installaing and commissioning of High Pressure color coded yellow Tube	metre	500	500	400	1400.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1292	Supplying, Installaing and commissioning of Low Pressure Tube (Transparent)	metre	500	500	400	1400.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
COMPRESSED MEDICAL AIR SYSTEM																							
1293	Supplying, Installaing and commissioning of Duplex 113CFM each Capacity Screw / Scroll type Air Compressor with 8bar pressure with 02nos 1000Ltrs Vertical Mounted Air Receiver complete with auto / manual drain valves , pressure gauge, safety valve, Air Receiver suitably with facility for statutory inspection, by pass arrangement. The vessels should have Manufacturer's Test Certificate with 01nos of Duplex 120cfm Dessiccant Medical Air Dryer should deliver Medical Air with water content not exceeding 67vpm (volume parts per million—equivalent to a dew point -46°C at atmospheric pressure). So, it should incorporate suitable Dessiccant Dryers of requisite capacity with Dew Point Hygrometre and CO Monitor to display with a minimum accuracy of +_3°C in a range from -20°C to -60°C atmospheric dew point with a set point of -46°C along with 4 stage filters particle content removal up to 0.5mg/cum & 0.01mg/cum, 0.003mg/cum	set	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1294	Supplying, Installaing and commissioning of Surface mounted Gas Outlet Complying to HTM- 02-01/ NFPA 99 standard with probe for MA 4.	nos.	116	116	64	296.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1295	Supplying, Installaing and commissioning of Surface mounted Gas Outlet Complying to HTM- 02-01/ NFPA 99 standard with probe for SA 7.	nos.	16	16	8	40.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1296	Supplying, Installaing and commissioning of HP colour coded black Tubing	metre	580	580	350	1510.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1295	Supplying, installation and commissioning of Compressed Air Conversion Kit with Hose Assembly	nos.	7	7	5	19.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
AGSS (SCAVANGING) SYSTEM																							
1296	AGSS Outlet Venturi type	set	4	4	4	12.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
COPPER PIPELINES																							
Supplying, Installaing and commissioning of Medical Grade Copper Pipes conforming to BS: EN13348:2014 duly certified by third party Lloyds Register with Test Certificates.																							
1297	76*1.2mm OD Lloyds Certified Copper pipes BS: EN13348:2014	metre	0	0	130	130.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1298	54*1.2mm OD Lloyds Certified Copper pipes BS: EN13348:2014	metre	0	0	150	150.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1299	54*1.2mm OD Lloyds Certified Copper pipes BS: EN13348:2014	metre	100	100	400	600.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1298	42*1.2mm OD Lloyds Certified Copper pipes BS: EN13348:2014	metre	150	150	650	950.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1299	35*0.9mm OD Lloyds Certified Copper pipes BS: EN13348:2014	metre	175	175	1000	1350.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1300	28*0.9mm OD Lloyds Certified Copper pipes BS: EN13348:2014	metre	850	850	2800	4500.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1301	22*0.9mm OD Lloyds Certified Copper pipes BS: EN13348:2014	metre	2500	2500	3000	8000.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1302	15*0.9mm OD Lloyds Certified Copper pipes BS: EN13348:2014	metre	3800	3800	1050	8650.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1303	12*1.0mm OD Lloyds Certified Copper pipes BS: EN13348:2014	metre	1700	1700	0	3400.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
MISCELLANEOUS ITEMS																							
										-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
1304	Supplying, Installing and commissioning of Master Electrical Control Panel - Supplying, Installing and commissioning of A dedicated electrical control panel for Air Compressors and Vacuum pumps & Air Dryers, Auto Drain Valves, starter, MCB, amm, hours run rm, hand/auto switch, sensors contacts. Under normal conditions the capacity of the plant should be 100% system design flow with one compressor / pump running another one set compressor/pump stand by basis. Integrated with BMS Compatibility and Cabable of communicating Master Alarm. Along with automic sequencing and cascading facility	nos.	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Bed Head Panel Units are designed and manufactured as per EN 13485 Medical Devices – QMS. The panels are designed and built with a view to provide a stylish finish and pleasing aesthetics in order to blend into the room decoration. All bed head panel are manufactured using individually heat treated extruded aluminium sections. The bed head panel provides separate compartment for medical gases and electrical services. Aluminium extruded Separate provision for gas and electricals Easy assembly with push/slide/screw type assembly with no visible screws. Outlet points – Double Locking Indigenous type as per customer requirement. Cut Out Provision for Electricals – 6/16A as per customer requirement Cut Out Provision of LED Light with On Off control can be made as per customer requirement Cut Out Provision of Nurse call system can be made as per customer requirement Supplied pre-piped and fully tested. Complies with HTM 02-01 and NFPA 99. Electrostatic Powder Paint finish on all exterior.Colour code as per customer requirement																						
1305	The Hospital Bed Head Panel - 900mm	nos.	0	0	150	150.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1306	The Hospital Bed Head Panel - 1200mm	nos.	150	150	67	367.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1307	The Hospital Bed Head Panel - 1500mm	nos.	67	67	25	159.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1308	The Hospital Bed Head Panel - 1800mm	nos.	25	25	10	60.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1309	Anaesthetic Rigid Pendant	nos.	7	7	7	21.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1310	Surgeon Pendant - Single Arm	nos.	0	0	0	0.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1311	Surgeon Pendant - Doubel Arm	nos.	4	4	4	12.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Digital Area Alarms - Supplying and commissioning of Meeical Gas Area Alarms, Microprocessor based, LCD Touch Screen,Wifi enabled, monitoring of real time Gas, Vacuum Pressure, audi-visual alarms for each gas, settable alarms limits, display the name of the area installed (like Ward/ICU/OT Etc..) must be cabale of communicating with master alarm, BMS Compatible, Optionally Temprature, Humidity Monitoring enabled, System complaining with HTM 02-02 & NFPS 99																						
1312	2 Gases Alarm	nos.	9	9	11	29.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1313	3 Gases Alarm	nos.	10	10	9	29.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1314	4 Gases Alarm	nos.	2	2	2	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1315	5 Gases Alarm (Rate Only)	nos.	0	0	0	0.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1316	6 Gases Alarm	nos.	4	4	4	12.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount																
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total							
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)					
1317	Master Alarm with BMS Compatibility The master alarms shall be capable to monitor minimum 40 Point. each point represents an alarm condition that the source equipment might have. When an alarm condition exists, a red light flashes and the audible alarm sounds. If several alarm conditions occur simultaneously, the most recent alarm light shall flash, while the other alarm lights shall remain lit. When an alarm condition is created, an audible alarm+ shall be actuated. The master alarm must be able to monitor the following source alarm conditions. Oxygen Source Empty/Fault Oxygen Cylinder Bank Empty/Fault (could be compatible supplied manufacturer of oxygen control panel)Oxygen Emergency Bank Empty/Fault - (could be compatible supplied manufacturer of oxygen control panel) Air Compressor Faulty/Operation - (could be compatible supplied manufacturer of electrical control panel) Vacuum Pump Faulty/Operational - (could be compatible supplied manufacturer of electrical control panel) Vacuum Deficiency Vacuum Reservoir And Other MGPS Signals & Alarms Master alarm shall be integrated with BMS/HIS	nos.	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
	Supplying, Installing and commissioning of Area Valve Service Unit (AVSU) - The Area Valve Service Unit (AVSU) shall conform to BS EN 739:1998, HTM 02-01 and BS EN ISO 7396-1:2007. The AVSU shall provide a zone isolation facility, for use either in an emergency or for maintenance purposes. The valves shall be operated by a quarter turn handle with over-travel prevention in both directions. A door shall lock in the closed position and AVSU's installed adjacent to each other shall be operated by different key/lock combinations. A blank zone identification label shall be provided with each AVSU fix assembly.									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1318	2 Gases AVSU	nos.	15	15	11	41.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1319	3 Gases AVSU	nos.	12	12	9	33.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1320	4 gases AVSU	nos.	4	4	4	12.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1321	5 Gases AVSU	nos.	1	1	0	2.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1322	6 Gases AVSU	nos.	4	4	4	12.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Isolation Valves									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1323	For 76 mm	nos.	0	0	5	5.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1324	For 54 mm	nos.	6	6	5	17.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1325	For 42 mm	nos.	6	6	7	19.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1326	For 28 mm	nos.	14	14	14	42.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1327	For 22 mm	nos.	26	26	26	78.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1328	For 15 mm	nos.	43	43	43	129.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1329	For 12 mm	nos.	734	734	734	2202.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Accessories									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1330	Single Gas Wall Outlet Box	nos.	3	3	10	16.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1331	2 Gas Wall Outlet Box	nos.	156	156	120	432.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1332	3 Gas Wall Outlet Box	nos.	47	47	50	144.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1333	4 Gas Wall Outlet Box	nos.	22	22	20	64.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1334	5 Gas Wall Outlet Box	nos.	24	24	25	73.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1335	6 Gas Wall Outlet Box	nos.	2	2	2	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	CAMC (Comprehensive Annual Maintenance Contract) Comprehensive Maintenance of the complete Medical Gas Pipeline System installation for 2 years after completion of Defect Liability Perios / Warranty Period of Five Years as per terms and conditions of comprehensive maintenance described in the NITs per following. The Comprehensive Maintenance of MGPS Installations includes complete MGPS Installations, Labour, Spares, all consumables etc. as required including the following. a.All MGPS Equipments in the NIT. b.Preventive Maintenance Including Testing & Calibration as per Technical / Service / Operational Manual of the Manufacturer. c.MGPS Installation inside the MGPS Plant Room										-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1336	1st Year	nos.	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
1337	2nd Year	nos.	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Sub Head 56 : Nurse Call System																						
	Controller									-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Supply and Installation of VDE 0834 compliant/Zone Controller									-	-	-	-	-	-	-	-	-	-	-	-	-	-
1338	The controller (with SMPS power supply) forms a decentralised communications node for exchanging data between the connected system devices and the rest of the communications system, consisting of : 1 x RJ45 socket, 100Mb IP Port, galvanically isolated conforming to EN 60950 and VDE 0834; which is connected to the hospital V lan POE port- 3 x RJ45 sockets, for connecting all system modules connecting communications,bedside,overdoor light and pull cord and for connection of the external data bus. The above entire unit shall be manufactured as per specifications ,Line Sketches & as per the approval of the Engineer-In-Charge.The rate including all material, labour, taxes, transportation etc to complete.	nos.	9	9	11	29.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Nurse station display									-	-	-	-	-	-	-	-	-	-	-	-	-	-
1339	Nurse Station shall comprises of minimum 10" large touch screen LC colour graphic display for displaying all details, a smash proof glass panel (to protect the sensitive display from unnecessary contact during cleaning and other processes). The ward terminal shall display date and time, indication of all presence, all set reminders, indication of all calls in accordance with VDE0834. All call indications follow the priority and must display the exact location of the calls. The above entire unit shall be manufactured as per specifications ,Line Sketches & as per the approval of the Engineer-In-Charge.The rate including all material, labour, taxes, transportation etc to complete.	nos.	14	14	15	43.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Nurse station display									-	-	-	-	-	-	-	-	-	-	-	-	-	-
1340	All errors and notifications are displayed on the information panel. Emergency codes, WC calls, nurse calls, and nurse presences can be monitored. All activities on the system are logged. All logs can be reported in detail.Panel to room communication, Panel to a group of rooms communication, General call from rooms or nurse stations, Full duplex, SIP protocol, PoE (Power Over Ethernet) The above entire unit shall be manufactured as per specifications ,Line Sketches & as per the approval of the Engineer-In-Charge.The rate including all material, labour, taxes, transportation etc to complete.	nos.	2	2	2	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	ROOM CONTROL UNIT									-	-	-	-	-	-	-	-	-	-	-	-	-	-
1341	Supply of Room Terminal with display & integrated functional components and operating membrane keypad with symbols; consisting of: It features a 5" touchscreen and built-in RFID card reader, which nurses use to verify their identity when responding to calls. All cards read by the unit are checked for authorization.The Room Control Unit can be used to initiate and terminate emergency code calls (Code Blue/Cardiac Arrest etc.), assist calls, consultation calls, and voice calls to the Nurse Control Panel. The above entire unit shall be manufactured as per specifications ,Line Sketches & as per the approval of the Engineer-In-Charge.The rate including all material, labour, taxes, transportation etc to complete.	nos.	25	25	24	74.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Bed side Unit and patient handset									-	-	-	-	-	-	-	-	-	-	-	-	-	-
1342	consisting of a plastic case in antimicrobial finish having - Call button with nurse symbol with integrated finder and reassurance light on the top end of the unit, - Membrane keypad in antimicrobial finish with integrated LEDES for operation, consisting of: - 1 call key, - 2 lighting keys - 2.80 metre connection cable with auto-disconnecting RJ45 connector plug It shall be supplied with cradle for holding patient terminals. The above entire unit shall be manufactured as per specifications ,Line Sketches & as per the approval of the Engineer-In-Charge.The rate including all material, labour, taxes, transportation etc to complete.	nos.	216	216	229	661.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
1347	The server provides log reporting through a web interface and enables integration with other systems used throughout the building. Our servers have a Linux-based robust and reliable infrastructure.Linux Operating System ,Fully redundant structure, Troubleshooting and error notification of all modules connected to the system. The above entire unit shall be manufactured as per specifications ,Line Sketches & as per the approval of the Engineer-In-Charge.The rate including all material, labour, taxes, transportation etc to complete.	nos.	1	1	1	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
Mifare card																							
1348	smart cards to verify the permissions of hospital personel who wish to initiate or terminate various calls. This allows custom permissions to be set for different type of card user, nurse , code blue team , Doctors etc The above entire unit shall be manufactured as per specifications ,Line Sketches & as per the approval of the Engineer-In-Charge.The rate including all material, labour, taxes, transportation etc to complete.	nos.	20	20	20	60.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
Supply of Backbone Switch																							
1349	Floor Switch: Uplink connections: 2 x 1Gb uplink ports, RJ45 (GBIC capable, possibility for LWL) Connections downlink: 24 x 100Mb downlink ports, RJ45 Switch must have all the Layer 2 and Layer 3 function which is mentioned in the tender Document. The above entire unit shall be manufactured as per specifications ,Line Sketches & as per the approval of the Engineer-In-Charge.The rate including all material, labour, taxes, transportation etc to complete.	nos.	16	16	16	48.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1350	Supply and fixing in position the following heavy duty ISI Marked PVC conduit in concealed or surface mounted 16 gauge ISI marked GI conduit including all accessories i.e. bends, junction boxes, outlet boxes with cover plates. The above entire unit shall be manufactured as per specifications ,Line Sketches & as per the approval of the Engineer-In-Charge.The rate including all material, labour, taxes, transportation etc to complete.	metre	10000	10000	10000	30000.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1351	25 mm dia heavy duty PVC conduit concealed. (in RM)	metre	12000	12000	12000	36000.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
Sub Head 57 : Hospital Cubical Curtain Track System,Wall Guard & Column Guard System																							
1352	Supply and installation of Optitrac® Cubicle Curtain Track System” heavy Duty Aluminium cubicle track made of Aluminum alloy (6063-T5) having minimum size 35mm wide x 19mm high x 1.52mm thick, made of aluminium Extruded with white powder coating having properties like Tensile Strength 195 MPa, Shear Strength 150 MPa, Corrosion resistance properties with 50-60 micron Standard white powder coating with seven stage processes, Tracks to have drill guide on the top. Runners shall be of Wheel Type Roller and made from Nylon, Deralin with SS 304 Hook. Roof suspender, wall support, bridge clamp all shall me made from Aluminum Powder coated. Shall Provide factory bent track sections with one-foot radius. End Cap: Provide thermoplastic end caps in a colour matching the track. End cap shall have a removable inner cap that allows carriers to be removed. Provide track aluminium splice to fit track section, with finish matching that of the track. Provide support sets, designed to receive attachment from track support. Provide brackets to mount to angle ceilings and receive attachment from track support. Unit includes durable hinge, latch and standard length. Acetal ipe ball and chain carriers with nonbinding nylon rollers accurately fit to track. Carriers to be fitted to curtain to prevent accidental curtain removal.	metre	670.00	670.00	670.00	2010.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
CUBICLE / PRIVACY CURTAIN :																							

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
1353	Supply and installation of 100% polyester cubical curtains. Fabric is to be opaque, water repellent, wrinkle free, shrink proof, Anti-odor, Anti-microbial, Anti-fungal with high strength 18" oval net nylon mesh on top and Fabric 7'6" (H) x 4' (W). Curtain Fabric shall be of 230GSM.	sqm	1330.00	1330.00	765.00	3425.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	WALL GUARD :																						
1354	Providing and fixing superior impact resistance Wall Guard (MAKE IN INDIA) having Vinyl: Snap on cover of .080" (2mm) thickness shall be extruded from chemical and stain resistant polyvinyl chloride with the addition of impact modifiers. no plasticizers shall be added (plasticizers may aid in bacterial growth). Surface shall have a pebble texture for scratch resistant and Continuous aluminum retainer of .080" (2mm) thickness shall be fabricated from 6063-T5 aluminum, with a mill finish. Dimensions to be of 6" (152mm) height x 1" (25mm) depth. Inner snap-on vinyl impact black bumper of .080" (2mm) thickness x 3.930" (100mm) width x 21mm height which shall be extruded from chemical and stain resistant unplasticized polyvinyl chloride (uPVC). The system shall resist an impact of 45.5 ft-lbs/inch while producing no visual blemishes upon the vinyl cover surface and no deformations in the aluminum retainers, as tested in accordance with applicable provisions of ASTM F 476-84, paragraph 18, Impact Test and shall not support fungal or bacterial growth in accordance with ASTM G-21 and G-22. The ipc system shall also conform to class A fire rating and ASTM D-543 for chemical and stain resistance. It shall include injection molded End Caps with black reveal strip.	metre	1656.00	1626.00	1385.00	4667.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	CORNER GUARD :																						
1355	Providing and fixing series high impact surface mount IPS Corner Guard (MAKE IN INDIA) having Vinyl: Snap on cover of .080" (2mm) thickness shall be extruded from chemical and stain resistant polyvinyl chloride with the addition of impact modifiers no plasticizers shall be added (plasticizers may aid in bacterial growth). Surface shall have a pebble texture for scratch resistant. Continuous aluminum retainer of .070" (1.8mm) thickness shall be fabricated from 6063-T5 aluminum, with a mill finish. Dimensions to be of 2" (51mm) x 2" (51mm), 90 degree. The rigid vinyl profile shall resist an impact of 30.2 ft-lbs/inch as per ASTM D-256-90b and shall not support fungal or bacterial growth in accordance with ASTM G-21 and G-22. The ipc system shall also conform to class A fire rating and ASTM D-543 for chemical and stain resistance. It includes Top caps and bottom caps which shall be made of injection molded thermoplastics.	metre	470.00	470.00	625.00	1565.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1356	Providing and fixing IPC Handrail (MAKE IN INDIA) having rigid vinyl snap-on cover(lead free) of 080" (2mm) thick, Surface shall have a pebble texture for scratch and stain resistant rigid vinyl cover mounted on a sturdy continuous aluminium retainer of .080" (2mm) thickness that shall be fabricated from 6063-T5 aluminium with a mill finish. 4-5/16" (110mm) height x 1-5/8" (41mm) gripping diam, extends 3-1/8" (79mm) from wall which has an oval gripping surface. The system shall resist an Impact Strength of 30.2 ft-lbs/inch of thickness as tested in accordance with the procedures specified in ASTM D-256-90b, Impact Resistance of Plastics. The rigid vinyl shall not support fungal or bacterial growth in accordance with ASTM G-21 and G-22. The system shall also conform to class A fire rating and ASTM D-543 for chemical and stain resistance. It includes Molded end returns with black reveal strip and mounting brackets.	metre	1656.00	1626.00	1385.00	4667.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Sub Head 58 : Kitchen Equipments																						
1357	WORK TABLE FOR SUPPORT OF TWO BURNER RANGE	nos	1.00	1.00	1.00	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Size 1350x600x850mm																						
	Top & undershelf of s.s.sheet on m.s.angle frame work & s.s.tubular legs, with adjustable feet. Top to have sound deadening material lining as required.																						
1358	EXHAUST HOOD (Without Ducting, Fixing & Extraction fan) FOR TWO BURNER RANGE	nos	1.00	1.00	1.00	3.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
	Size 1950x750x600mm																						

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
1367	Supply of pvc 60 Lit capacity Waste bins Rectangular types.The Size of the bin is height -850mm and Top Dia - 350X350mm and Bottn dia - 250X250mm and handle with cover including tax or its equivalent of ISI make with Green,Blue,Red,Black,Yellow, colours as directed by the Engineer - in -charge.	nos	85.00	85.00	212.00	382.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1368	Supply of pvc 90 Lit capacity Waste bins Rectangular types.The Size of the bin is height -850mm and Top Dia - 510X510mm and Bottn dia - 380X400mm and handle with cover including tax or its equivalent of ISI make with Green,Blue,Red,Black,Yellow, colours as directed by the Engineer - in -charge.	nos	135.00	135.00	160.00	430.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1369	Sanitary Napkin Waste Bin.	nos	250.00	250.00	320.00	820.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1370	Supply of pvc 240 Lit capacity Two Wheeled Waste bin .The Size of the bin is height -1065 mm and Top Length 740mm and Top width 580mm and handle with cover including tax or its equivalent of ISI make with Green,Blue,Red,Black,Yellow, colours as directed by the Engineer - in -charge.	nos	14.00	14.00	12.00	40.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1371	Collection of Soil Waste Wheel Capacity 100lit	nos	4.00	4.00	4.00	12.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1372	Supply of pvc 120 Lit capacity Waste bin with Permanent structure .The Size of the bin is height -915 mm and width 410mm and handle with cover including tax or its equivalent of ISI make with Green,Blue colours as directed by the Engineer - in -charge.	nos	214.00	214.00	208.00	636.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1373	Supply of pvc 660 Lit capacity Waste bin with Permanent structure .The Size of the bin is height -915 mm and width 410mm and handle with cover including tax or its equivalent of ISI make with Green,Blue colours as directed by the Engineer - in -charge.	nos	2.00	2.00	2.00	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
Sub Head 60 : Hospital & Annex Block Furniture																							
1374	Supplying and fixing of Matrix Lounge Chair as per the following specifications. DIVANO LITE/TANDEM PUBLIC 3 SEATER/TANDEM SEATING/1735L X 720W X 800H, Seat Perfo - 1.2 mm thk, Seat Bracket - 1.2 mm, Back Perfo - 1.2 mm, Back Bracket 1.2 mm, Seat Clamp & Back Clamp- 4.0 mm, Solid Center beam- 2.0 mm Handle- 1.2 mm, Handle Bracket- 2.0 mm, Leg- 1.2 mm, Leg Plate- 4.0 mm, Leg Bush-2.0 mm, Leveller Cup - 0.6 mm The above entire unit shall be manufactured as per specifications .Line Sketches & as per the approval of the Engineer-In-Charge.The rate including all material, labour, taxes, transportation etc to complete.	nos	8.00	8.00	8.00	24.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1375	Supplying and fixing of Matrix Lounge Chair as per the following specifications. DIVANO LITE/TANDEM PUBLIC 4 SEATER/TANDEM SEATING/2290L X 720W X 800H, Seat Perfo - 1.2 mm thk, Seat Bracket - 1.2 mm, Back Perfo - 1.2 mm, Back Bracket 1.2 mm, Seat Clamp & Back Clamp- 4.0 mm, Solid Center beam- 2.0 mm, Handle- 1.2 mm, Handle Bracket- 2.0 mm, Leg- 1.2 mm, Leg Plate 4.0 mm, Leg Bush-2.0 mm, Leveller Cup - 0.6 mm. The above entire unit shall be manufactured as per specifications .Line Sketches & as per the approval of the Engineer-In-Charge.The rate including all material, labour, taxes, transportation etc to complete.	nos	277.00	277.00	209.00	763.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount													
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total				
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)		
1376	Supplying and fixing of Chair as per the following specifications. Nexa Chair with foam seating, pushback mechanism, fixed armrest and 50mm twin-wheel Nylon castors mounted on 600 dia Nylon base. Chair back is ergonomically designed, made of Hot pressed Plywood and PU foam of density 50-55 kg/m³ and upholstered with 100% Polyester Fabric. The above entire unit shall be manufactured as per specifications, Line Sketches & as per the approval of the Engineer-In-Charge. The rate including all material, labour, taxes, transportation etc to complete.	nos	255	255.00	262.00	772.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1377	Supplying and fixing of Table as per the following specifications. Main Table 1200Lx6000Dx750H, Pedestal - 400W x 450D x 675H, TABLETOP & GABLE END to be made of 25 mm thick Prelaminated particle board with machine pressed PVC edge band on all sides. MODESTY PANEL @725H to be made of 18 mm thick Prelaminated particle board with machine pressed PVC edge band on all sides. Pedestal - TOP: 18mm Thick Prelaminated Partical Board with 2MM PVC edge band on all edges. CARCASS (Body/ Shutter / Back) : 18MM thick Prelaminated Partical Board with PVC edge band on all exposed edges. HARDWARE : Hettich Hinges, Lock. The above entire unit shall be manufactured as per specifications, Line Sketches & as per the approval of the Engineer-In-Charge. The rate including all material, labour, taxes, transportation etc to complete.	nos	202	202.00	220.00	624.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1378	Supplying and fixing of Matrix Lounge Chair as per the following specifications. The seat shall be made of Mild Steel. The back shall be made of SS tubular frame. Size shall be in 78.5 cm. (B) x 210.0 cm. (L) x 63.8 cm (H) & SEAT HEIGHT size shall be in 42.0 cm (SH). The above entire unit shall be manufactured as per specifications, Line Sketches & as per the approval of the Engineer-In-Charge. The rate including all material, labour, taxes, transportation etc to complete.	nos	13	13.00	40.00	66.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1379	Supplying and fixing of Table as per the following specifications. Main Table 1200Lx750Dx750H, Side Combo Storage 1050Lx450Dx750H, TABLETOP & GABLE END to be made of 25 mm thick Prelaminated particle board with machine pressed PVC edge band on all sides. MODESTY PANEL @725H to be made of 18 mm thick Prelaminated particle board with machine pressed PVC edge band on all sides. STORAGE - TOP: 25mm Thick Prelaminated Partical Board with 2MM PVC edge band on all edges. CARCASS (Body/ Shutter / Back) : 18MM thick Prelaminated Partical Board with PVC edge band on all exposed edges. SHELF : made of 18MM thick Prelaminated Partical Board with PVC edge band on al edges SHUTTERS : Lockable Swing shutters with Flush Handle / Finger Groove handle. HARDWARE : Hettich Hinges, Lock The above entire unit shall be manufactured as per specifications, Line Sketches & as per the approval of the Engineer-In-Charge. The rate including all material, labour, taxes, transportation etc to complete.	nos	41	41.00	36.00	118.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-
1380	Supplying and fixing of Chairs as per the following specifications. MID BACK SIZE shall be in 60.0 cm. (L) x 60.0 cm (B) x 100.0 cm. (H) & SEAT HEIGHT shall be in 50.0 cm (SH) {Adjustable}. The seat and back shall be made up of 1.2 cm. thick hot-pressed plywood, upholstered with fabric and moulded Polyurethane foam, together with moulded seat and back covers. The back foam is designed with contoured lumbar support for extra comfort. The Polyurethane foam is moulded with density of 45 +/- 2 kg/m and Hardness of 20 +/- 2 on Hampden machine at 25% compression. The armrest top should be made of moulded polyurethane (Polyurethane) and mounted on to a drop lift height adjustable type Mild Steel tubular armrest support chrome plated. The armrest height should be adjustable up to 6.5cm in 5 steps & also should have swivel adjustment on both sides. The Knee tilt synchro mechanism should be designed with the following features - 360° revolving type, Tilt tension adjustment, 4-position locking with anti-shock feature, Seat back tilting ratio of 1 : 2 (11 ° Seat Tilt / 22° back tilt). The backrest consists of a sliding up down mechanism, which should be adjusted in the range of 7.5 cm and should be locked in 4 positions for correct position of lumbar support. The pneumatic height adjustment has an adjustment stroke of 9.0 cm. The twin wheel castors shall be injection moulded in black Nylon.	nos	104	104.00	108.00	316.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
1385	Supplying and fixing of Centre Table as per the following specifications. 600Lx600Dx420HT, Top: Table Top with rectilinear form with rounded boundaries and chamfered edges give it crisp and formal visual appearance. 12mm thick black tinted or toughned Glass top is scratch resistant.Understructure: 12mm MS rod or SS (202 GRADE) rod. Understructure provides structural stability with a lighter look to the entire product. The above entire unit shall be manufactured as per specifications ,Line Sketches & as per the approval of the Engineer-In-Charge.The rate including all material, labour, taxes, transportation etc to complete.	nos	8	8.00	0.00	16.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1386	Supplying and fixing of Table as per the following specifications. TABLETOP & GABLE END made of 25 mm thick Prelaminated particle board with machine pressed PVC edge band on all sides. MODESTY PANEL @725H made of 18 mm thick Prelaminated particle board with machine pressed PVC edge band on all sides.PRELAM 3 DRAWER (2B+1F) PEDESTAL UNIT 400Wx450Dx670H (With Castor) - madeup of 18mm thick Prelaminated Particle Board with PVC Edge band and the telescopic slides for mobility of drawers and filers. The drawer is made up of 0.7 mm thick CRCA steel. with Centre Locking Mechanism considered. Side Finger Groove Handle is considered. STORAGE - TOP: 25mm Thick Prelaminated Partical Board with 2MM PVC edge band on all edges. CARCASS (Body/ Shutter / Back) : 18MM thick Prelaminated Partical Board with PVC edge band on all exposed edges. SHELF : made of 18MM thick Prelaminated Partical Board with PVC edge band on al edges SHUTTERS : Lockable Swing shutters with Finger Groove handle. HARDWARE : Hettich Hinges, Lock The above entire unit shall be manufactured as per specifications, Line Sketches & as per the approval of the Engineer-In-Charge. The rate including all material, labour, taxes, transportation etc to complete.	nos	2	2.00	2.00	6.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1387	Supplying and fixing of Chairs as per the following specifications. MID BACK SIZE shall be in 60.0 cm. (L) x 60.0 cm (B) x 100.0 cm. (H) & SEAT HEIGHT shall be in 50.0 cm (SH) {Adjustable}. The seat and back shall be made up of 1.2 cm. thick hot-pressed plywood, upholstered with fabric and moulded Polyurethane foam, together with moulded seat and back covers. The back foam is designed with contoured lumbar support for extra comfort. The Polyurethane foam is moulded with density of 45 +/- 2 kg/m and Hardness of 20 +/- 2 on Hampden machine at 25% compression. The armrest top should be made of moulded polyurethane (Polyurethane) and mounted on to a drop lift height adjustable type Mild Steel tubular armrest support chrome plated. The armrest height should be adjustable up to 6.5cm in 5 steps & also should have swivel adjustment on both sides. The Knee tilt synchro mechanism should be designed with the following features - 360° revolving type, Tilt tension adjustment, 4-position locking with anti-shock feature, Seat back tilting ratio of 1 :2 (11 ° Seat Tilt /22° back tilt).The backrest consists of a sliding up down mechanism, which should be adjusted in the range of 7.5 cm and should be locked in 4 positions for correct position of lumbar support.	nos	23	23.00	4.00	50.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	The pneumatic height adjustment has an adjustment stroke of 9.0 cm.The twin wheel castors shall be injection moulded in black Nylon. The above entire unit shall be manufactured as per specifications, Line Sketches & as per the approval of the Engineer-In-Charge. The rate including all material, labour, taxes, transportation etc to complete.									-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1388	Supply and Fixing of Chair For Visitors Dimensions: 60.90 Lx 64.20 D x 98.20 H x 44.80 seat Ht. in CM Frame Tubular Stain less Steel High Density Polyurethane Foam combined with Premium Leatherette. Sturdy PU Soft Arms. Seat and back rest with comfort cushion Legs with Nylon heavy duty bushes Certificates: ISO 9001, BIS/ CE The above entire unit shall be manufactured as per specifications, Line Sketches & as per the approval of the Engineer-In-Charge. The rate including all material, labour, taxes, transportation etc to complete.	nos	34	34.00	16.00	84.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
1389	Supplying and fixing of Meeting Table 15seater as per the following specifications. TABLETOP & GABLE END made of 25 mm thick Prelaminated particle board with machine pressed PVC edge band on all sides. MODESTY made of 18mm thick Prelaminated particle board with machine pressed PVC edge band on all sides. WIRE MANAGEMENT The Vertical (snake) & Horizontal(Switch mounting box) wire carriers are placed below worktop, made up of CRCA with Powder Coating & Fixed to the understructure with specially designed brackets. Provision of placing switch plates in the cable tray which is easily accessible through a Access Flap (450L) . The above entire unit shall be manufactured as per specifications, Line Sketches & as per the approval of the Engineer-In-Charge. The rate including all material, labour, taxes, transportation etc to complete.	nos	6	6.00	1.00	13.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1390	Supply and Fixing of Chair For Visitors Dimensions: 60.90 Lx 64.20 D x 98.20 H x 44.80 seat Ht. in CM Frame Tubular Stain less Steel High Density Polyurethane Foam combined with Premium Leatherette. Sturdy PU Soft Arms. Seat and back rest with comfort cushion Legs with Nylon heavy duty bushes Certificates: ISO 9001, BIS/ CE The above entire unit shall be manufactured as per specifications, Line Sketches & as per the approval of the Engineer-In-Charge. The rate including all material, labour, taxes, transportation etc to complete.	nos	24	22.00	17.00	63.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
BILL OF QUANTITY (MEDICINE STORE)																								
1391	Supply and Fixing of L Angular Rack Size: 2130 (H) X 1080 (W) X 380 (D) mm Rack with 5 Compartments of 6 nos. of shelves. Distance between each shelf will be 410 mm. These 6 shelves should be hanging arrangement (adjustable). Racks shall be manufactured from Slotted M.S angle 14 SWG. Shelves shall be manufactured from 18 SWG thick sheet. The rack shall be assembled with G 1 bolt, nuts and washers. Slotted angle and M.S sheet shall be made of cold rolled with anti-rust treated and shall be finished with powder coating (color: Prince Gray). H/D Rubber bushes shall be provided to the bottom of legs of slotted angle racks. The quality of M.S sheet which is used for racks shall be free from any defects, Undulations, and old paints and surface corrosion, etc. Certificates: ISO 9001, BIS/CE The above entire unit shall be manufactured as per specifications, Line Sketches & as per the approval of the Engineer-In-Charge. The rate including all material, labour, taxes, transportation etc to complete.	nos	84	78.00	100.00	262.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1392	Supply and Fixing of ALMIRAH SS 1 Internal Size of Almirah: 1850 (H) X 900 (W) X 450 (D) mm 2 Leg Size of Almirah: 150 (H) X 120 (W) X 450 (D) mm 3 Rack with 5 Compartments. 4 Distance between each shelf will be 360 mm. 5 These 4 shelves should be hanging arrangement (adjustable). 6 One shelf should have internal door and lock 7 Standard lock and 2 sets of keys. 8 The thickness of the Almirah sheet shall be 18 SWG. 9 The body of the Almirah shall be manufactured from cold rolled MS sheet (C. R. Sheet) with Antirust treatment and shall be finished with powder coating The quality of used M.S sheet for making Almirah shall be free from any pitting and corrosion etc. 10 H/D Rubber bushes shall be provided to the bottom of legs of Almirah. Certificates : ISO 9001 and BIS/notified CE The above entire unit shall be manufactured as per specifications, Line Sketches & as per the approval of the Engineer-In-Charge. The rate including all material, labour, taxes, transportation etc to complete.	nos	23	18.00	150.00	191.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
1393	Supply and Fixing of Almirah with glass door Steel almirah with Toughened Glass Size: Height 1980mm, Width 915mm, Depth 480mm Manufactured from CRCA sheet conforming to IS 513-1994 grade D material. The CRCA sheet of uniform thickness and of 22 gauge for the body, 20 gauge for doors duly cut and bend with the help of CNC machines. The almirah shall be equipped with four fixed shelves, manufactured from 22 gauge CRCA sheet, thereby making five compartments in the Almirah. The steel shelf shall be capable of carrying a uniformly distributed load of 70kgms. Certification: Manufacturer should have ISO: 9001, BIS/ CE The above entire unit shall be manufactured as per specifications, Line Sketches & as per the approval of the Engineer-In-Charge. The rate including all material, labour, taxes, transportation etc to complete.	nos	50	50.00	25.00	125.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1394	Supply and Fixing of Table for clerk WORKTOP - Made of 25 mm thick Prelaminated particle board with machine pressed PVC edge band on all sides. UNDERSTRUCTURE- C LEG constructed of Vertical of 50X50X1.6 mm & Horizontal of 40mm X 40mm X 1.6mm thick MS Pipe with caps & levellers . Cross member is made of 40mm X 40mm X 1.6mm MS pipes. . powder coated finish of 50 to 60 Microns DFT. The above entire unit shall be manufactured as per specifications, Line Sketches & as per the approval of the Engineer-In-Charge. The rate including all material, labour, taxes, transportation etc to complete.	nos	55	55.00	0.00	110.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1395	Supply and Fixing of Table for Computer Contemporary & Modern Style Computer Desk set-up for Study & Home Office with Storage Space W x H x D: 1003.3 mm x 749.3 mm x 508 mm (3 ft 3 in x 2 ft 5 in x 1 ft 8 in) With CPU Compartment Built-in Keyboard Tray Certificates: BIS/CE, ISO 9001 The above entire unit shall be manufactured as per specifications, Line Sketches & as per the approval of the Engineer-In-Charge. The rate including all material, labour, taxes, transportation etc to complete.	nos	55	30.00	20.00	105.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1396	Supply and Fixing of Revolving Chair Material: Fire retardant breathable mesh inbuilt into the backrest and Polyester fabric integrated into the seat. (BM Mesh & 5060 fabric seat). Base: 700 mm diarm Nylon base with 50 mm castors for stability and easy movement. Arms: Fixed Polypropylene inbuilt arms. Centre tilt: Adjust your work posture by using the tilt to recline on the chair for meetings / phone calls and more. Use the tilt lock for upright posture like keyboarding. Pneumatic height: Change the height of the chair relative to the floor by 100 mm. Certificates: ISO 9001, notified CE/BIS The above entire unit shall be manufactured as per specifications, Line Sketches & as per the approval of the Engineer-In-Charge. The rate including all material, labour, taxes, transportation etc to complete.	nos	55	65.00	20.00	140.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

SL. no	Description of Item	Unit	Quantity				Rate			Amount														
			SMCH	FAAMCH	LMCH	Total Quantity	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	SMCH			FAAMCH			LMCH			Total					
										INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)	INR (in Figures only)	JPY (in Figures only)	USD (in Figures only)			
1397	Supply and Fixing of Chair For Visitors Dimensions: 60.90 Lx 64.20 D x 98.20 H x 44.80 seat Ht. in CM Frame Tubular Stain less Steel High Density Polyurethane Foam combined with Premium Leatherette. Sturdy PU Soft Arms. Seat and back rest with comfort cushion Legs with Nylon heavy duty bushes Certificates: ISO 9001, BIS/ CE The above entire unit shall be manufactured as per specifications, Line Sketches & as per the approval of the Engineer-In-Charge. The rate including all material, labour, taxes, transportation etc to complete.	nos	10	8.00	10.00	28.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1398	Supply and Fixing of Attender stool Approx. size:- 300mm square 18G double bent top of MS Height 510mm. Framework of MS press bent 25mm x 25mm x 3mm angles and 'C' channe riveted to angles made from 18G. MS CRCA sheet superimposed press bent argon arc welded top made from 0.6mm thick 304 grade S.S. sheet riveted with MS Drive on MS. Top. Legs fitted with PVC angle shoe Certificates : Manufacturer should have ISO:900, notified CE/BIS The above entire unit shall be manufactured as per specifications, Line Sketches & as per the approval of the Engineer-In-Charge. The rate including all material, labour, taxes, transportation etc to complete.	nos	30	12.00	20.00	62.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
BILL OF QUANTITY (NURSE STATION)																								
1399	Supply and fixing of Nurse station table as per the drawing & detail. The whole structure is formed of 19mm thick ply finished with approved laminate. Table top is formed out of 19mm thick ply finished with laminate cladding on both sides. The Table to have twin level table top at 750mm & 1050mm level of approved laminte finish as per approval of the architect. The depth of table top at 750mm level is 500mm deep and table top at 1050 mm level is 600mm deep. below 750mm to be provided with openable storages Counter top to be formed out of 19mm thick ply finished with approved laminate The table to have a 1 no of fully extendable drawer pedestal unit at every 2m intervals on ball bearing drawer guides and finished with laminate of approved colour and shade as per details. Drawer to be complete with hardware installed as directed to consist of the following: 1 no multi purpose lock as specified,100mm SS handle, keyboard tray, Space for CPU unit etc complete as per details and Architeet's approval.All internal surfaces to be finished with 0.8mm thick balancing laminate of approved shade. Cost to include Borer/Antitermite treatment for wood/plywood Hardware: All hardware shall be as per the approved model/make mentioned in finishing schedule. The above entire unit shall be manufactured as per specifications, Line Sketches & as per the approval of the Engineer-In-Charge.	metre	155	145.00	220.00	520.00				-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
The rate including all material, labour, taxes, transportation etc to complete.																								
Total Bill no-8 Allied works																								
										-	-	-	-	-	-	-	-	-	-	-	-	-		

LIST OF APPROVED MAKES FOR MEDICAL GAS PIPELINE SYSTEM

S.No.	Item Description	List of Makes
1.	Medical Grade Copper Pipe	SAB INDIA/HELIX INDIA/AMBA MEDI NEX / Mex flow / Metal Gem / Cubex / Janya/ or Equivalent
2.	Gas Outlet Points/Terminal Unit	SAB INDIA/HELIX INDIA/AMBA MEDI NEX /Nippon Engineering Company/MDD Medical system/MPS/Medfeshe/ Tri-Tech (USA) / Reanimed (Turkey) / Allied (USA) / Pneumatech or Equivalent
3.	Matching Probe/adopter	SAB INDIA/HELIX INDIA/AMBA MEDI NEX /Nippon Engineering Company/MDD Medical system/MPS/Medfeshe/ Tri-Tech (USA) / Reanimed (Turkey) / Allied (USA) or Equivalent
4.	Area Valve Box	SAB INDIA/HELIX INDIA/AMBA MEDI NEX /Nippon Engineering Company/MDD Medical system/MPS/Medfeshe/ Tri-Tech (USA) / Reanimed (Turkey) / Allied (USA) Wika or Equivalent
5.	Medical Gas Alarm	SAB INDIA/HELIX INDIA/AMBA MEDI NEX /Nippon Engineering Company/MDD Medical system/MPS/Medfeshe/ Tri-Tech (USA) / Reanimed (Turkey) / Allied (USA) Amico or Equivalent
6.	Fully Automatic Oxygen Control System	SAB INDIA/HELIX INDIA/AMBA MEDI NEX /Nippon Engineering Company/MDD Medical system/MPS/Medfeshe/ Tri-Tech (USA) / Reanimed (Turkey) / Allied (USA), Pneumatech or Equivalent
7.	Oxygen Manifold	SAB INDIA/HELIX INDIA/AMBA MEDI NEX /Nippon Engineering Company/MDD Medical system/MPS/Medfeshe/ Tri-Tech (USA) / Reanimed (Turkey) / Allied (USA) or Equivalent

8.	Emergency Oxygen Supply System	SAB INDIA/HELIX INDIA/AMBA MEDI NEX /Nippon Engineering Company/MDD Medical system/MPS/Medfeshe/ Tri-Tech (USA) / Reanimed (Turkey) / Allied (USA) or Equivalent
9.	Oxygen Flow meter with Humidifier Bottle	SAB INDIA/HELIX INDIA/AMBA MEDI NEX /Nippon Engineering Company/MDD Medical system/MPS/Medfeshe / Tri-Tech (USA) / Reanimed (Turkey) / Allied (USA) or Equivalent
10.	Ward Vacuum Units	SAB INDIA/HELIX INDIA/AMBA MEDI NEX /Nippon Engineering Company/MDD Medical system/MPS/Medfeshe/ AMICO/ Tri-Tech (USA) / Reanimed (Turkey) / Allied (USA) or Equivalent
11.	Nitrous Oxide Manifold	SAB INDIA/HELIX INDIA/AMBA MEDI NEX /Nippon Engineering Company/MDD Medical system/MPS/Medfeshe/ Pneumatech/ Tri-Tech (USA) / Reanimed (Turkey) / Allied (USA) or Equivalent
12.	Emergency Nitrous Oxide Supply System	SAB INDIA/HELIX INDIA/AMBA MEDI NEX /Nippon Engineering Company/MDD Medical system/MPS/Medfeshe/ Pneumatech/ Tri-Tech (USA) / Reanimed (Turkey) / Allied (USA) or Equivalent
13.	Duplex Medical Vacuum Plant	SAB INDIA/HELIX INDIA/AMBA MEDI NEX /Nippon Engineering Company/MDD Medical system/MPS/Medfeshe/ Atlas Copco / Tri-Tech (USA) / Reanimed (Turkey) / Allied (USA) or Equivalent
14.	Bacterial Filter	SAB INDIA/HELIX INDIA/AMBA MEDI NEX /Nippon Engineering Company/MDD Medical system/MPS/Medfeshe/ Johnson & Johnson / Tri-Tech (USA) / Reanimed (Turkey) / Allied (USA) or Equivalent
15.	Receiver	SAB INDIA/HELIX INDIA/AMBA MEDI NEX /Nippon Engineering Company/MDD Medical system/MPS/Medfeshe/ Tri-Tech (USA) / Reanimed (Turkey) / Allied (USA) or Equivalent

16.	Triplex Medical Air Plant	SAB INDIA/HELIX INDIA/AMBA MEDI NEX /Nippon Engineering Company/MDD Medical system/MPS/Medfeshe / Pneumatech / Tri-Tech (USA) / Reanimed (Turkey) / Allied (USA) or Equivalent
17.	Air Dryer	SAB INDIA/HELIX INDIA/AMBA MEDI NEX /Nippon Engineering Company/MDD Medical system/MPS/Medfeshe/ Atlas Copco / Tri-Tech (USA) / Reanimed (Turkey) / Allied (USA) or Equivalent
18.	4Stage Air Filtration	SAB INDIA/HELIX INDIA/AMBA MEDI NEX /Nippon Engineering Company/MDD Medical system/MPS/Medfeshe / Atlas Copco / Tri-Tech (USA) / Reanimed (Turkey) / Allied (USA) or Equivalent
19.	Pressure Reducing Station	SAB INDIA/HELIX INDIA/AMBA MEDI NEX /Nippon Engineering Company/MDD Medical system/MPS/Medfeshe / Atlas Copco / Tri-Tech (USA) / Reanimed (Turkey) / Allied (USA) or Equivalent
20.	Receiver of 3000liter	SAB INDIA/HELIX INDIA/AMBA MEDI NEX /Nippon Engineering Company/MDD Medical system/MPS/Medfeshe / Tri-Tech (USA) / Reanimed (Turkey) / Allied (USA) or Equivalent
21.	Lockable line Medical valves	SAB INDIA/HELIX INDIA/AMBA MEDI NEX /Nippon Engineering Company/MDD Medical system/MPS/Medfeshe / Wika /Tri-Tech (USA) / Reanimed (Turkey) / Allied (USA) or Equivalent
22.	Horizontal/Vertical Bed Head Panel	SAB INDIA/HELIX INDIA/AMBA MEDI NEX /Nippon Engineering Company/MDD Medical system/MPS/Medfeshe/ / Tri-Tech (USA) / Reanimed (Turkey) / Allied (USA) or Equivalent
23.	Anesthesia Gas Scavenging System (AGSS) Plant (Simplex) 520lpm	SAB INDIA/HELIX INDIA/AMBA MEDI NEX / RB/RN/SIM/AUDCO/MEDILINE or Equivalent